# **Main Electrical Components for Novaroute** Single Immersed Tube Highway Tunnel Option tunnel= 20300 m Number of tunnels=

Length of each tunnel= Tunnel width= 9.5

ltem	Component	Unit	Qty	Unit Cost	Total Cost	
	Lighting			I		
	Threshold + transition (1st 700m)	m2	7280	315	2293200	Lighting costed elsewhere.
	Interior (balance)	m2	186200	120.00	22344000	
			Lightin	g subtotal	0	
	Substations, generate		_			
	Substations	Ea	2	1337000	2674000	
	Emergency generator	Ea	1	955000	955000	
	UPS (Battery system)	Ea	1	573000	573000	
	Substa	tions, gene	erators, UP	S subtotal	4202000	
	CCTV system					
	Cameras (every 60m)	Each	338	3100	1047800	
	Control station	Each	1	30000	30000	
	•		CTV syste		1077800	
	Provide power for gas	detection	ventilation	n etc.	ı	
	Power provision	m	20300	45	913500	
	T		Powe	er subtotal	913500	
	Lane control system		I	I	I	
	Fibre optic display (every 200m)	Each	101	12500	0	
		Lane coi	ntrol syster	m subtotal	0	

Total Electrical 6193300


### Initialisation

Project: Newfoundland Fixed Link Pre-feasibility Study

Section: North Approach
Option: IT Highway Tunnel

Date: 8-Jun-04

Calculations by: ANW



- Total length= 306.6667 m
- Total Cost=\$ 5.5 M


- + sloping same way as track/road
- sloping against track/road

Newfoundland Fixed Link Pre-feasibility Study	Date:	8-Jun-04
North Approach	Calculations by:	ANW
IT Highway Tunnel		

## UNIT RATES

## **Materials**


Item	unit	Rate
excavation	m3	60
concrete	m3	190
rebar	tonnes	1600
formwork/falsework	m2	140
SP&L<=4.6m deep	m2	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=6.7m>	m2	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0</td></sp&l<=10.6m>	m2	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=13.7m>	m2	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0</td></sp&l<=16.8m>	m2	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0</td></sp&l<=20.0m>	m2	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0</td></sp&l<=25m>	m2	0
backfill + compact	m3	40
surface reinstatement	m2	30



Newfoundland Fixed Link Pre-feasibility Study Date: 8-Jun-04 North Approach IT Highway Tunnel Calculated costs Calculations by: ANW Page 2 of 2

Item	Unit	Quantity	Rate	Cost
excavation	m3	6861.5	60	411689
concrete	m3	1242.276	190.0	236032.4
rebar	tonnes	149.1	1600	238517
formwork/falsework	m2	1023.04	140	143225.6
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>1072.1</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	1072.1	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	392.5333	30	11776


Total 1041240



Newfoundland Fixed Link Pre-feasibility Study North Approach IT Highway Tunnel Calculated costs Date: 8-Jun-04 Calculations by: ANW Page 2 of 2

Item	Unit	Quantity	Rate	Cost
excavation	m3	6139.2	60	368353.3
concrete	m3	1140.708	190.0	216734.5
rebar	tonnes	136.9	1600	219015.9
formwork/falsework	m2	910.1867	140	127426.1
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>959.3</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	959.3	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	392.5333	30	11776


Total 943305.9



Newfoundland Fixed Link Pre-feasibility Study Date: 8-Jun-04 North Approach IT Highway Tunnel Calculated costs Calculations by: ANW Page 2 of 2

Item	Unit	Quantity	Rate	Cost
excavation	m3	5332.3	60	319939.2
concrete	m3	954.5	190.0	181355
rebar	tonnes	114.5	1600	183264
formwork/falsework	m2	797.3333	140	111626.7
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>846.4</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	846.4	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	386.4	30	11592


Total 807776.9



Newfoundland Fixed Link Pre-feasibility Study North Approach IT Highway Tunnel Calculated costs Date: 8-Jun-04 Calculations by: ANW Page 2 of 2

Item	Unit	Quantity	Rate	Cost
excavation	m3	4621.3	60	277280.6
concrete	m3	864.2173	190.0	164201.3
rebar	tonnes	103.7	1600	165929.7
formwork/falsework	m2	684.48	140	95827.2
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>733.5</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	733.5	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	386.4	30	11592


Total 714830.9



Newfoundland Fixed Link Pre-feasibility Study North Approach IT Highway Tunnel Calculated costs Date: 8-Jun-04 Calculations by: ANW Page 2 of 2

Item	Unit	Quantity	Rate	Cost
excavation	m3	3868.2	60	232089.7
concrete	m3	731.7275	190.0	139028.2
rebar	tonnes	87.8	1600	140491.7
formwork/falsework	m2	571.6267	140	80027.73
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>620.7</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	620.7	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	382.2293	30	11466.88

Total 603104.2




Newfoundland Fixed Link Pre-feasibility Study Date: 8-Jun-04 North Approach IT Highway Tunnel Calculated costs

Calculations by: ANW Page 2 of 2

Item	Unit	Quantity	Rate	Cost
excavation	m3	3039.4	60	182365.3
concrete	m3	523.6824	190.0	99499.66
rebar	tonnes	62.8	1600	100547
formwork/falsework	m2	458.7733	140	64228.27
SP&L<=4.6m deep	m2	0.0	0	0
4 6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>507.8</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	507.8	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	367.08	30	11012.4


Total 457652.7



Newfoundland Fixed Link Pre-feasibility Study Date: 8-Jun-04 North Approach IT Highway Tunnel Calculated costs Calculations by: ANW Page 2 of 2

Item	Unit	Quantity	Rate	Cost
excavation	m3	2303.6	60	138213.7
concrete	m3	408.5156	190.0	77617.96
rebar	tonnes	49.0	1600	78434.99
formwork/falsework	m2	345.92	140	48428.8
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>395.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	395.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	357.696	30	10730.88


Total 353426.4



Newfoundland Fixed Link Pre-feasibility Study North Approach IT Highway Tunnel Calculated costs Date: 8-Jun-04 Calculations by: ANW Page 2 of 2

Item	Unit	Quantity	Rate	Cost
excavation	m3	1619.4	60	97166.72
concrete	m3	345.092	190.0	65567.48
rebar	tonnes	41.4	1600	66257.66
formwork/falsework	m2	233.0667	140	32629.33
SP&L<=4.6m deep	m2	282.1	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	352.0533	30	10561.6


Total 272182.8



Newfoundland Fixed Link Pre-feasibility Study Date: 8-Jun-04 North Approach IT Highway Tunnel Calculated costs Calculations by: ANW Page 2 of 2

Item	Unit	Quantity	Rate	Cost
excavation	m3	956.1	60	57365.61
concrete	m3	302.4334	190.0	57462.35
rebar	tonnes	36.3	1600	58067.22
formwork/falsework	m2	120.2133	140	16829.87
SP&L<=4.6m deep	m2	169.3	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	346.4107	30	10392.32

Total 200117.4



Newfoundland Fixed Link Pre-feasibility Study Date: 8-Jun-04 North Approach IT Highway Tunnel Calculated costs Calculations by: ANW Page 2 of 2

Item	Unit	Quantity	Rate	Cost
excavation	m3	318.8	60	19128.64
concrete	m3	285.844	190.0	54310.36
rebar	tonnes	34.3	1600	54882.05
formwork/falsework	m2	7.36	140	1030.4
SP&L<=4.6m deep	m2	56.4	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	346.5333	30	10396

Total 139747.4

Newfoundland Fixed Link Pre-feasibility Study Date: 8-Jun-04					
Newfoundland Fixed	LINK Pre-T			-04	
North Approach		Calc	ılations by: ANW		
IT Highway Tunnel					
Summary of Costs					
		Markup for adjacent	0 %		
		Markup for adjacent	70		
	Section	Cost			
	1	1041240			
	2	943305.9			
	3	807776.9			
	4	714830.9			
	5	603104.2			
	6	457652.7			
	7	353426.4			
	8	272182.8			
	9	200117.4			
	10	139747.4			
	Sub-total	5533384			
	Oub-total	0000004			

### Newfoundland Fixed Link Pre-feasibility Study Highway IT Tunnel - North Approach Tunnel Final Liner Cost Estimate

Tunnel length= 2375 m Liner cross section area= 17.20 m2

## Shift pattern

Shifts	Hours	Days
3	8	5

Advance rate= 20 m/day

Rebar ratio= 0.12 t/m3 of concrete

Concrete supply=\$ 135 /m3

Rebar supply=\$ 900 /t

Initial form set-up time= 4 weeks

#### **Durations**

Number of days= 139 days
Number of hours= 3330 hours
Number of weeks= 28 weeks

#### Labour

Crew size 20
Average labour rate \$ 47 /hour

Total labour cost=\$ 3,130,200

### **Equipment**

Form \$ 1000000
Weekly cost of other equipment \$ 15000 (see TED 2370)

Total equipment cost=\$ 1,416,250

### Materials Cost Summary

Concrete= 40850 m3 Labour 3,130,200
Rebar= 4902 Equipment 1,416,250

Materials 9,926,550

Concrete cost=\$ 5,514,750

Rebar cost=\$ 4,411,800

Total material cost=\$ 9,926,550

## Newfoundland Fixed Link Pre-feasibility Study Highway IT Tunnel - North Approach Tunnel Drill and Blast Cost Estimate

Drill & blast excavation @ \$ 300 /m3

Tunnel length= 2375 m

Tunnel excavated diameter= 10 m

Excavated volume= 186532.1 m3

Excavation cost=\$ 55,959,619

## Newfoundland Fixed Link Pre-feasibility Study Highway IT Tunnel - North Approach Cost Summary

D&B Excavation 55,959,619 Liner 14,473,000 Shaft 0 70,432,619

### Newfoundland Fixed Link Pre-feasibility Study Highway IT Tunnel - North Vent Adit Tunnel Final Liner Cost Estimate

Tunnel length= 1500 m Liner cross section area= 5.47 m2

### Shift pattern

Shifts	Hours	Days
3	8	5

Advance rate= 30 m/day

Rebar ratio= 0.12 t/m3 of concrete

Concrete supply=\$ 135 /m3

Rebar supply=\$ 900 /t

Initial form set-up time= 4 weeks

#### **Durations**

Number of days= 70 days
Number of hours= 1680 hours
Number of weeks= 14 weeks

#### Labour

Crew size 15
Average labour rate \$ 47 /hour

Total labour cost=\$ 1,184,400

### **Equipment**

Form \$ 1000000
Weekly cost of other equipment \$ 15000

Total equipment cost=\$ 1,210,000

#### **Materials**

## Cost Summary

(see TED 2370)

Concrete= 8199.5568 m3 Rebar= 983.94682

Concrete cost=\$ 1,106,940 Rebar cost=\$ 885,552

Total material cost=\$ 1,992,492

Labour 1,184,400
Equipment 1,210,000
Materials 1,992,492
Total 4,386,892

## Newfoundland Fixed Link Pre-feasibility Study Highway IT Tunnel - North Vent Adit Tunnel Drill and Blast Cost Estimate

Drill & blast excavation @ \$ 250 /m3

Tunnel length= 1500 m

Tunnel excavated diameter= 6.5 m

Excavated volume= 49774.6 m3

Excavation cost=\$ 12,443,652

## Newfoundland Fixed Link Pre-feasibility Study Highway IT Tunnel - North Vent Adit Shaft Tunnel Drill and Blast Cost Estimate

shaft excavated diameter=	5.5	m
depth=	70	m
shaft final diameter=	6.1	m

### From graph

unlined shaft cost=\$ 17000 /m

### Quantities

Concrete Base= 24 m3
Shotcrete= 121 m3
Rockbolts= 1210 m2
final cast in place liner= 383 m3

### **Direct Costs**

\$ - Cost shaft excavation etc. 70 17000 1190000 Concrete Base 24 3564 150 Shotcrete 121 500 60476 Rockbolts 1210 10 12095 liner 383 600 229588 (includes steel & forms)

Total Direct Cost= 1495722

## Newfoundland Fixed Link Pre-feasibility Study Highway IT Tunnel North Vent Adit

D&B Excavation 12,443,652 Liner 4,386,892 Shaft 1,495,722 18,326,267

### Initialisation


Project: Newfoundland Fixed Link Pre-feasibility Study

Section: South Approach

Option: Bored Highway Tunnel

Date: 8-Jun-04

Calculations by: ANW




- + sloping same way as track/road
- sloping against track/road

Date: 8-Jun-04	
Calculations by: ANW	

## **Materials**

Item	unit	Rate
excavation	m3	60
concrete	m3	190
rebar	tonnes	1600
formwork/falsework	m2	140
SP&L<=4.6m deep	m2	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=6.7m>	m2	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0</td></sp&l<=10.6m>	m2	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=13.7m>	m2	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0</td></sp&l<=16.8m>	m2	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0</td></sp&l<=20.0m>	m2	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0</td></sp&l<=25m>	m2	0
backfill + compact	m3	40
surface reinstatement	m2	30




Newfoundland Fixed Link Pre-feasibility Study Date: 8-Jun-04 South Approach Bored Highway Tunnel Calculated costs Calculations by: ANW


Page 2 of 2

Item	Unit	Quantity	Rate	Cost
excavation	m3	82080.0	60	4924800
concrete	m3	12899.25	190.0	2450858
rebar	tonnes	1547.9	1600	2476656
formwork/falsework	m2	12585	140	1761900
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	1920	30	57600


Total 11671814




Item	Unit	Quantity	Rate	Cost
excavation	m3	73440.0	60	4406400
concrete	m3	11684.25	190.0	2220008
rebar	tonnes	1402.1	1600	2243376
formwork/falsework	m2	11235	140	1572900
SP&L<=4.6m deep	m2	0.0	0	0
	m2	0.0	0	0
	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td colspan="2">0.0 0</td><td>0</td></sp&l<=16.8m>	m2	0.0 0		0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	1920	30	57600



Item	Unit	Quantity	Rate	Cost
excavation	m3	55687.5	60	3341250
concrete	m3	1356.75	190.0	257782.5
rebar	tonnes	162.8	1600	260496
formwork/falsework	m2	9885	140	1383900
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td rowspan="2">0</td><td rowspan="3">0 0</td></sp&l<=6.7m>	m2	0.0	0	0 0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td></sp&l<=10.6m>	m2	0.0		
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	
13.7 <sp&l<=16.8m deep<="" td=""><td colspan="2">deep m2 0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	deep m2 0.0		0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	1650	30	49500




Item	Unit	Quantity	Rate	Cost
excavation	m3	48262.5	60	2895750
concrete	m3	1356.75	190.0	257782.5
rebar	tonnes	162.8	1600	260496
formwork/falsework	m2	8535	140	1194900
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td rowspan="3">0 0</td></sp&l<=6.7m>	m2	0.0	0	0 0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	1650	30	49500




Page 2 of 2


ltem	Unit	Quantity	Rate	Cost
excavation	m3	40837.5	60	2450250
concrete	m3	1356.75	190.0	257782.5
rebar	tonnes	162.8	1600	260496
formwork/falsework	m2	7185	140	1005900
	m2	0.0	0	0
	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td rowspan="2">0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>7425.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	7425.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	1650	30	49500




Item	Unit	Quantity	Rate	Cost
excavation	m3	33412.5	60	2004750
concrete	m3	1356.75	190.0	257782.5
rebar	tonnes	162.8	1600	260496
formwork/falsework	m2	5835	140	816900
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td rowspan="2">0</td><td rowspan="2">0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td></sp&l<=10.6m>	m2	0.0		
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td colspan="2">0.0 0</td><td>0</td></sp&l<=13.7m>	m2	0.0 0		0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>6075.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	6075.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	1650	30	49500




Item	Unit	Quantity	Rate	Cost
excavation	m3	25987.5	60	1559250
concrete	m3	1356.75	190.0	257782.5
rebar	tonnes	162.8	1600	260496
formwork/falsework	m2	4485	140	627900
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td rowspan="3">0 0</td></sp&l<=13.7m>	m2	0.0	0	0 0
13.7 <sp&l<=16.8m deep<="" td=""><td rowspan="2"></td><td>4725.0</td><td rowspan="2">0</td></sp&l<=16.8m>		4725.0	0	
16.8 <sp&l<=20.0m deep<="" td=""><td>0.0</td></sp&l<=20.0m>		0.0		
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	1650	30	49500



Item	Unit	Quantity	Rate	Cost
excavation	m3	21262.5	21262.5 60	
concrete	m3	4056.75	190.0	770782.5
rebar	tonnes	486.8	1600	778896
formwork/falsework	m2	3135	140	438900
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>3375.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	3375.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	1890	30	56700



Item	Unit	Quantity	Rate	Cost
excavation	m3	11841.2	60	710471.3
concrete	m3	2060.438	190.0	391483.1
rebar	tonnes	247.3	1600	395604
formwork/falsework	m2	1785	140	249900
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>4.6<sp&l<=6.7m deep="" m2<="" td=""><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m></td></sp&l<=6.7m>	4.6 <sp&l<=6.7m deep="" m2<="" td=""><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>2025.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	2025.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td colspan="2">m2 0.0 0</td><td>0</td></sp&l<=13.7m>	m2	m2 0.0 0		0
13.7 <sp&l<=16.8m deep<="" td=""><td colspan="2">p m2 0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	p m2 0.0		0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	1754.25	30	52627.5



Page 2 of 2

Item	Unit	Quantity	Rate	Cost
excavation	m3	3813.8	60	228825
concrete	m3	1458	190.0	277020
rebar	tonnes	175.0	1600	279936
formwork/falsework	m2	435	140	60900
SP&L<=4.6m deep	m2	675.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	1695	30	50850

Total 897531

Date: 8-Jun-04

Newfoundland Fixed Link Pre-f South Approach Bored Highway Tunnel		Date: 8-Jun-04 ulations by: ANW			
Doled Highway Tullilei					
Summary of Costs	Markup for adjacent	0 %			
Section	<b>Cost</b> 11671814				
1 2	10500284				
3	5292929				
4	4658429				
5	4023929				
6 7	3389429 2754929				
8	3321029				
9	1800086				
10 Sub-total	897531 39536811				

## **Newfoundland Fixed Link Highway IT Option Tunnel Lighting Costs**

## Fraser River Project - 2x3 lane tunnels

For	1550	m length of Theo Van Kooten calculated the tunnel lighting cost as follows:

732	m of threshold lighting costs \$	661231.22	1260	lights		
818	m of interior lighting costs \$	73151.75	139	lights		
1550	m of nightime circuit costs \$	126767.31	241	lights		
1640	lights cost \$	117280.47 to	o instal			
1550	m of conduit costs	101424.99				
		1079855.74	*	2	= \$	2,159,711

# Prorating for Newfoundland - assuming \*50% for single lane tunnel for 20300 m length of tunnel

732	m of threshold lighting costs \$	661231.22	1260	lights		
19568	m of interior lighting costs \$	1749918.6	3326	lights		
20300	m of nightime circuit costs \$	1660242.83	3157	lights		
7743	lights cost \$	553721.15 to	o instal			
20300	m of conduit costs	1328340.19				
		5953454.03	*	0.5	= \$	2,976,727



## Newfoundland Fixed Link Pre-feasibility - Immersed Tube Highway Tunnel - Cost Summary

·		
ITEM	UNIT	
MOBILIZATION & DEMOBILIZATION	LS	7,536,834
FABRICATION FACILITIES LEASE	LS	52,309,783
TUNNEL ELEMENT FABRICATION	LS	927,970,027
TUNNEL ELEMENT FINISHES	LS	94,194,981
MARINE DREDGE & BACKFILL	LS	743,334,442
UNIT TRANSPORT, PLACEMENT & CLOSURE	LS	247,961,957
NORTH DRILL AND BLAST TUNNEL	LS	69,969,983
NORTH APPROACH STRUCTURES	LS	5,533,384
SOUTH APPROACH STRUCTURES	LS	39,536,811
NORTH VENTILATION ADIT	LS	18,149,867
SOUTH VENTILATION ADIT	LS	0
ROAD FINISHES	LS	3,170,000
TUNNEL DRAINAGE	LS	7,370,000
NORTH VEHICLE HOLDING AREA	LS	6,960,000
		· · ·
SOUTH VEHICLE HOLDING AREA	LS	4,260,000
UTILITY DIVERSIONS	LS	1,000,000
MONITORING	LS	1,000,000
<del> </del>	<del>  -</del>	
SUBTOTAL CIVIL	<del>  </del>	\$2,230,258,068
CIVIL CONTINGENCIES	1	
CIVIL CONTINGENCIES		
CONTINGENCY	40%	\$892,103,227
	<u> </u>	
TOTAL CIVIL		\$3,122,361,295
	MASSA	ND FINISHING WORK
VENTU ATION FOLIDMENT		\$6,000,000
VENTILATION EQUIPMENT	LS	
VENTILATION BUILDINGS x 2	LS	\$2,000,000
FIRE SUPPRESSION SYSTEM	LS	\$4,000,000
CONTROL CENTRE	LS	\$4,000,000
SIGNALLING	LS	\$0
LIGHTING	LS	\$2,976,727
CCTV SYSTEM	LS	\$1,077,800
GAS DETECTION	LS	\$913,500
SUBSTATION, GENERATORS, UPS	LS	\$4,202,000
CURTOTAL MOE AND FINIOUS		¢05 470 007
SUBTOTAL M&E AND FINISHING	+	\$25,170,027
CONTINGENCIES	20%	\$5,034,005
TOTAL M&E AND FINISHING		\$30,204,032
TOTAL CIVIL, M&E AND FINISHING	+	\$3,152,565,328
TO THE OWIE, MIGE AND I MICHING	+	ΨΟ, 10Σ,000,0Σ0
ALLOWANCES		
CONTRACTOR OU	450/	¢472 004 700
CONTRACTOR OH	15%	\$472,884,799
CONTRACTOR PROFIT	15%	\$472,884,799
CONSTRUCTION TOTAL	+	\$4,099,000,000
	PRE-CONSTR	UCTION AND SUPERVISION
FEASIBILITY STUDY	LS	\$11,000,000
ENVIRONMENTAL ASSESSMENT	LS	\$4,000,000
DESIGN	5%	\$204,950,000
CONSTRUCTION MANAGEMENT	10%	\$409,900,000
OWNERS COSTS	2%	\$81,980,000
PRE-CONSTRUCTION TOTAL	+	\$711,830,000
GRAND TOTAL		\$4,810,830,000



ltem .	Unit	Quantity	Rate	Total
General Details				
Tunnel Length	18,000	metres		
Tunnel Element Length	150	metres	No. Elements =	120
The cross sectionof the tunnel element varies across three ventilation	on zones.			
Zone 1 from stations 0 to 1+800, and 16+200 to 18+000	3,600	metres	24	elements
Zone 2 from stations 1+800 to 6+150, and 11+850 to 16+200	8,700	metres	58	elements
Zone 3 from stations 6+150 to 11+850	5,700	metres	38	elements
1 Miscellaneous				
Mobilisation/demobilisation @ 3% of subtotal structure cost	ls	1	\$5,547,109.65	\$5,547,110
Fabrication facility lease (2 facilities assumed @ 5.5 yrs each)	year	11	\$3,500,000.00	\$38,500,000
2 Tunnel Element Fabrication - Zone 1				
Concrete				
Structural grade 4,000 psi placed by pump - slab on grade	$m^3$	94,968	\$157.32	\$14,940,366
Structural grade 4,000 psi placed by pump - elevated slab	$m^3$	80,640	\$169.62	\$13,678,157
Structural grade 4,000 psi placed by pump - walls	$m^3$	58,572	\$175.31	\$10,268,257
External Protection Layer, 2,500 psi, placed by pump	$m^3$	10,746	\$153.34	\$1,647,792
Keyed control joints transverse (at 20m centres approx)	m	10,161	\$13.25	\$134,633
Keyed control joints longitudinal (2 total at base/wall junction)	m	7,200	\$13.25	\$95,400
Curing, sprayed membrane, internal surfaces only	m	210,600	\$1.32	\$277,992
Formwork				
Walls, multiple use forms	$m^2$	146,700	\$78.92	\$11,577,564
Elevated Slab, multiple use forms	$m^2$	61,920	\$74.27	\$4,598,798
Reinforcement: grade 60 high yield				
Wall & Slab reinforcing, 150 kg/m <sup>3</sup>	tonnes	35,127	\$1,501.87	\$52,756,187
Bending, cutting & splicing	tonnes	35,127	\$270.44	\$9,499,746
Waterproofing Membrane				
Steel skin plate, A36, 6 mm thick	tonnes	19,143	\$3,132.11	\$59,957,982
Shear connectors, 150 mm x 12 mm, including stud welding	each	812,880	\$0.10	\$81,288
Automated Welding	m	91,044	\$14.86	\$1,352,914
Tunnel Joints				
Structural Steel End Frames (2/element)				
Embedded steel beams, 180 kg/m	tonnes	480	\$2,709.04	\$1,300,339
Front plates, 20 mm thick	tonnes	216	\$3,132.11	\$676,536
Gina fabrication, installation	each	24	\$29,128.00	\$699,072
Omega fabrication, installation & testing	each	24	\$36,693.00	\$880,632
Joint concrete, shear keys, cover plates etc.	each	24	\$20,000.00	\$480,000
			Page Total	\$228,950,765

Page 2 of 7 11/25/04 9:11 AM



ltem	Unit	Quantity	Rate	Total
		Тоа	Brought Forward	\$228,950,765
Temporary Works Items (Per Element)				
Structural Steel Bulkheads (2/element)				
Support Columns, 250 kg/m	tonnes	936	\$2,709.04	\$2,535,661
Skin plate, 12 mm thick	tonnes	480	\$3,132.11	\$1,503,413
Plate siffening angle, 18 kg/m	tonnes	168	\$3,174.03	\$533,237
Embedded perimeter angle, 18 kg/m	tonnes	96	\$3,174.03	\$304,707
Welding	m	22,656	\$14.86	\$336,668
Field Welding Premium	m	22,656	\$40.06	\$907,599
Misc. Structural Steel				
Alignment & pulling brackets etc., 5 tonnes per element Ballast Tanks (2/element)	tonnes	120	\$3,132.11	\$375,853
Steel support columns, 100 kg/m	tonnes	672	\$2,709.04	\$1,820,475
Timber lagging, 150 mm deep	$m^2$	10,776	\$60.40	\$650,870
Membrane liner	$m^2$	10,776	\$27.84	\$300,004
3 Internal Structural & Civil Finish Works - Zone 1				
Ballast				
Road ballast concrete, 2,500 psi, placed by chute	m3	18,810	\$140.06	\$2,634,529
Road ballast reinforcement: welded wire fabric 6 x 6 x #4, 2.8kg/m <sup>2</sup>	$m^2$	25,200	\$9.36	\$235,872
Deduct in excess of 4.5 tonnes	tonne	66	-\$41.01	-\$2,707
Emergency corridor sand/cement mix for HVDC cables	m3	4,410	\$140.06	\$617,665
Precast Divider for Emergency Egress Corridor & Vent Duct				
Panel fabrication, 8" thick, incuding reinformcement & lifting points	$m^2$	50,490	\$196.98	\$9,945,520
Panel setting, based upon max panel weight of 6 tons.	each	3,600	\$285.70	\$1,028,520
Seal and caulk panels	m	14,400	\$5.48	\$78,912
Sprayed fireproofing for precast panels	$m^2$	50,490	\$20.77	\$1,048,677
Roadway Surfacing				
Surface treatment, prepare & clean surface	km	3.6	\$4,188.69	\$15,079
Bituminous surface course, 75 mm thick	m3	1,890	\$75.08	\$141,901
4 Tunnel Element Fabrication - Zone 2				
Concrete				
Structural grade 4,000 psi placed by pump - slab on grade	$m^3$	169,563	\$157.32	\$26,675,651
Structural grade 4,000 psi placed by pump - elevated slab	$m^3$	149,205	\$169.62	\$25,308,152
Structural grade 4,000 psi placed by pump - walls	$m^3$	106,401	\$175.31	\$18,653,159
External Protection Layer, 2,500 psi, placed by pump	$m^3$	20,384	\$153.34	\$3,125,698
Keyed control joints transverse (at 20m centres approx)	$m^2$	20,097	\$13.25	\$266,285
Keyed control joints longitudinal (2 total at base/wall junction)	m	17,400	\$13.25	\$230,550
Curing, sprayed membrane, internal surfaces only	m	337,125	\$1.32	\$445,005
			Page Total	\$328,667,722

Page 3 of 7 11/25/04 9:11 AM



ltem	Unit	Quantity	Rate	Total
		Тоа	l Brought Forward	\$328,667,722
Formwork				
Walls, multiple use forms	$m^2$	241,860	\$78.92	\$19,087,591
Elevated Slab, multiple use forms	$m^2$	117,885	\$74.27	\$8,755,319
Reinforcement: grade 60 high yield				
Wall & Slab reinforcing, 200 kg/m <sup>3</sup>	tonnes	85,034	\$1,501.87	\$127,709,713
Bending, cutting & splicing	tonnes	85,034	\$270.44	\$22,996,541
Waterproofing Membrane				
Steel skin plate, A36, 6 mm thick	tonnes	19,140	\$3,132.11	\$59,948,585
Shear connectors, 150 mm x 12 mm, including stud welding	each	1,642,560	\$0.10	\$164,256
Automated Welding	m	186,528	\$14.86	\$2,771,806
Tunnel Joints				
Structural Steel End Frames (2/element)				
Embedded steel beams, 180 kg/m	tonnes	986	\$2,709.04	\$2,671,113
Front plates, 20 mm thick	tonnes	464	\$3,132.11	\$1,453,299
Gina fabrication, installation	each	58	\$24,355.00	\$1,412,590
Omega fabrication, installation & testing	each	58	\$30,680.00	\$1,779,440
Joint concrete, shear keys, cover plates etc.	each	58	\$20,000.00	\$1,160,000
Temporary Works Items (Per Element)				
Structural Steel Bulkheads (2/element)				
Support Columns, 250 kg/m	tonnes	1,682	\$2,709.04	\$4,556,605
Skin plate, 12 mm thick	tonnes	870	\$3,132.11	\$2,724,936
Plate siffening angle, 18 kg/m	tonnes	348	\$3,174.03	\$1,104,562
Embedded perimeter angle, 18 kg/m	tonnes	116	\$3,174.03	\$368,187
Welding	m	77,024	\$14.86	\$1,144,577
Field Welding Premium	m	77,024	\$40.06	\$3,085,581
Misc. Structural Steel				
Alignment & pulling brackets etc., 5 tonnes per element	tonnes	290	\$3,132.11	\$908,312
Ballast Tanks (2/element)				
Steel support columns, 100 kg/m	tonnes	1,508	\$2,709.04	\$4,085,232
Timber lagging, 150 mm deep	$m^2$	24,360	\$60.40	\$1,471,344
Membrane liner	$m^2$	24,360	\$27.84	\$678,182
5 Internal Structural & Civil Finish Works - Zone 2				
Ballast				
Road ballast concrete, 2,500 psi, placed by chute	m3	36,540	\$140.06	\$5,117,792
Road ballast reinforcement: welded wire fabric 6 x 6 x #4, 2.8kg/m <sup>2</sup>	$m^2$	60,900	\$9.36	\$570,024
Deduct in excess of 4.5 tonnes	tonne	166	-\$41.01	-\$6,808
Emergency corridor sand/cement mix for HVDC cables	m3	10,658	\$140.06	\$1,492,689
			Page Total	\$605,879,194

Page 4 of 7 11/25/04 9:11 AM



Item	Unit	Quantity	Rate	Total
		Toa	l Brought Forward	\$605,879,194
Precast Divider for Emergency Egress Corridor				
Panel fabrication, 8" thick, incuding reinformcement & lifting points	$m^2$	137,460	\$196.98	\$27,076,871
Panel setting, based upon max panel weight of 6 tons.	each	13,050	\$285.70	\$3,728,385
Seal and caulk panels	m	52,200	\$5.48	\$286,056
Sprayed fireproofing for precast panels	$m^2$	167,040	\$20.77	\$3,469,421
Roadway Surfacing				
Surface treatment, prepare & clean surface	km	8.7	\$4,188.69	\$36,442
Bituminous surface course, 75 mm thick	m3	4,568	\$75.08	\$342,928
6 Tunnel Element Fabrication - Zone 3				
Concrete				
Structural grade 4,000 psi placed by pump - slab on grade	$m^3$	71,193	\$157.32	\$11,200,083
Structural grade 4,000 psi placed by pump - elevated slab	$m^3$	58,767	\$169.62	\$9,968,059
Structural grade 4,000 psi placed by pump - walls	$m^3$	55,475	\$175.31	\$9,725,366
External Protection Layer, 2,500 psi, placed by pump	$\mathbf{m}^3$	9,320	\$153.34	\$1,429,052
Keyed control joints transverse (at 20m centres approx)	$m^2$	10,616	\$13.25	\$140,665
Keyed control joints longitudinal (2 total at base/wall junction)	m	11,400	\$13.25	\$151,050
Curing, sprayed membrane, internal surfaces only	m	169,005	\$1.32	\$223,087
Formwork				
Walls, multiple use forms	$m^2$	152,190	\$78.92	\$12,010,835
Elevated Slab, multiple use forms	$m^2$	52,440	\$74.27	\$3,894,719
Reinforcement: grade 60 high yield				
Wall & Slab reinforcing, 150 kg/m <sup>3</sup>	tonnes	27,815	\$1,501.87	\$41,774,946
Bending, cutting & splicing	tonnes	27,815	\$270.44	\$7,522,366
Waterproofing Membrane				
Steel skin plate, A36, 6 mm thick	tonnes	9,975	\$3,132.11	\$31,242,797
Shear connectors, 150 mm x 12 mm, including stud welding	each	424,650	\$0.10	\$42,465
Automated Welding	m	99,465	\$14.86	\$1,478,050
Tunnel Joints				
Structural Steel End Frames (2/element)				
Embedded steel beams, 180 kg/m	tonnes	504	\$2,709.04	\$1,365,031
Front plates, 20 mm thick	tonnes	222	\$3,132.11	\$696,268
Gina fabrication, installation	each	38	\$19,221.00	\$730,398
Omega fabrication, installation & testing	each	38	\$24,213.00	\$920,094
Joint concrete, shear keys, cover plates etc.	each	38	\$20,000.00	\$760,000
			Page Total	\$776,094,627

Page 5 of 7 11/25/04 9:11 AM



ltem .	Unit	Quantity	Rate	Total
		Toa	al Brought Forward	\$776,094,627
Temporary Works Items (Per Element)				
Structural Steel Bulkheads (2/element)				
Support Columns, 250 kg/m	tonnes	749	\$2,709.04	\$2,027,987
Skin plate, 12 mm thick	tonnes	371	\$3,132.11	\$1,160,447
Plate siffening angle, 18 kg/m	tonnes	129	\$3,174.03	\$410,085
Embedded perimeter angle, 18 kg/m	tonnes	42	\$3,174.03	\$132,674
Welding	m	18,392	\$14.86	\$273,305
Field Welding Premium	m	18,392	\$40.06	\$736,784
Misc. Structural Steel				
Alignment & pulling brackets etc., 5 tonnes per element	tonnes	190	\$3,132.11	\$595,101
Ballast Tanks (2/element)				
Steel support columns, 100 kg/m	tonnes	836	\$2,709.04	\$2,264,757
Timber lagging, 150 mm deep	$m^2$	13,543	\$60.40	\$818,009
Membrane liner	$m^2$	13,543	\$27.84	\$377,043
7 Internal Structural & Civil Finish Works - Zone 3				
Ballast				
Road ballast concrete, 2,500 psi, placed by chute	m3	17,813	\$140.06	\$2,494,819
Road ballast reinforcement: welded wire fabric 6 x 6 x #4, 2.8kg/m <sup>2</sup>	$m^2$	39,900	\$9.36	\$373,464
Deduct in excess of 4.5 tonnes	tonne	107	-\$41.01	-\$4,388
Emergency corridor sand/cement mix for HVDC cables	m3	3,563	\$140.06	\$498,964
Precast Divider for Emergency Egress Corridor				
Panel fabrication, 8" thick, incuding reinformcement & lifting points	$m^2$	32,063	\$196.98	\$6,315,671
Panel setting, based upon max panel weight of 6 tons.	each	2,850	\$285.70	\$814,245
Seal and caulk panels	m	11,400	\$5.48	\$62,472
Sprayed fireproofing for precast panels	$m^2$	32,063	\$20.77	\$665,938
Roadway Surfacing				
Surface treatment, prepare & clean surface	km	5.7	\$4,188.69	\$23,876
Bituminous surface course, 75 mm thick	m3	2,993	\$75.08	\$224,677
	1110	2,000	Ψ. σ.σσ	Ψ22 1,01 1
8 Tunnel Transport & Placement				
Element Transport: tug rental etc.	each	120	\$500,000.00	\$60,000,000
Element placement: barge/pontoons,divers, survey etc.	each	120	\$1,000,000.00	\$120,000,000
Tunnel Closure				
Underwater joint completion	each	1	\$2,500,000.00	\$2,500,000
			Page Total	\$978,860,556


Page 6 of 7 11/25/04 9:11 AM



ltem .	Unit	Quantity	Rate	Total
		Тоа	al Brought Forward	\$978,860,556
9 Marine Operation				
Dredging				
Mobilization/Demobilzation per season, 6 seasons, 2 vessels	each	24	\$150,000.00	\$3,600,000
Stage 1 bulk dredging of material	m3	5,255,299	\$84.00	\$441,445,116
Stage 2 fine tolerance dredging & additional trench cleaning	m3	788,295	\$43.00	\$33,896,685
Foundation and Backfill				
Bedded sand foundation	m3	263,385	\$35.00	\$9,218,475
Selected locking fill	m3	298,955	\$35.00	\$10,463,425
Backfill	m3	416,616	\$35.00	\$14,581,560
Rock armor protection	m3	664,488	\$51.00	\$33,888,888
Subtotal Structure Cost				\$1,525,954,705
Tunnel MEP Systems	ls	10 % of structure cost		\$152,595,470
Rail Systems	ls	15 % of structure cost		\$228,893,206
Contingency on Tunnel Costs	ls	30% of subtotal structure	re cost	\$457,786,411
"Soft" Costs				
Engineers design & construction supervision fee	ls	10% of construction cos	st	\$236,522,979
Estimated Construction Cost				\$2,601,752,772
Estimated Construction Cost per linear metre				\$144,542

Page 7 of 7 11/25/04 9:11 AM


## Newfoundland Fixed Link Pre-feasibility Study South Vehicle Holding Area




### **Earthworks**



### **Surface**



### Buildings etc.



Total cost **4,260,000** 



## **Tunnel Estimating Database**

Version 2.6 Copyright Hatch Mott MacDonald, 2004

**Project:** Newfoundland Fixed Link Pre-feasibility Study

**Estimate Description:** Set-up TBM

**Tunnel Name:** Single Highway Bored **Construction Activity:** Erect TBM Only

**Tunnel Technique:** EPB TBM - Precast segmental

**Estimate Definition ID:** 

**Estimate Definition ID:** 

2631

Printed by: whit2782, 8/16/04 11:40:07 AM

**Project Number:** 213789

**Parent Estimate ID:** 1563

**Project Phase:** Conceptual

Geology Type:

Not Applicable

**Estimate Date:** May 31, 2004

**Tunnel Characteristics ID: 842** 

### **Tunnel Characteristics**

**Finished Diameter:** 11 m

### **Activity Details**

3 - 8 hour shifts x 7 days per week **Shift Arrangement** 

**Duration of Activity** 

4.5 Weeks

**Total Number of Shifts** 

94.5

Estimated by:

Checked by:

	Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Tota
Labor						
	Pit boss	52.29	\$/hr	756.00	1.00	39,53
	Tunnel miner	48.89	\$/hr	756.00	2.00	73,922
	Shaft bottom	48.44	\$/hr	756.00	3.00	109,862
	Tunnel fitter	49.34	\$/hr	756.00	1.00	37,30
	Tunnel electrician	49.34	\$/hr	756.00	1.00	37,30
	Shaft top	47.99	\$/hr	756.00	1.00	36,280
	Crane operator	49.34	\$/hr	756.00	2.00	74,602
	Surface laborer	47.99	\$/hr	756.00	1.00	36,28
	Equipment laborer	48.44	\$/hr	756.00	1.00	36,62
					13.00	\$481,701
Plant						
	Loco	5,000.00	\$/wk	4.50	1.00	22,50
	Muck cars & grout cars	1,900.00	\$/wk	4.50	6.00	51,30
	Flat cars	310.00	\$/wk	4.50	2.00	2,79
	Transformers & switchgear - LV	750.00	\$/wk	4.50	1.00	3,37
	Small tools	2,600.00	\$/wk	4.50	1.00	11,70
	Shaft crane	9,000.00	\$/wk	4.50	1.00	40,50
	Erection crane	10,000.00	\$/wk	4.50	1.00	45,00
	Compressors	950.00	\$/wk	4.50	1.00	4,27
	Generators	2,000.00	\$/wk	4.50	1.00	9,00
	Transformers & switchgear - HV	5,200.00	\$/wk	4.50	1.00	23,40
	Loaders	2,300.00	\$/wk	4.50	1.00	10,35
						\$224,190
Consun	nables					
	Electrical power	0.00	\$/kwh	756.00	300.00	
	Gas oil	0.00	\$/L	0.00	1.00	

Page 1 of 2

Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Lubrication materials	0.00	\$/wk	4.50	1.00	0
Filters etc.	0.00	\$/wk	4.50	1.00	0
Hydraulic oil	0.00	<b>\$</b> /L	0.00	1.00	0
Other consumables	0.00	\$/wk	4.50	1.00	0
N/ / 1					\$0
Materials					
Temporary materials	2,000.00	\$/wk	4.50	1.00	9,000
Thrust frame	5,000.00	\$/wk	4.50	1.00	22,500
					\$31,500
	Total Estimated Cost:				\$737,391

Estimate Definition ID: 2631

Printed by: whit2782, 8/16/04 11:40:08 AM

Page 2 of 2

Checked by:



## **Tunnel Estimating Database**

Version 2.6

Copyright Hatch Mott MacDonald, 2004

Project: Newfoundland Fixed Link Pre-feasibility Study

Tunnel drive **Estimate Description:** 

Single Highway Bored **Tunnel Name:** 

**Construction Activity:** TBM Tunneling

**Tunnel Technique:** EPB TBM - Precast segmental

**Estimate Definition ID:** 

**Project Number:** 213789

**Parent Estimate ID:** 1559

**Project Phase:** Conceptual

Geology Type: Not Applicable

**Estimate Date:** May 31, 2004

**Tunnel Characteristics ID: 842** 

### **Tunnel Characteristics**

19,991 m **Tunnel Length:** 

**Finished Diameter:** 11 m

Initial Support Type: Pre-cast concrete segments

**Initial Support Thickness:**  $0 \, \mathrm{m}$ 

**Final Lining Thickness:**  $0.55 \, \text{m}$ 

> **Grout Thickness:** 0.125 m

### **Theoretical Excavation Volumes**

**Total Neat Excavation:** 2,394,738 Cubic Metres

0 Cubic Metres **Initial Lining Volume:** 

398,959 Cubic Metres Final Lining Volume:

**Theoretical Grout Volume:** 95,972 Cubic Metres

### Normal Excavation/Support Cycle

1.5 Metres **Excavation Cycle Length:** 

> 28 Minutes Excavate: 36 Minutes **Erect Support: Extend Services:** 0 Minutes

**Total Cycle Time:** 64 Minutes **Difficult Excavation/Support Cycle** 

1400 Metres Length of Difficult Excavation:

> **Excavate:** 92 Minutes **Erect Support:** 74 Minutes

**Extend Services:** 0 Minutes

**Total Cycle Time:** 166 Minutes

### **Reduction Factors**

Machine availability: 80 % Back up efficiency: 55 % 5 % Planned maintenance:

40 % Learning curve efficiency:

8 Weeks Learning curve duration time:

**Learning Curve Rate:** 

**Experienced Advance Rate:** 

14.1 m/day

m/day

5.6

**Difficult Advance Rate:** 5.4 m/day

### TBM Skidding Through Excavation

**Duration of skidding:** 

0 Weeks

Length of skidding:

0 Metres

Metres

### **Advance Rate and Shift Details**

**Shift Arrangement:** 3 - 8 hour shifts x 7 days per week

Avg. Drive Advance per Shift: 4.14 Metres 12 Metres Avg. Drive Advance per Day: Avg. Drive Advance per Week: 87 Metres 229.83 Weeks

**Duration of Tunneling (Incl. Skid):** 

Total number of shifts (Incl. Skid): 4,827 **Learning Curve Drive: Experienced Drive:** 

316 18,275 1,295

**Difficult Drive: Skidding Portion:**  1,400

0 0

Days

56

257

**Estimate Definition ID:** 

Printed by: whit2782, 8/16/04 11:40:41 AM

2632

Estimated by:

Page 1 of 3 Checked by:

	Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Labor						
	Pit boss	52.29	\$/hr	38,615.00	1.00	2,019,178
	Working foreman	52.29	\$/hr	38,615.00	2.00	4,038,357
	Tunnel miner	48.89	\$/hr	38,615.00	3.00	5,663,662
	Tunnel laborer	48.44	\$/hr	38,615.00	4.00	7,482,042
	Loco driver	49.34	\$/hr	38,615.00	4.00	7,621,056
	Shaft bottom	48.44	\$/hr	38,615.00	1.00	1,870,511
	TBM operator	49.34	\$/hr	38,615.00	1.00	1,905,264
	Tunnel fitter	49.34	\$/hr	38,615.00	1.00	1,905,264
	Tunnel electrician	49.34	\$/hr	38,615.00	1.00	1,905,264
	Shaft top	47.99	\$/hr	38,615.00	2.00	3,706,268
	Crane operator	49.34	\$/hr	38,615.00	1.00	1,905,264
	Surface laborer	47.99	\$/hr	38,615.00	4.00	7,412,535
	Equipment laborer	48.44	\$/hr	38,615.00	4.00	7,482,042
DI 4					29.00	\$54,916,708
Plant	TBM	300,000.00	\$/m2	119.79	0.80	28,749,600
	TBM backup	1,430,000.00		1.00	1.00	1,430,000
	Loco	5,000.00		229.83	4.00	4,596,600
	Muck cars & grout cars	1,900.00		229.83	56.00	24,453,912
	Flat cars	310.00		229.83	8.00	569,978
	Manriders	310.00		229.83	2.00	142,495
	Track	130.00		19,991.00	1.00	2,598,830
	Air pipe	30.00		19,991.00	1.00	599,730
	Water pipe	25.00		19,991.00	1.00	499,775
	Pump main	50.00		19,991.00	1.00	999,550
	Cabling	80.00		19,991.00	1.00	1,599,280
	Lighting	30.00		19,991.00	1.00	599,730
	Vent ducting	30.00		19,991.00	1.00	599,730
	Grout mixers	7,100.00		229.83	1.00	1,631,793
	Grout pumps	3,400.00		229.83	1.00	781,422
	Grout hoses & pipes	196.00		229.83	2.00	90,093
	Transformers & switchgear - LV	750.00		229.83	2.00	344,745
	Small tools	2,600.00		229.83	1.00	597,558
	Shaft crane	9,000.00		229.83	1.00	2,068,470
	Compressors	950.00		229.83	1.00	218,339
	Low pressure C/A system	3,800.00		229.83	1.00	873,354
	Pipework and controls	655.00		229.83	2.00	301,077
	Generators	2,000.00		229.83	1.00	459,660
	Transformers & switchgear - HV	5,200.00		229.83	1.00	1,195,116
	Surface fans	800.00		229.83	2.00	367,728
	Loaders	2,300.00		229.83	2.00	1,057,218
	Other surface plant	2,600.00		229.83	1.00	597,558
Estimate	<b>Definition ID:</b> 2632			Estimated	by:	

Estimate Definition ID: 2632

Printed by: whit2782, 8/16/04 11:40:42 AM

Page 2 of 3

Checked by:

Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Tunnel C/A system	40,000.00	\$/wk	229.83	1.00	9,193,200
					\$87,216,541
Consumables					
Electrical power	0.10	\$/kwh	38,615.00	3,000.00	11,584,500
Gas oil	0.45	<b>\$</b> /L	48,000.00	1.00	21,600
Lubrication materials	90.00	\$/wk	229.83	1.00	20,685
TBM spares, cutters	250.00	\$/m	19,991.00	1.00	4,997,750
Filters etc.	300.00	\$/wk	229.83	1.00	68,949
Hydraulic oil	0.90	<b>\$</b> /L	32,000.00	1.00	28,800
Other consumables	160.00	\$/wk	229.83	1.00	36,773
Tail seal grease	100.00	\$/m	19,991.00	1.00	1,999,100
					\$18,758,157
Materials					
Concrete lining rings	13,211.47	\$/Nr	13,328.00	1.00	176,082,407
Gaskets	110.00	\$/m	19,991.00	1.00	2,199,010
Bolts	12.00	\$/Nr	1,765.00	30.00	635,400
Grout	145.00	\$/m3	95,972.00	1.00	13,915,940
Grout plugs	0.50	\$/Nr	1,765.00	7.00	6,178
Packers	10.00	\$/Nr	3,633.00	12.00	435,960
Temporary materials	2,250.00	\$/wk	229.83	1.00	517,118
Other materials	0.00	<b>\$</b> /t	0.00	1.00	0
					\$193,792,012
Subcontracts					
Soil disposal	20.00	\$/m3	2,394,738.00	1.50	71,842,140
					\$71,842,140
		7	Total Estimated Co	ost:	\$426,525,558
	To	otal Estim	ated Cost per Me	tre:	\$21,336
	T	otal Estin	ated Cost per We	ek:	\$1,855,833
	7	Total Estin	nated Cost per Sh	ift:	\$88,364

Estimate Definition ID: 2632

Printed by: whit2782, 8/16/04 11:40:42 AM

Page 3 of 3

Checked by:



## **Tunnel Estimating Database**

Version 2.6

Copyright Hatch Mott MacDonald, 2004

**Project:** Newfoundland Fixed Link Pre-feasibility Study

**Estimate Description:** Maintain TBM

Tunnel Name: Single Highway Bored
Construction Activity: TBM Maintenance

**Tunnel Technique:** EPB TBM - Precast segmental

**Estimate Definition ID:** 2633

**Project Number:** 213789

Parent Estimate ID: 1561

Project Phase: Conceptual

Geology Type: Not Applicable

Estimate Date: May 31, 2004

**Tunnel Characteristics ID: 842** 

### **Tunnel Characteristics**

Finished Diameter: 11 m

### **Activity Details**

**Shift Arrangement** 1 - 6 hour shifts x 1 days per week

**Duration of Activity** 229 Weeks

Total Number of Shifts 229

	Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Labor						
	Working foreman	52.29	\$/hr	1,374.00	1.50	107,770
	Loco driver	49.34	\$/hr	1,374.00	1.50	101,690
	Shaft bottom	48.44	\$/hr	1,374.00	1.50	99,835
	TBM operator	49.34	\$/hr	1,374.00	1.50	101,690
	Tunnel fitter	49.34	\$/hr	1,374.00	1.50	101,690
	Tunnel electrician	49.34	\$/hr	1,374.00	1.50	101,690
	Shaft top	47.99	\$/hr	1,374.00	1.50	98,907
	Surface laborer	47.99	\$/hr	1,374.00	1.50	98,907
					12.00	\$812,178
Consun	nables					
	Electrical power	0.10	\$/kwh	1,374.00	600.00	82,440
	Gas oil	0.45	<b>\$</b> /L	0.00	1.00	0
	Other consumables	0.00	\$/wk	229.00	1.00	0
						\$82,440
Materia	als					
	Temporary materials	200.00	\$/wk	229.00	1.00	45,800
	Other materials	0.00	<b>\$</b> /t	0.00	1.00	0
						\$45,800

**Total Estimated Cost:** \$940,418

Estimate Definition ID: 2633 Estimated by:

Printed by: whit2782, 8/16/04 11:41:08 AM Page 1 of 1 Checked by:



## **Tunnel Estimating Database**

Version 2.6

Copyright Hatch Mott MacDonald, 2004

**Project:** Newfoundland Fixed Link Pre-feasibility Study

**Estimate Description:** Clean tunnel

Tunnel Name: Single Highway Bored
Construction Activity: Tunnel Clean Up

**Tunnel Technique:** EPB TBM - Precast segmental

**Estimate Definition ID:** 2634

**Total Cycle Time** 

**Project Number:** 213789

Parent Estimate ID: 1562

Project Phase: Conceptual

Geology Type: Not Applicable

Estimate Date: May 21, 2004

**Tunnel Characteristics ID: 842** 

### **Tunnel Characteristics**

Tunnel Length: 19,991 m

Finished Diameter: 11 m (Circular Tunnels)

Excavated Cross Section: 0 m2 (Non-circular Tunnels)

Excavated Perimeter: 0 m (Non-circular Tunnels)

### Productivity Cycle Reduction Factors

Section Length30 MetresLearning Curve Efficiency:50 %Vent Line Removal Time120 MinutesBack Up Efficiency:80 %Track Removal Time60 MinutesLearning Curve Duration:1 Weeks

**Temp Lighting Removal Time** 60 Minutes

Clean Up Time 120 Minutes

360 Minutes

Shift Details

Shift Arrangement: 3 - 8 hour shifts x 7 days per week

Avg. Advance per Shift:31.45 MetresAvg. Advance per Week:661 Metres

**Total number of hours:** 5,086

### Clean Up Productivity Data

	Average Advance	<b>Drive Length</b>	<b>Drive Duration</b>			
Learning Curve Portion:	48.0 m/day	336 Metres	21 Shifts 7 Days 1.00 Week	s		
Experienced Drive Portion:	96.0 m/day	19,655 Metres	614 Shifts 205 Days 29.25 Week	s		
Total:	94.4 m/day	19,991 Metres	636 Shifts 212 Days 30.25 Week	s		

	Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Labor						
	Tunnel laborer	48.44	\$/hr	5,086.00	6.00	1,478,195
	Shaft bottom	48.44	\$/hr	5,086.00	1.00	246,366
	Shaft top	47.99	\$/hr	5,086.00	1.00	244,077
	Crane operator	49.34	\$/hr	5,086.00	1.00	250,943
					9.00	\$2,219,581
Plant						
	Transformers & switchgear - LV	750.00	\$/wk	30.25	1.00	22,688

Estimate Definition ID: 2634 Estimated by:

Printed by: whit2782, 8/16/04 11:41:37 AM Page 1 of 2 Checked by:

Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
2,600.00	\$/wk	30.25	1.00	78,650
9,000.00	\$/wk	30.25	1.00	272,250
950.00	\$/wk	30.25	1.00	28,738
2,260.00	\$/wk	30.25	1.00	68,365
2,600.00	\$/wk	30.25	1.00	78,650
500.00	\$/wk	30.25	1.00	15,125
				\$564,465
0.10	\$/kwh	5,086.00	200.00	101,720
				\$101,720
Total Estimated Cost: Total Estimated Cost per Metre: Total Estimated Cost per Week:			\$2,885,766	
			\$144	
			\$95,402	
Т	otal Estima	ited Cost per Sh	ift:	\$4,539
	2,600.00 9,000.00 950.00 2,260.00 500.00	Total Estimat Total Estima	Unit Rate         UOM         Quantity           2,600.00         \$/wk         30.25           9,000.00         \$/wk         30.25           950.00         \$/wk         30.25           2,260.00         \$/wk         30.25           2,600.00         \$/wk         30.25           500.00         \$/wk         30.25           Total Estimated Cost per Met           Total Estimated Cost per Met           Total Estimated Cost per We	Unit Rate         UOM         Quantity         Quantity           2,600.00         \$/wk         30.25         1.00           9,000.00         \$/wk         30.25         1.00           950.00         \$/wk         30.25         1.00           2,260.00         \$/wk         30.25         1.00           2,600.00         \$/wk         30.25         1.00           500.00         \$/wk         30.25         1.00    Total Estimated Cost:  Total Estimated Cost per Metre:

Estimate Definition ID: 2634

Printed by: whit2782, 8/16/04 11:41:38 AM

Page 2 of 2

Checked by:



## **Tunnel Estimating Database**

Version 2.6 Copyright Hatch Mott MacDonald, 2004

**Project:** Newfoundland Fixed Link Pre-feasibility Study

**Estimate Description:** Remove TBM

Tunnel Name: Single Highway Bored

Construction Activity: TBM Removal

Tunnel Technique: EPB TBM - Precast segmental

**Estimate Definition ID: 2635** 

**Finished Diameter:** 

**Project Number:** 213789

Parent Estimate ID: 1564

**Project Phase:** Preliminary

Geology Type:

Not Applicable

cology Type.

Not Applicable

Estimate Date: May 21, 2004

**Tunnel Characteristics ID: 842** 

### **Tunnel Characteristics**

11 m

### **Activity Details**

**Shift Arrangement** 3 - 8 hour shifts x 7 days per week

**Duration of Activity** 

2.2 Weeks

**Total Number of Shifts** 

46.2

Labor         Pit boss       52.29 \$/hr       370.00         Tunnel miner       48.89 \$/hr       370.00         Shaft bottom       48.44 \$/hr       370.00         Tunnel fitter       49.34 \$/hr       370.00         Tunnel electrician       49.34 \$/hr       370.00         Shaft top       47.99 \$/hr       370.00         Crane operator       49.34 \$/hr       370.00         Surface laborer       47.99 \$/hr       370.00         Equipment laborer       48.44 \$/hr       370.00         Plant         Loco       5,000.00 \$/wk       2.20	3.00 2.00	19,34 54,26
Tunnel miner 48.89 \$/hr 370.00   Shaft bottom 48.44 \$/hr 370.00   Tunnel fitter 49.34 \$/hr 370.00   Tunnel electrician 49.34 \$/hr 370.00   Shaft top 47.99 \$/hr 370.00   Crane operator 49.34 \$/hr 370.00   Surface laborer 47.99 \$/hr 370.00   Equipment laborer 48.44 \$/hr 370.00   Plant	3.00 2.00	54,26
Shaft bottom       48.44 \$/hr       370.00         Tunnel fitter       49.34 \$/hr       370.00         Tunnel electrician       49.34 \$/hr       370.00         Shaft top       47.99 \$/hr       370.00         Crane operator       49.34 \$/hr       370.00         Surface laborer       47.99 \$/hr       370.00         Equipment laborer       48.44 \$/hr       370.00          Plant	2.00	
Tunnel fitter 49.34 \$/hr 370.00 Tunnel electrician 49.34 \$/hr 370.00 Shaft top 47.99 \$/hr 370.00 Crane operator 49.34 \$/hr 370.00 Surface laborer 47.99 \$/hr 370.00 Equipment laborer 48.44 \$/hr 370.00  Plant		
Tunnel electrician 49.34 \$/hr 370.00   Shaft top 47.99 \$/hr 370.00   Crane operator 49.34 \$/hr 370.00   Surface laborer 47.99 \$/hr 370.00   Equipment laborer 48.44 \$/hr 370.00   Plant	1.00	35,84
Shaft top 47.99 \$/hr 370.00 Crane operator 49.34 \$/hr 370.00 Surface laborer 47.99 \$/hr 370.00 Equipment laborer 48.44 \$/hr 370.00 Plant		18,25
Crane operator 49.34 \$/hr 370.00 Surface laborer 47.99 \$/hr 370.00 Equipment laborer 48.44 \$/hr 370.00  Plant	1.00	18,25
Surface laborer 47.99 \$/hr 370.00 Equipment laborer 48.44 \$/hr 370.00  Plant	2.00	35,51
Equipment laborer 48.44 \$/hr 370.00	2.00	36,51
Plant	2.00	35,51
	1.00	17,92
	15.00	\$271,432
Loco 5,000.00 \$/wk 2.20		
	1.00	11,00
Muck cars & grout cars 1,900.00 \$/wk 2.20	6.00	25,08
Flat cars 310.00 \$/wk 2.20	4.00	2,72
Manriders 310.00 \$/wk 2.20	1.00	68
Booster fans 800.00 \$/wk 2.20	1.00	1,76
Transformers & switchgear - LV 750.00 \$/wk 2.20	1.00	1,65
Other plant 1,400.00 \$/wk 2.20	1.00	3,08
Man hoists 2,000.00 \$/wk 2.20	1.00	4,40
Shaft crane 9,000.00 \$/wk 2.20	1.00	19,80
50T Crane 3,000.00 \$/wk 2.20	1.00	6,60
TBM Crane 15,000.00 \$/wk 2.20	1.00	33,00
Compressors 950.00 \$/wk 2.20	1.00	2,09
Transformers & switchgear - HV 5,200.00 \$/wk 2.20	1.00	11,44
Surface fans 800.00 \$/wk 2.20	1.00	1,76
	1.00	1,70

Estimate Definition ID: 2635 Estimated by:

Printed by: whit2782, 8/16/04 11:42:02 AM Page 1 of 2 Checked by:

Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Consumables					
Electrical power	0.00	\$/kwh	370.00	600.00	0
Gas oil	0.40	\$/L	15.00	1,000.00	6,000
Lubrication materials	0.00	\$/wk	2.20	1.00	0
Filters etc.	0.00	\$/wk	2.20	1.00	0
Hydraulic oil	0.00	<b>\$</b> /L	0.00	1.00	0
Other consumables	500.00	\$/wk	2.20	1.00	1,100
					\$7,100
Materials					
Temporary materials	500.00	\$/wk	2.20	1.00	1,100
Thrust frame	0.00	\$/wk	2.20	1.00	0
					\$1,100
<b>General Supplies</b>					
Small tools	700.00	\$/wk	2.20	1.00	1,540
					\$1,540
		То	tal Estimated C	ost:	\$406,242

Estimate Definition ID: 2635 Estimated by:

Printed by: whit2782, 8/16/04 11:42:03 AM Page 2 of 2 Checked by:

### Initialisation

Project: Newfoundland Fixed Link Pre-feasibility Study

Section: North Approach

Option: Bored Highway Tunnel

Date: 8-Jun-04

Calculations by: ANW

Surface gradient 0.4 %

+ sloping same way as track/road

Track/Road Gradient 6 %

Ground elevation at portal 100 m

Bottom of slab elevation at portal 81.6 m

Total length= 328.5714 m

Total Cost=\$ 5.9 M


- sloping against track/road

Newfoundland Fixed Link Pre-feasibility Study	Date:	8-Jun-04
North Approach	Calculations by:	ANW
Bored Highway Tunnel		

## **UNIT RATES**

## **Materials**

Item	unit	Rate
excavation	m3	60
concrete	m3	190
rebar	tonnes	1600
formwork/falsework	m2	140
SP&L<=4.6m deep	m2	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=6.7m>	m2	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0</td></sp&l<=10.6m>	m2	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=13.7m>	m2	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0</td></sp&l<=16.8m>	m2	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0</td></sp&l<=20.0m>	m2	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0</td></sp&l<=25m>	m2	0
backfill + compact	m3	40
surface reinstatement	m2	30



Newfoundland Fixed Link Pre-feasibility Study


North Approach

Bored Highway Tunnel

Calculations by: ANW
Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	7351.6	60	441095.3
concrete	m3	1331.01	190.0	252891.9
rebar	tonnes	159.7	1600	255553.9
formwork/falsework	m2	1096.114	140	153456
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>1148.7</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	1148.7	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	420.5714	30	12617.14



Newfoundland Fixed Link Pre-feasibility Study


North Approach

Bored Highway Tunnel

Calculations by: ANW
Page 2 of 2


# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	6577.7	60	394664.2
concrete	m3	1222.187	190.0	232215.6
rebar	tonnes	146.7	1600	234659.9
formwork/falsework	m2	975.2	140	136528
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>1027.8</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	1027.8	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	420.5714	30	12617.14



Item	Unit	Quantity	Rate	Cost
excavation	m3	5713.2	60	342792
concrete	m3	1022.679	190.0	194308.9
rebar	tonnes	122.7	1600	196354.3
formwork/falsework	m2	854.2857	140	119600
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>906.9</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	906.9	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	414	30	12420


Total 865475.2



Page 2 of 2

Item	Unit	Quantity	Rate	Cost
excavation	m3	4951.4	60	297086.4
concrete	m3	925.9471	190.0	175930
rebar	tonnes	111.1	1600	177781.9
formwork/falsework	m2	733.3714	140	102672
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>785.9</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	785.9	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	414	30	12420

Total 765890.2




Newfoundland Fixed Link Pre-feasibility Study Date: 8-Jun-04 North Approach Bored Highway Tunnel Calculations by: ANW

Page 2 of 2


# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	4144.5	60	248667.5
concrete	m3	783.9938	190.0	148958.8
rebar	tonnes	94.1	1600	150526.8
formwork/falsework	m2	612.4571	140	85744
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>665.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	665.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	409.5314	30	12285.94




Item	Unit	Quantity	Rate	Cost
excavation	m3	3256.5	60	195391.4
concrete	m3	561.0883	190.0	106606.8
rebar	tonnes	67.3	1600	107729
formwork/falsework	m2	491.5429	140	68816
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>544.1</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	544.1	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	393.3	30	11799

Total 490342.2



Item	Unit	Quantity	Rate	Cost
excavation	m3	2468.1	60	148086.1
concrete	m3	437.6953	190.0	83162.1
rebar	tonnes	52.5	1600	84037.49
formwork/falsework	m2	370.6286	140	51888
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>423.2</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	423.2	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	383.2457	30	11497.37


Total 378671.1



Page 2 of 2


Item	Unit	Quantity	Rate	Cost
excavation	m3	1735.1	60	104107.2
concrete	m3	369.7414	190.0	70250.87
rebar	tonnes	44.4	1600	70990.35
formwork/falsework	m2	249.7143	140	34960
SP&L<=4.6m deep	m2	302.3	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	377.2	30	11316

Total 291624.4



Item	Unit	Quantity	Rate	Cost
excavation	m3	1024.4	60	61463.15
concrete	m3	324.0358	190.0	61566.81
rebar	tonnes	38.9	1600	62214.88
formwork/falsework	m2	128.8	140	18032
SP&L<=4.6m deep	m2	181.4	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	371.1543	30	11134.63

Total 214411.5



Item	Unit	Quantity	Rate	Cost
excavation	m3	341.6	60	20494.97
concrete	m3	306.2614	190.0	58189.67
rebar	tonnes	36.8	1600	58802.19
formwork/falsework	m2	7.885714	140	1104
SP&L<=4.6m deep	m2	60.5	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	371.2857	30	11138.57

Total 149729.4

Newfoundland Fixed Link Pre-feasibility Study Date: 8-Jun-04					
Newfoundiand Fixed Link Pre-	reasibility Study	Date: 8-Jun-04			
North Approach	Calc	ulations by: ANW			
Bored Highway Tunnel					
Summary of Costs					
,	Markup for adjacent	0 %			
	mamap isi dajassin	,,			
Saction	Coot				
Section					
1	1115614				
2	1010685				
3	865475.2				
4	765890.2				
5	646183				
6	490342.2				
7	378671.1				
8	291624.4				
9	214411.5				
10	149729.4				
Sub-total	5928626				

### Initialisation

Project: Newfoundland Fixed Link Pre-feasibility Study

Section: South Approach

Option: Bored Highway Tunnel

Date: 8-Jun-04

Calculations by: ANW

Surface gradient 0.55 %

+ sloping same way as track/road - sloping against track/road

Track/Road Gradient 6 %

Ground elevation at portal 100 m

Bottom of slab elevation at portal 81.6 m

Total length= 337.6147 m


Total Cost=\$ 6.1 M

Newfoundland Fixed Link Pre-feasibility Study	Date:	8-Jun-04
South Approach	Calculations by:	ANW
Bored Highway Tunnel		


## UNIT RATES

## **Materials**


Item	unit	Rate
excavation	m3	60
concrete	m3	190
rebar	tonnes	1600
formwork/falsework	m2	140
SP&L<=4.6m deep	m2	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=6.7m>	m2	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0</td></sp&l<=10.6m>	m2	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=13.7m>	m2	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0</td></sp&l<=16.8m>	m2	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0</td></sp&l<=20.0m>	m2	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0</td></sp&l<=25m>	m2	0
backfill + compact	m3	40
surface reinstatement	m2	30



Item	Unit	Quantity	Rate	Cost
excavation	m3	7553.9	60	453235.6
concrete	m3	1367.643	190.0	259852.2
rebar	tonnes	164.1	1600	262587.5
formwork/falsework	m2	1126.283	140	157679.6
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>1180.3</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	1180.3	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	432.1468	30	12964.4




Item	Unit	Quantity	Rate	Cost
excavation	m3	6758.8	60	405526.5
concrete	m3	1255.825	190.0	238606.8
rebar	tonnes	150.7	1600	241118.5
formwork/falsework	m2	1002.04	140	140285.7
SP&L<=4.6m deep	m2	0.0	0	0
4 6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>1056.1</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	1056.1	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	432.1468	30	12964.4




Item	Unit	Quantity	Rate	Cost
excavation	m3	5870.4	60	352226.6
concrete	m3	1050.826	190.0	199656.9
rebar	tonnes	126.1	1600	201758.5
formwork/falsework	m2	877.7982	140	122891.7
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>931.8</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	931.8	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	425.3945	30	12761.83

Total 889295.6




Item	Unit	Quantity	Rate	Cost
excavation	m3	5087.7	60	305263.1
concrete	m3	951.4319	190.0	180772.1
rebar	tonnes	114.2	1600	182674.9
formwork/falsework	m2	753.556	140	105497.8
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>807.6</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	807.6	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	425.3945	30	12761.83

Total 786969.8




Item	Unit	Quantity	Rate	Cost
excavation	m3	4258.5	60	255511.5
concrete	m3	805.5716	190.0	153058.6
rebar	tonnes	96.7	1600	154669.7
formwork/falsework	m2	629.3138	140	88103.93
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>683.3</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	683.3	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	420.8029	30	12624.09

Total 663967.9




Item	Unit	Quantity	Rate	Cost
excavation	m3	3346.2	60	200769.2
concrete	m3	576.5311	190.0	109540.9
rebar	tonnes	69.2	1600	110694
formwork/falsework	m2	505.0716	140	70710.02
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>559.1</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	559.1	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	404.1248	30	12123.74

Total 503837.8




Item	Unit	Quantity	Rate	Cost
excavation	m3	2536.0	60	152161.9
concrete	m3	449.7419	190.0	85450.96
rebar	tonnes	54.0	1600	86350.45
formwork/falsework	m2	380.8294	140	53316.11
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>434.8</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	434.8	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	393.7938	30	11813.81

Total 389093.2




ltem	Unit	Quantity	Rate	Cost
excavation	m3	1782.9	60	106972.5
concrete	m3	379.9178	190.0	72184.38
rebar	tonnes	45.6	1600	72944.22
formwork/falsework	m2	256.5872	140	35922.2
SP&L<=4.6m deep	m2	310.6	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	387.5817	30	11627.45

Total 299650.8



Item	Unit	Quantity	Rate	Cost
excavation	m3	1052.6	60	63154.8
concrete	m3	332.9542	190.0	63261.31
rebar	tonnes	40.0	1600	63927.22
formwork/falsework	m2	132.345	140	18528.29
SP&L<=4.6m deep	m2	186.4	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	381.3695	30	11441.09

Total 220312.7




Item	Unit	Quantity	Rate	Cost
excavation	m3	351.0	60	21059.05
concrete	m3	314.6906	190.0	59791.22
rebar	tonnes	37.8	1600	60420.6
formwork/falsework	m2	8.102752	140	1134.385
SP&L<=4.6m deep	m2	62.1	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	381.5046	30	11445.14


Total 153850.4

Newfoundland Fixed Li South Approach Bored Highway Tunnel	Newfoundland Fixed Link Pre-feasibility Study Date: 8-Jun-04 South Approach Calculations by: ANW Sored Highway Tunnel						
Borca riigiiway raiiiici							
Summary of Costs		Markup for adjacent	0	%			
\$	Section	Cost					
	1 2	1146319 1038502					
	3	889295.6					
	4	786969.8					
	5 6	663967.9 503837.8					
	7	389093.2					
	8 9	299650.8 220312.7					
	10	153850.4					
Sı	ub-total	6091799					

Newfoundland Fixed Link Pre-feasibility Study Cost Estimating Single Lane Bored Highway Tunnel Tunnel Structural Finishes Page 1 of 2

**Date:** June 07, 2004 **Calculation by:** A.White





**Assumed tunnel cross section** 

# Newfoundland Fixed Link Pre-feasibility Study Cost Estimating Single Lane Bored Highway Tunnel Tunnel Structural Finishes

Page 2 of 2

**Date:** June 07, 2004 **Calculation by:** A.White

# **Quantity Take-off**

Concrete					Concrete	Rebar
Element	Nr.	L(m)	b(m)	d(m)	Qty(m3)	Qty(m3)
1	1	20248	0.5	2.5	25310	3037.2
2	1	20248	9.4	0.5	95166	11419.9
3	1	20248	0.3	4.8	29157	3498.9
4	1	20248	7.5	0.5	75930	9111.6
5	1	20248	0.3	6.6	40091	4810.9
6	1	20248	2.1	0.3	12756	1530.7
					278410 m3	21989 t

# Formwork/falsework

Element	Nr.	L(m)	d(m)	Faces	Area(m2)
1	1	20248	2.5	2	101240
2	2	20248	8.5	1	172108
3	1	20248	4.8	1	97190.4
4	2	20248	7	1	141736
5	2	20248	6.6	2	267273.6
6	1	20248	2.1	1	42520.8
					822068.8 m2

# Rates

Concrete	m3	190
Formwork	m2	140
Reinforcement	t	1600

## Costs

Concrete	m3	278410 m3	at	190	=	52,897,900
Formwork	m2	822069 m2	at	140	=	115,089,632
Reinforcement	t	21989 t	at	1600	=	35,182,925
				\$		203,170,457

# Main Electrical Components for Novaroute Newfoundland Fixed Link

# Single TBM Bored Highway Tunnel Option

Length of each tunnel= 19991 m Number of tunnels= 1
Tunnel width= 9.5 m

ltem	Component	Unit	Qty	Unit Cost	Total Cost	
	Lighting					
	Threshold + transition (1st 700m)	m2	7280	315	2293200	Lighting costed elsewhere
	Interior (balance)	m2	183264.5	120.00	21991740	
			Lightin	g subtotal	0	
	Substations, generate	rs, UPS				
	Substations	Ea	2	1337000	2674000	
	Emergency generator	Ea	1	955000	955000	
	UPS (Battery system)	Ea	1	573000	573000	
	, , ,	tions, gene	erators, UP	S subtotal	4202000	
	CCTV system					
	Cameras (every 60m)	Each	333	3100	1032300	
	Control station	Each	1	30000	30000	
	•	C	CTV syste	m subtotal	1062300	<u>'</u>
	Provide power for gas	detection	, ventilatior	etc.		
	Power provision	m	19991	45	899595	
			Powe	er subtotal	899595	
	Lane control system				I	
	Fibre optic display (every 200m)	Each	99	12500	0	
		Lane col	ntrol syster	n subtotal	0	

Total Electrical 6163895

# Newfoundland Fixed Link Pre-feasibility Study TBM Bored Highway Tunnel Option Tunnel Lighting Costs

# Fraser River Project - 2x3 lane tunnels

For	1550	m length of Theo Van Kooten calculated the tunnel lighting cost as follows:	
-----	------	---	--

732	m of threshold lighting costs \$	661231.22	1260	lights		
818	m of interior lighting costs \$	73151.75	139	lights		
1550	m of nightime circuit costs \$	126767.31	241	lights		
1640	lights cost \$	117280.47 to	o instal			
1550	m of conduit costs	101424.99				
		1079855.74	*	2	= \$	2,159,711

# Prorating for Newfoundland - assuming \*50% for single lane tunnel

for	19991	m length of tunnel
-----	-------	--------------------

732	m of threshold lighting costs \$	661231.22	1260	lights		
19259	m of interior lighting costs \$	1722285.5	3273	lights		
19991	m of nightime circuit costs \$	1634971.16	3109	lights		
7642	lights cost \$	546498.39 to	o instal			
19991	m of conduit costs	1308120.63				
		5873106.91	*	0.5	= \$	2,936,553

# Newfoundland Fixed Link Pre-feasibility Study TBM Bored Highway Tunnel - North Vent Adit Tunnel Final Liner Cost Estimate

Tunnel length= 600 m Liner cross section area= 5.47 m2

# Shift pattern

Shifts	Hours	Days
3	8	5

Advance rate= 30 m/day

Rebar ratio= 0.12 t/m3 of concrete

Concrete supply=\$ 135 /m3

Rebar supply=\$ 900 /t

Initial form set-up time= 4 weeks

#### **Durations**

Number of days= 40 days
Number of hours= 960 hours
Number of weeks= 8 weeks

#### Labour

Crew size 15
Average labour rate \$ 47 /hour

Total labour cost=\$ 676,800

## **Equipment**

Form \$ 1000000
Weekly cost of other equipment \$ 15000 (see TED 2370)

Total equipment cost=\$ 1,120,000

## Materials Cost Summary

 Concrete=
 3279.8227 m3
 Labour 676,800


 Rebar=
 393.57873
 Equipment 1,120,000

 Materials 796,997
 Total 2,593,797


Concrete cost=\$ 442,776 Rebar cost=\$ 354,221

Total material cost=\$ 796,997

# Newfoundland Fixed Link Pre-feasibility Study TBM Bored Highway Tunnel - North Vent Adit Tunnel Drill and Blast Cost Estimate



# Newfoundland Fixed Link Pre-feasibility Study TBM Bored Highway Tunnel - North Vent Adit Shaft Tunnel Drill and Blast Cost Estimate



# From graph

unlined shaft cost=\$ 17000 /m

## Quantities

Concrete Base= 24 m3
Shotcrete= 173 m3
Rockbolts= 1728 m2
final cast in place liner= 547 m3

# **Direct Costs**

				\$ - Cost	
shaft excavation etc.	100	*	17000	1700000	
Concrete Base	24	*	150	3564	
Shotcrete	173	*	500	86394	
Rockbolts	1728	*	10	17279	
liner	547	*	600	327982	(includes steel & forms)
		Total D	Direct Cost=	2135219	<del>-</del>

# Newfoundland Fixed Link Pre-feasibility Study TBM Bored Highway Tunnel TBM Bored Option - North Vent Adit

D&B Excavation 4,977,461 Liner 2,593,797 Shaft 2,135,219 9,706,476

# Newfoundland Fixed Link Pre-feasibility Study TBM Bored Highway Tunnel - South Vent Adit Tunnel Final Liner Cost Estimate

Tunnel length= 2000 m Liner cross section area= 5.47 m2

# Shift pattern

Shifts	Hours	Days
3	8	5

Advance rate= 30 m/day

Rebar ratio= 0.12 t/m3 of concrete

Concrete supply=\$ 135 /m3

Rebar supply=\$ 900 /t

Initial form set-up time= 4 weeks

#### **Durations**

Number of days= 87 days
Number of hours= 2080 hours
Number of weeks= 17 weeks

#### Labour

Crew size 15
Average labour rate \$ 47 /hour

Total labour cost=\$ 1,466,400

## **Equipment**

Form \$ 1000000
Weekly cost of other equipment \$ 15000 (see TED 2370)

Total equipment cost=\$ 1,260,000

## Materials Cost Summary

1,180,736


Concrete= 10932.742 m3 Labour 1,466,400 Rebar= 1311.9291 Equipment 1,260,000

Materials 2,656,656
Concrete cost=\$ 1,475,920
Total 5,383,056


Total material cost=\$ 2,656,656

Rebar cost=\$

# Newfoundland Fixed Link Pre-feasibility Study TBM Bored Highway Tunnel - South Vent Adit Tunnel Drill and Blast Cost Estimate



# **Newfoundland Fixed Link Pre-feasibility Study TBM Bored Highway Tunnel - South Vent Adit Shaft Tunnel Drill and Blast Cost Estimate**



From graph

unlined shaft cost=\$ 17000

## Quantities

Concrete Base= 24 m3 Shotcrete= 0 m3 Rockbolts= 0 m2 final cast in place liner= 0 m3

# **Direct Costs**

\$ - Cost shaft excavation etc. 0 17000 0 3564 Concrete Base 24 150 Shotcrete 0 500 0 Rockbolts 0 10 0 liner 0 600 0 Total Direct Cost= 3564

(includes steel & forms

# Newfoundland Fixed Link Pre-feasibility Study TBM Bored Highway Tunnel TBM Bored Option - South Vent Adit


 **Newfoundland Fixed Link Pre-feasibility Study Tunnel Drainage Bored Highway Tunnel Drainage Costs** 

# Page 1 of 1

Calculation by: ANW

Date: Jun.08, 2004

# **Sump Sizing**



# **Piping**

300 Assume mm diameter steel pipe connecting each sump to the portal areas Number of pipes=

Assume sumps located at 1/3 and 2/3 of tunnel length

Total length of piping= 14300 m

## **Rates**

Sump construction-\$ 17795 /m of sump

Pipe-\$ 265 /m of pipe


Pipe installation labour -\$ 29 /m of pipe (assume 6 man crew installing 100m/day) Pipe installation equipment-\$ 10 /m of pipe (assume \$1000/day for equipment)

Pumps-\$ 125000 /pump


#### Costs

Item	Unit	Qty	Rate	\$-Cost
Sump construction	m	142	17795	2,526,890
Pipe	m	14300	265	3,789,500
Pipe installation	m	14300	29	411,840
Equipment	m	14300	10	143,000
Pumps	Nr	4	125000	500,000
			Total	7,371,230

# Newfoundland Fixed Link Pre-feasibility Study Highway Tunnel Options South Vehicle Holding Area



# **Earthworks**



Earthworks= 2,700,000

# **Surface**

Assume surface @ 20 /m2

Surface= 3,600,000

# Buildings etc.

Public facilities building @ 80000 See CJT estimate
Site maintenance building @ 220000 See CJT estimate
Fire engines @ 360000 See CJT estimate

Total cost **6,960,000** 



Newfoundland Fixed Link Pre-feasibility - TBM Bored Highway Tunnel - Cost Summary


	──   BORED TUNNE	L CONSTRUCTION COSTS
ITEM	UNIT	MAIN TUNNEL
MOBILIZATION & DEMOBILIZATION	LS	8,000,000
TUNNELLING	LS	429,709,000
TUNNEL FINISHES	LS	203,170,000
NORTH APPROACH STRUCTURES	LS	5,920,000
SOUTH APPROACH STRUCTURES	LS	6,090,000
NORTH VENTILATION ADIT	LS	9,706,476
SOUTH VENTILATION ADIT	LS	21,978,156
ROAD FINISHES	LS	2,581,875
NORTH VEHICLE HOLDING AREA	LS	6,960,000
SOUTH VEHICLE HOLDING AREA	LS	4,260,000
TUNNEL DRAINAGE	LS	7,370,000
UTILITY DIVERSIONS	LS	1,000,000
MONITORING	LS	1,000,000
MONTONING	10	1,000,000
SUBTOTAL CIVIL		\$707,745,508
SOBTOTAL CIVIL		ψ1 01 <sub>3</sub> 1 40,000
CIVIL CONTINGENCIES		
STATE CONTINUE NOISE		
CONTINGENCY	40%	\$283,098,203
TOTAL MOLITO	70/0	ψ200 <sub>1</sub> 000 <sub>1</sub> 200
TOTAL CIVIL		\$990,843,711
TO THE STATE		400010101111
	M&E AN	D FINISHING WORK
VENTILATION EQUIPMENT	LS	\$6,000,000
VENTILATION BUILDINGS x 2	LS	\$2,000,000
FIRE SUPPRESSION SYSTEM	LS	\$4,000,000
CONTROL CENTRE	LS	\$4,000,000
SIGNALLING	LS	\$0
LIGHTING	LS	\$2,936,553
CCTV SYSTEM	LS	\$30,000
GAS DETECTION	LS	\$890,000
SUBSTATION, GENERATORS, UPS	LS	\$570,000
SUBTOTAL M&E AND FINISHING		\$20,426,553
CONTINGENCIES	20%	\$4,085,311
TOTAL M&E AND FINISHING		\$24,511,864
TOTAL CIVIL, M&E AND FINISHING		\$1,015,355,575
ALLOWANCES		
		<u> </u>
CONTRACTOR OH	15%	\$152,303,336
CONTRACTOR PROFIT	15%	\$152,303,336
		<u> </u>
CONSTRUCTION TOTAL		\$1,320,000,000
		CTION AND SUPERVISION
FEASIBILITY STUDY	LS	\$11,000,000
ENVIRONMENTAL ASSESSMENT	LS 5%	\$4,000,000 \$66,000,000
DESIGN CONSTRUCTION MANAGEMENT	10%	\$66,000,000 \$132,000,000
OWNERS COSTS	2%	\$26,400,000
PRE-CONSTRUCTION TOTAL		\$239,400,000
GRAND TOTAL		\$1,559,400,000

Hatch Mott MacDonald	Newfoundland Fixed Link Pre-feasibility - TBM Bored Highway Tunnel Civil Costs					
ITEM	UNIT	QTY	RATE	TOTAL		
MOBILIZATION	LS	1.00	\$8,000,000	\$8,000,000		
TUNNELLING						
- Set-up TBM	LS	1.00	\$723,000	\$723,000		
- Tunnel drive	LS	1.00	\$424,854,000	\$424,854,000		
- TBM maintenance	LS	1.00	\$916,000	\$916,000		
- Remove TBM	LS	1.00	\$398,000	\$398,000		
- Clean tunnel	LS	1.00	\$2,818,000	\$2,818,000		
- Structural finishes	LS	1.00	\$203,170,000	\$203,170,000		
NORTH APPROACH STRUCTURES						
- cut and cover approach	LS	1.00	\$5,920,000	\$5,920,000		
SOUTH APPROACH STRUCTURES						
- cut and cover approach	LS	1.00	\$6,090,000	\$6,090,000		
END VENTILATION ADITS						
- south adit	LS	1.00	\$21,978,156	\$21,978,156		
- north adit	LS	1.00	\$9,706,476	\$9,706,476		
DRAINAGE						
Drainage sumps and piping	LS	1.00	\$7,370,000	\$7,370,000		
ROAD FINISHES						
- bored tunnel	m2	124,943.75	\$20	\$2,498,875		
- north approach	m2	2,075.00	\$20	\$41,000		
- south approach	m2	2,100.00	\$20	\$42,000		

\$694,525,508

SUB-TOTAL


# Newfoundland Fixed Link Pre-feasibility Study Drill & Blast Highway Tunnel - South Vehicle Holding Area



## **Earthworks**



#### **Surface**



# Buildings etc.



Total cost **4,260,000** 

# Newfoundland Fixed Link Pre-feasibility Study Drill and Blast Highway Tunnel - Zones 1, 3, and 5 Tunnel Final Liner Cost Estimate

Tunnel length= 6500 m Liner cross section area= 15 m2

# Shift pattern

Shifts	Hours	Days
3	8	5

Advance rate= 10 m/day

Rebar ratio= 0.12 t/m3 of concrete

Concrete supply=\$ 135 /m3

Rebar supply=\$ 900 /t

Initial form set-up time= 4 weeks

#### **Durations**

Number of days= 670 days
Number of hours= 16080 hours
Number of weeks= 134 weeks

#### Labour

Crew size 30
Average labour rate \$ 47 /hour

Total labour cost=\$ 22,672,800

## **Equipment**

Form \$ 1000000
Weekly cost of other equipment \$ 15000 (see TED 2370)

Total equipment cost=\$ 3,010,000

## Materials Cost Summary

Concrete= 97500 m3 Labour 22,672,800 Rebar= 11700 Equipment 3,010,000

Materials 23,692,500
Concrete cost=\$ 13,162,500
Total 49,375,300

Rebar cost=\$ 10,530,000 Total 49,375,30

Total material cost=\$ 23,692,500

# Newfoundland Fixed Link Pre-feasibility Study Drill and Blast Highway Tunnel - Zones 1, 3, and 5 Tunnel Final Liner Cost Estimate

Tunnel length= 13748 m Liner cross section area= 17.2 m2

# Shift pattern

Shifts	Hours	Days
3	8	5

Advance rate= 10 m/day

Rebar ratio= 0.12 t/m3 of concrete

Concrete supply=\$ 135 /m3

Rebar supply=\$ 900 //

Initial form set-up time= 4 weeks

#### **Durations**

Number of days= 1395 days
Number of hours= 33475 hours
Number of weeks= 279 weeks

#### Labour

Crew size 30
Average labour rate \$ 40 /hour

Total labour cost=\$ 40,170,240

## **Equipment**

Form \$ 1000000
Weekly cost of other equipment \$ 15000 (see TED 2370)

Total equipment cost=\$ 5,184,400

## Materials Cost Summary

Concrete= 236465.6 m3 Labour 40,170,240
Rebar= 28375.872 Equipment 5,184,400

Materials <u>57,461,141</u> Concrete cost=\$ 31,922,856

Total <u>102,815,781</u>

Total material cost=\$ 57,461,141

Rebar cost=\$ 25,538,285

# Main Electrical Components for Novaroute Drill & Blast Highway Tunnel Option unnel= 20248 m Number of tunnels=

Length of each tunnel= Tunnel width= 9.5

Item	Component	Unit	Qty	Unit Cost	Total Cost	
	Lighting					<u>'</u>
	Threshold + transition (1st 700m)	m2	7280	315	2293200	Lighting costed elsewhere
	Interior (balance)	m2	185706	120.00	22284720	
			Lightin	g subtotal	0	
	Substations, generate					
	Substations	Ea	2	1337000	2674000	
	Emergency generator	Ea	1	955000	955000	
	UPS (Battery system)	Ea	1	573000	573000	
	` ,	tions, gene	erators, UP	S subtotal	4202000	
	CCTV system					
	Cameras (every 60m)	Each	337	3100	1044700	
	Control station	Each	1	30000	30000	
	•	C	CTV syste	m subtotal	1074700	
	Provide power for gas	detection	ventilation	n etc.	1	
	Power provision	m	20248	45	911160	
	-		Powe	er subtotal	911160	
	Lane control system	T	I	I	I	
	Fibre optic display (every 200m)	Each	101	12500	0	
		Lane coi	ntrol syster	n subtotal	0	

Total Electrical 6187860

## Initialisation

Project: Newfoundland Fixed Link Pre-feasibility Study

Section: North Approach
Option: D&B Highway Tunnel

Date: 8-Jun-04

Calculations by: ANW

Surface gradient 2.87 %

+ sloping same way as track/road - sloping against track/road

Track/Road Gradient 6 %

Ground elevation at portal 100 m

Bottom of slab elevation at portal 81.6 m

Total length= 587.8594 m


Total Cost=\$ 10.6 M

Newfoundland Fixed Link Pre-feasibility Study	Date:	8-Jun-04
North Approach	Calculations by:	ANW
D&B Highway Tunnel		

# UNIT RATES


# **Materials**

Item	unit	Rate				
excavation	m3	60				
concrete	m3	190				
rebar	tonnes	1600				
formwork/falsework	m2	140				
SP&L<=4.6m deep	m2	0				
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=6.7m>	m2	0				
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0</td></sp&l<=10.6m>	m2	0				
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=13.7m>	m2	0				
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0</td></sp&l<=16.8m>	m2	0				
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0</td></sp&l<=20.0m>	m2	0				
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0</td></sp&l<=25m>	m2	0				
backfill + compact	m3	40				
surface reinstatement	m2	30				




Item	Unit	Quantity	Rate	Cost
excavation	m3	13153.0	60	789180.1
concrete	m3	2381.36	190.0	452458.4
rebar	tonnes	285.8	1600	457221.1
formwork/falsework	m2	1961.099	140	274553.9
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>2055.2</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	2055.2	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	752.4601	30	22573.8


Total 1995987




Item	Unit	Quantity	Rate	Cost
excavation	m3	11768.5	60	706108.5
concrete	m3	2186.661	190.0	415465.5
rebar	tonnes	262.4	1600	419838.9
formwork/falsework	m2	1744.767	140	244267.3
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>1838.8</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	1838.8	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	752.4601	30	22573.8




Item	Unit	Quantity	Rate	Cost
excavation	m3	10221.7	60	613302
concrete	m3	1829.712	190.0	347645.4
rebar	tonnes	219.6	1600	351304.8
formwork/falsework	m2	1528.435	140	213980.8
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>1622.5</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	1622.5	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	740.7029	30	22221.09



Item	Unit	Quantity	Rate	Cost
excavation	m3	8858.8	60	531528.4
concrete	m3	1656.647	190.0	314762.9
rebar	tonnes	198.8	1600	318076.2
formwork/falsework	m2	1312.102	140	183694.3
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>1406.2</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	1406.2	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	740.7029	30	22221.09




Item	Unit	Quantity	Rate	Cost
excavation	m3	7415.0	60	444900.3
concrete	m3	1402.673	190.0	266507.8
rebar	tonnes	168.3	1600	269313.1
formwork/falsework	m2	1095.77	140	153407.8
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1189.8</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1189.8	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	732.708	30	21981.24




Item	Unit	Quantity	Rate	Cost
excavation	m3	5826.4	60	349582.1
concrete	m3	1003.864	190.0	190734.2
rebar	tonnes	120.5	1600	192741.9
formwork/falsework	m2	879.4377	140	123121.3
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>973.5</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	973.5	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	703.6677	30	21110.03

Total 877289.5




Item	Unit	Quantity	Rate	Cost
excavation	m3	4415.8	60	264946.5
concrete	m3	783.0969	190.0	148788.4
rebar	tonnes	94.0	1600	150354.6
formwork/falsework	m2	663.1054	140	92834.76
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>757.2</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	757.2	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	685.6792	30	20570.38

Total 677494.6




Item	Unit	Quantity	Rate	Cost
excavation	m3	3104.4	60	186262.1
concrete	m3	661.5182	190.0	125688.5
rebar	tonnes	79.4	1600	127011.5
formwork/falsework	m2	446.7732	140	62548.24
SP&L<=4.6m deep	m2	540.8	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	674.8626	30	20245.88

Total 521756.2



Item	Unit	Quantity	Rate	Cost
excavation	m3	1832.8	60	109966
concrete	m3	579.7446	190.0	110151.5
rebar	tonnes	69.6	1600	111311
formwork/falsework	m2	230.4409	140	32261.73
SP&L<=4.6m deep	m2	324.5	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	664.046	30	19921.38

Total 383611.6



Item	Unit	Quantity	Rate	Cost
excavation	m3	611.1	60	36668.32
concrete	m3	547.9438	190.0	104109.3
rebar	tonnes	65.8	1600	105205.2
formwork/falsework	m2	14.10863	140	1975.208
SP&L<=4.6m deep	m2	108.2	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	664.2812	30	19928.43

Total 267886.5

No. Committee of the Dec	. f !!. !!!t- Ot!-	D-1 0 los 04	
Newfoundland Fixed Link Pro	e-feasibility Study	Date: 8-Jun-04	
North Approach	Calc	ulations by: ANW	
D&B Highway Tunnel			
Summary of Costs			
•	Markup for adjacent	0 %	
		,,	
Sectio	n Cost		
1	1995987		
2	1808254		
3	1548454		
4	1370283		
5	1156110		
6	877289.5		
7	677494.6		
8	521756.2		
9	383611.6		
10	267886.5		
Sub-tota			
Sub-tota	al 10607127		


## Initialisation

Project: Newfoundland Fixed Link Pre-feasibility Study

Section: South Approach
Option: D&B Highway Tunnel

Date: 8-Jun-04

Calculations by: ANW



elevation at portal

Total length= 334.5455 m

81.6

Total Cost=\$ 6.0 M


- + sloping same way as track/road
- sloping against track/road

Newfoundland Fixed Link Pre-feasibility Study	Date:	8-Jun-04
South Approach	Calculations by:	ANW
D&B Highway Tunnel		


# UNIT RATES

## **Materials**


matorialo		
Item	unit	Rate
excavation	m3	60
concrete	m3	190
rebar	tonnes	1600
formwork/falsework	m2	140
SP&L<=4.6m deep	m2	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=6.7m>	m2	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0</td></sp&l<=10.6m>	m2	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=13.7m>	m2	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0</td></sp&l<=16.8m>	m2	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0</td></sp&l<=20.0m>	m2	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0</td></sp&l<=25m>	m2	0
backfill + compact	m3	40
surface reinstatement	m2	30



Item	Unit	Quantity	Rate	Cost
excavation	m3	7485.3	60	449115.2
concrete	m3	1355.21	190.0	257489.9
rebar	tonnes	162.6	1600	260200.4
formwork/falsework	m2	1116.044	140	156246.1
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>1169.6</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	1169.6	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	428.2182	30	12846.55




Item	Unit	Quantity	Rate	Cost
excavation	m3	6697.3	60	401839.9
concrete	m3	1244.409	190.0	236437.7
rebar	tonnes	149.3	1600	238926.5
formwork/falsework	m2	992.9309	140	139010.3
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>1046.5</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	1046.5	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	428.2182	30	12846.55




Item	Unit	Quantity	Rate	Cost
excavation	m3	5817.1	60	349024.6
concrete	m3	1041.273	190.0	197841.8
rebar	tonnes	125.0	1600	199924.4
formwork/falsework	m2	869.8182	140	121774.5
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>923.3</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	923.3	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	421.5273	30	12645.82

Total 881211.1




Item	Unit	Quantity	Rate	Cost
excavation	m3	5041.5	60	302488
concrete	m3	942.7825	190.0	179128.7
rebar	tonnes	113.1	1600	181014.2
formwork/falsework	m2	746.7055	140	104538.8
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>800.2</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	800.2	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	421.5273	30	12645.82

Total 779815.5




Item	Unit	Quantity	Rate	Cost
excavation	m3	4219.8	60	253188.7
concrete	m3	798.2482	190.0	151667.2
rebar	tonnes	95.8	1600	153263.7
formwork/falsework	m2	623.5927	140	87302.98
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>677.1</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	677.1	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	416.9775	30	12509.32

Total 657931.8




Item	Unit	Quantity	Rate	Cost
excavation	m3	3315.7	60	198944
concrete	m3	571.2899	190.0	108545.1
rebar	tonnes	68.6	1600	109687.7
formwork/falsework	m2	500.48	140	70067.2
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>554.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	554.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	400.4509	30	12013.53

Total 499257.5




Item	Unit	Quantity	Rate	Cost
excavation	m3	2513.0	60	150778.6
concrete	m3	445.6534	190.0	84674.14
rebar	tonnes	53.5	1600	85565.44
formwork/falsework	m2	377.3673	140	52831.42
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>430.9</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	430.9	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	390.2138	30	11706.41



Newfoundland Fixed Link Pre-feasibility Study Date: 8-Jun-04 South Approach
D&B Highway Tunnel
Calculated costs Calculations by: ANW Page 2 of 2

Item	Unit	Quantity	Rate	Cost
excavation	m3	1766.7	60	106000.1
concrete	m3	376.464	190.0	71528.16
rebar	tonnes	45.2	1600	72281.09
formwork/falsework	m2	254.2545	140	35595.64
SP&L<=4.6m deep	m2	307.8	0	0
4.6 <sp&l<=6.7m deep<br="">6.7<sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m></sp&l<=6.7m>	m2	0.0	0	0
	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	384.0582	30	11521.75


Total 296926.7



Newfoundland Fixed Link Pre-feasibility Study Date: 8-Jun-04 South Approach
D&B Highway Tunnel
Calculated costs Calculations by: ANW Page 2 of 2

Item	Unit	Quantity	Rate	Cost
excavation	m3	1043.0	60	62580.66
concrete	m3	329.9274	190.0	62686.2
rebar	tonnes	39.6	1600	63346.06
formwork/falsework	m2	131.1418	140	18359.85
SP&L<=4.6m deep	m2	184.7	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	377.9025	30	11337.08

Total 218309.9



Newfoundland Fixed Link Pre-feasibility Study Date: 8-Jun-04 South Approach
D&B Highway Tunnel
Calculated costs Calculations by: ANW Page 2 of 2

Item	Unit	Quantity	Rate	Cost
excavation	m3	347.8	60	20867.61
concrete	m3	311.8298	190.0	59247.67
rebar	tonnes	37.4	1600	59871.33
formwork/falsework	m2	8.029091	140	1124.073
SP&L<=4.6m deep	m2	61.6	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	378.0364	30	11341.09

Total 152451.8

Newfoundland Fixed Link Pre-feasibility Study Date: 8-Jun-04 South Approach Calculations by: ANW D&B Highway Tunnel				
Summary of Costs				
		Markup for adjacent	0 %	
	Section	Cost		
	1	1135898		
	2	1029061		
	3	881211.1		
	4	779815.5		
	5 6	657931.8 499257.5		
	7	385556		
	8	296926.7		
	9	218309.9		
_	10	152451.8		
8	Sub-total	6036419		

#### Newfoundland Fixed Link Pre-feasibility Study Highway Tunnel - North Vent Adit Tunnel Final Liner Cost Estimate

Tunnel length= 600 m Liner cross section area= 5.47 m2

#### Shift pattern

Shifts	Hours	Days
3	8	5

Advance rate= 30 m/day

Rebar ratio= 0.12 t/m3 of concrete

Concrete supply=\$ 135 /m3

Rebar supply=\$ 900 /t

Initial form set-up time= 4 weeks

#### **Durations**

Number of days= 40 days
Number of hours= 960 hours
Number of weeks= 8 weeks

#### Labour

Crew size 15
Average labour rate \$ 47 /hour

Total labour cost=\$ 676,800

#### **Equipment**

Form \$ 1000000
Weekly cost of other equipment \$ 15000 (see TED 2370)

Total equipment cost=\$ 1,120,000

#### Materials Cost Summary

Concrete= 3279.8227 m3 Labour 676,800
Rebar= 393.57873 Equipment 1,120,000
Materials 796,997

Concrete cost=\$ 442,776 Total 2,593,797


Rebar cost=\$ 354,221

Total material cost=\$ 796,997

## Newfoundland Fixed Link Pre-feasibility Study Highway Tunnel - North Vent Adit Tunnel Drill and Blast Cost Estimate

Drill & blast excavation	@ \$	250	/m3
Tunnel length= Tunnel excavated diameter=	600 6.5	m m	
Excavated volume=	19909.8	m3	
Excavation cost=\$	4,977,461		

#### Newfoundland Fixed Link Pre-feasibility Study Highway Tunnel - North Vent Adit Shaft Tunnel Drill and Blast Cost Estimate



#### From graph

unlined shaft cost=\$ 17000 /m

#### Quantities

Concrete Base= 24 m3
Shotcrete= 173 m3
Rockbolts= 1728 m2
final cast in place liner= 547 m3

#### **Direct Costs**

				\$ - Cost	
shaft excavation etc.	100	*	17000	1700000	
Concrete Base	24	*	150	3564	
Shotcrete	173	*	500	86394	
Rockbolts	1728	*	10	17279	
liner	547	*	600	327982	(includes steel & forms)
		Total D	Direct Cost=	2135219	<del>-</del>

## Newfoundland Fixed Link Pre-feasibility Study Highway Tunnel - North Vent Adit Summary

D&B Excavation 4,977,461 Liner 2,593,797 Shaft 2,135,219 9,706,476

#### Newfoundland Fixed Link Pre-feasibility Study Highway Tunnel - South Vent Adit Tunnel Final Liner Cost Estimate

Tunnel length= 2000 m
Liner cross section area= 5.47 m2

#### Shift pattern

Shifts	Hours	Days
3	8	5

Advance rate= 30 m/day

Rebar ratio= 0.12 t/m3 of concrete

Concrete supply=\$ 135 /m3

Rebar supply=\$ 900 /t

Initial form set-up time= 4 weeks

#### **Durations**

Number of days= 87 days
Number of hours= 2080 hours
Number of weeks= 17 weeks

#### Labour

Crew size 15
Average labour rate \$ 47 /hour

Total labour cost=\$ 1,466,400

#### **Equipment**

Form \$ 1000000
Weekly cost of other equipment \$ 15000 (see TED 2370)

Total equipment cost=\$ 1,260,000

Total material cost=\$ 2,656,656

#### Materials Cost Summary

Concrete= 10932.742 m3 Labour 1,466,400 Rebar= 1311.9291 Equipment 1,260,000


Materials <u>2,656,656</u> Concrete cost=\$ 1,475,920 Total **5,383,056** 

Rebar cost=\$ 1,180,736

#### Newfoundland Fixed Link Pre-feasibility Study Highway Tunnel - South Vent Adit Tunnel Drill and Blast Cost Estimate

Drill & blast excavation	n @ \$	250	/m3
Tunnel length= Tunnel excavated diameter=		m m	
Excavated volume=	66366.1	m3	
Excavation cost=\$	16,591,536		

#### Newfoundland Fixed Link Pre-feasibility Study **Highway Tunnel - South Vent Adit Shaft Tunnel Drill and Blast Cost Estimate**



#### From graph

unlined shaft cost=\$ 17000

#### Quantities

Concrete Base= 24 m3 Shotcrete= 0 m3 Rockbolts= 0 m2 final cast in place liner= 0 m3

#### **Direct Costs**

\$ - Cost shaft excavation etc. 0 17000 0 3564 Concrete Base 24 150 Shotcrete 0 500 0 Rockbolts 0 10 0 liner 0 600 0 Total Direct Cost= 3564

(includes steel & forms

## Newfoundland Fixed Link Pre-feasibility Study Highway Tunnel - South Vent Adit Summary

D&B Excavation 16,591,536 Liner 5,383,056 Shaft 3,564 21,978,156

#### **Newfoundland Fixed Link Drill & Blast Highway Tunnel Tunnel Lighting Cost**

#### Fraser River Project - 2x3 lane tunnels

For	1550	m length of Theo Van Kooten calculated the tunn	el lighting cost as follows:

732	m of threshold lighting costs \$	661231.22	1260	lights		
818	m of interior lighting costs \$	73151.75	139	lights		
1550	m of nightime circuit costs \$	126767.31	241	lights		
1640	lights cost \$	117280.47 to	o instal	_		
1550	m of conduit costs	101424.99				
		1079855.74	*	2	= \$	2,159,711

# Prorating for Newfoundland - assuming \*50% for single lane tunnel for 20248 m length of tunnel

732	m of threshold lighting costs \$	661231.22	1260	lights		
19516	m of interior lighting costs \$	1745268.4	3317	lights		
20248	m of nightime circuit costs \$	1655990.00	3149	lights		
7726	lights cost \$	552505.43 t	o instal			
20248	m of conduit costs	1324937.55				
		5939932.60	*	0.5	= \$	2,969,966

# Newfoundland Fixed Link Pre-feasibility Study Drill & Blast Highway Tunnel - North Vehicle Holding Area



#### **Earthworks**

Assume 0.5 m depth cleared over entire area

Spoil excavation and removal @ \$ 30 /m3

Earthworks= 2,700,000

#### **Surface**

Assume surface @ 20 /m2

Surface= 3,600,000

#### Buildings etc.


Public facilities building @ 80000 See CJT estimate
Site maintenance building @ 220000 See CJT estimate
Fire engines @ 360000 See CJT estimate


Total cost **6,960,000** 

Newfoundland Fixed Link Pre-feasibility Study Cost Estimating Single Lane Drill & Blast Highway Tunnel Tunnel Structural Finishes

Page 1 of 2

**Date:** June 07, 2004 **Calculation by:** A.White





#### Newfoundland Fixed Link Pre-feasibility Study Cost Estimating Single Lane Drill & Blast Highway Tunnel

**Tunnel Structural Finishes** 

Page 2 of 2

**Date:** June 07, 2004 **Calculation by:** A.White

## **Quantity Take-off**

Concrete					Concrete	Rebar
Element	Nr.	L(m)	b(m)	d(m)	Qty(m3)	Qty(m3)
1	1	6500	8.8	0	0	0.0
2	1	6500	0.3	5.4	10530	1263.6
3	1	6500	1.8	0.3	3510	421.2
					14040 m3	421 t

#### Formwork/falsework

Element	Nr.	L(m)	d(m)	Faces	Area(m2)	)
1	1	6500	0	0	0	
2	2	6500	5.4	2	70200	
3	1	6500	1.8	1	11700	
					81900	_m2

#### Rates

Concrete	m3	190
Formwork	m2	140
Reinforcement	t	1600


#### Costs

Concrete	m3	14040 m3	at	190	=	2667600
Formwork	m2	81900 m2	at	140	=	11466000
Reinforcement	t	421 t	at	1600	=	673920
				\$		14807520

Newfoundland Fixed Link Pre-feasibility Study Cost Estimating Single Lane Drill & Blast Highway Tunnel Tunnel Structural Finishes Page 1 of 2

**Date:** June 07, 2004 **Calculation by:** A.White

Tunnel length= 13748 m



#### Newfoundland Fixed Link Pre-feasibility Study Cost Estimating Single Lane Drill & Blast Highway Tunnel Tunnel Structural Finishes

Page 2 of 2

**Date:** June 07, 2004 **Calculation by:** A.White

#### **Quantity Take-off**

Concrete					Concrete	Rebar
Element	Nr.	L(m)	b(m)	d(m)	Qty(m3)	Qty(m3)
1	1	13748	0.5	1.5	10311	1237.3
2	1	13748	9	0.5	61866	7423.9
3	1	13748	8.6	0.5	59116	7094.0
4	1	13748	0.3	5	20622	2474.6
5	1	13748	1.8	0.3	7423.9	890.9
					159339 m3	10459 t

#### Formwork/falsework

Element	Nr.	L(m)	d(m)	Faces	Area(m2)
1	1	13748	1.5	2	41244
2	2	13748	8.5	1	116858
3	1	13748	8.6	1	118232.8
4	1	13748	5	2	137480
5	1	13748	1.8	1	24746.4
					438561.2 m2

#### Rates

Concrete	m3	190
Formwork	m2	140
Reinforcement	t	1600

#### Costs

Concrete	m3	159339 m3	at	190	= 30274471
Formwork	m2	438561 m2	at	140	= 61398568
Reinforcement	t	10459 t	at	1600	= 16735165
				\$	108408204

680.360656

#### Newfoundland Fixed Link Drill & Blast Highway Tunnel - Tunnel Finishes Cost Summary

	Zones	Zones		
	1, 3, and 5	2 and 4	Total	
Concrete	2,667,600	30,274,471	32,942,071	
Formwork	11,466,000	61,398,568	72,864,568	
Reinforcement	673,920	16,735,165	17,409,085	
			123,215,724	710.6714



Newfoundland Fixed Link Pre-feasibility - Drill & Blast Highway Tunnel - Cost Summary

	BORED TUNNEL CO	ONSTRUCTION COSTS
ITEM	UNIT	MAIN TUNNEL
MOBILIZATION & DEMOBILIZATION	LS	8,000,000
DRILL & BLAST TUNNELLING	LS	461,565,738
TUNNEL LINER	LS	152,191,081
TUNNEL FINISHES	LS	123,215,724
NORTH APPROACH STRUCTURES	LS	10,607,127
SOUTH APPROACH STRUCTURES	LS	6,036,419
NORTH VENTILATION ADIT	LS	9,706,476
SOUTH VENTILATION ADIT	LS	21,978,156
ROAD FINISHES	LS	2,646,625
TUNNEL DRAINAGE	LS	7,370,000
NORTH VEHICLE HOLDING AREA	LS	6,960,000
SOUTH VEHICLE HOLDING AREA	LS	4,260,000
UTILITY DIVERSIONS	LS	1,000,000
MONITORING	LS	1,000,000
		· ·
SUBTOTAL CIVIL		\$816,537,346
CIVIL CONTINGENCIES		
CONTINGENCY	40%	\$326,614,939
TOTAL CIVIL		\$1,143,152,285
	440 5 4415 51	NIOUNIO MODIZ
VENTU ATION FOLUDATION		NISHING WORK
VENTILATION EQUIPMENT	LS	\$6,000,000
VENTILATION BUILDINGS x 2	LS	\$2,000,000
FIRE SUPPRESSION SYSTEM	LS	\$4,000,000
CONTROL CENTRE	LS	\$4,000,000
SIGNALLING	LS	\$0
LIGHTING	LS	\$2,969,966
CCTV SYSTEM	LS	\$1,074,700
GAS DETECTION	LS	\$911,160
SUBSTATION, GENERATORS, UPS	LS	\$4,202,000
SUBTOTAL M&E AND FINISHING		\$25,157,826
SUBTUTAL MIGE AND FINISHING		\$25,157,020
CONTINGENCIES	20%	\$5,031,565
CONTINGENCIES	20%	φυ,υυ ι ,υυυ
TOTAL M&E AND FINISHING		\$30,189,392
TOTAL MIGLAND FINISHING		ψ30,103,332
TOTAL CIVIL, M&E AND FINISHING		\$1,173,341,676
TOTAL SIVIL, MAL AND TIMOTIMO		¥1,110,011,010
ALLOWANCES		
CONTRACTOR OH	15%	\$176,001,251
CONTRACTOR PROFIT	15%	\$176,001,251
CONSTRUCTION TOTAL		\$1,526,000,000
		ON AND SUPERVISION
FEASIBILITY STUDY	LS	\$11,000,000
ENVIRONMENTAL ASSESSMENT	LS	\$4,000,000
DESIGN	5%	\$76,300,000
CONSTRUCTION MANAGEMENT	10%	\$152,600,000
OWNERS COSTS	2%	\$30,520,000
		MO74 400 CCC
PRE-CONSTRUCTION TOTAL		\$274,420,000
GRAND TOTAL		\$1,800,420,000
OITHE TOTAL		ψ1,000,T20,000



## **Tunnel Estimating Database**

Copyright Hatch Mott MacDonald, 2002

MEMORIAL/213789/DESIC/Cost Estimating & Scheduling/Costs 4 - End Sept Final/SingleHighwayD&BRev/[Nwfld Cost - Highway - June 11 2004.xls	TED Title Page
--	----------------

Version VANC-1.0

Project: Estimate Description: Newfoundland Fixed Link Study Prefeasibility Level Project Number:

213789

**Project Phase:** 

Prefeasibility Design

Estimate Date:

June 11 2004

# Newfoundland Fixed Link Study Prefeasibility Level

213789

Prefeasibility Design

June 11 2004

STRUCTION AND SUPERVISION

Printed: 9:07 AM on 11/25/04

Estimated by: \_\_\_\_PJP\_\_\_\_



Project:

## **Tunnel Estimating Database**

213789

Copyright Hatch Mott MacDonald, 2002

P://MEMORIAL.213789/DES/C/Cost Estimating & Scheduling/Costs 4 - End Sept Final/SingleHighwayD&BRev/[Nwfld Cost - Highway - June 11 2004.ds [V-317

Newfoundland Fixed Link Study

Version VANC-1.5

Estimate Description:	Prefeasibility Level		Parent Estimate ID:	V-300				
Tunnel Name:	Highway Tunnel - Single Lane - Down Drive		Project Phase:	Prefeasibility Design				
Construction Activity:	Excavation (Drill & Blast) & Initial Support		ıpport	Geology Type:		Poor to Fair Sediments & Volcanics		
Estimate Definition ID:	V-317			Estimate Date:		June 11 2 004		
	Tunnal C	Characteristics			C	hift Details		
Tunnel Length:	6,500.0	mar acteristics	m		Shift Arrangement:	3.0	Shifts / Day	
Design Width:	10.9				Same Arrangement.	8.0	Hours / Shift	
0	4.5		m			7.0	Days / Week	
Design Wall to Poof:	3.7		m		Drill Charge Pla	st, Vent & Muckin		
Design Wall to Roof:	8.2				·	30.0		
Design Max Height:			m		Survey Tunnel / Holes / Map:	30.0	Min / Cycle	
Ave Tunnel Overbreak:	20.0	(Includes Overbrook)	cm m <sup>2</sup>		Drilling Blast Holes:	2.0	/ II-1-	
Tunnel Face Area:	86.8	(Includes Overbreak)			Hole Length:	3.9	m / Hole	
Crown Perimeter:	15.1	(Includes Overbreak)	m		Perim. Blast Hole Spacing:	0.50	m	
Wall & Crown Perimeter:	24.5	(Includes Overbreak)	m 2		Interior Blast Hole Spacing:	1.25	m	
Wall & Crown Area:	159,433	(Includes Overbreak)	m <sup>2</sup>		No. Perimeter Holes:	49	No.	
Neat Tunnel Excav. Vol.:	564,086	(Includes Overbreak)	m <sup>3</sup>		No. Interior Area Holes:	55.5	No.	
Re-Muck / Pull-Out Bays:					No. Blast Initiation Holes:	15	No.	
Bay Length:	10.0		m		Number of Drillholes / Blast:	120	Blastholes / Blast	
Spacing Bttn Bays:	1000.0		m		Blast Hole / Face Area Ratio:	1.38	Holes / m <sup>2</sup>	
Number of Bays:	6		No.		Typical / Check Ratio:	<u>1.26</u>	Holes / m <sup>2</sup>	
Total Length of Bays:	60.0		m		Drill Eqpt Set-Up Time:	40	min / Set-up	
Neat Excavation Vol.:	5,207		$m^3$		Drill Penetration Rate:	0.30	m / Min	
Total Tunnel Volume:	569,293		$m^3$			18	m/hour	
Muck Bulking Factor:	1.6		Ratio		# of Drills or Booms:	6.0	No.	
Bulked Tunnel Volume:	910,869	(Loose Muck Volume)	$m^3$		Charging & Blasting:			
<u>Prin</u>	nary Muckin	ng Production Details			Prime & Load Rate / Hole:	2.50	min / Blasthole	
(Activity to remove blast mu	ck from face	to conveyor & muck cars)			Prep & Hook-up Time:	40.0	min / Set-up	
Muck Volume / Blast:	458.2		$m^3$		Total No. Blasts / Tunnel:	1988	No.	
Mucking Volume / Trip:	5.00		$m^3$		Net Blast Break Length:	3.3	m / Blast	
Bucket Fill Factor (%):	90.0		%		Blast & Ventilation Time:	1.0	Hours	
Number of Trips:	102		No.			ation Grouting Det		
Ave. Dist. to Load:		e Distance One Way)	m		% Tunnel to be Grouted:	12.0	%	
Ave. Tramming Speed:	8.0	e Bistance one way)	km/hr		Tunnel Length to Grout:	780	m	
Load, Dump, Manoever:		me per Trip)	Min		Grout Hole Length:	7.0	m	
Face Cleanup / Blast:	15.0	ine per 111p)	Min		No. of Grouting Applications:	111	No.	
Mucking Time:	2.8		Hours		Perim. Grout Holes Spacing:	1.50	m	
_	161.5		m <sup>3</sup> / H	OUF	# Perim. Grout Holes:	16	Holes / Grout Cycle	
Mucking Rate:		port Class Details	ш / п	oui	Drilling Penetration Rate:	50	m/hour	
Class I - No Support:	0.0 (%		0	(m)	9			
• •					No. of Drill Booms:	2	No.	
Class II - Spot Bolts:	0.0 (%		0	(m)	Drilling Time per Cycle:	128	Min	
Class III - Crown Only:	40.0 (%		2,600	(m)	Grout Eqpt. Set-Up Time:	1.0	Hours / Grout Cycle	
Class IV - Full Pattern:	50.0 (%		3,250		No. of Holes Grouted at Once:	2	Hoses	
Class V - Steel Sets:	<u>10.0</u> (%	o)	<u>650</u>	(m)	Grouting Injection Rate:	10	min / Drillhole	
Total	100.0		6,500	(m)	Full Grout Cycle Time:	66.0	Hours	
		ete Support Details				Installation Details		
Support Arc Length:	24.5		m		Steel Set Spacing:	1.0	m	
Thickness:	25.0		mm		Total No. Sets / Tunnel:	650	No.	
Volume / Round:	2.3		m <sup>3</sup>		Ave. Installation Time / Set:	3.0	Hours	
Time:	0.8 (Incl	udes Scaling & Equip Set-up)	Hours		Total Installation Time:	1,950	Hours	

Project Number:

Printed: 9:07 AM on 11/25/04 Page 3 of 12

<u>y</u>	Viremesh Installation Details		<u>Re</u>	ockbolt Support Class Deta	<u>ils</u>
Install Rate:	100	m² / Hour	<u>(Bc</u>	olts Per	(Bolts Per Support
Total Install Time:	1,757.7	Hours	<u>R</u>	(Bolts Per m)	<u>Class</u> )
Ave. Install Time:	53.1	Min	Class I:	0.0	0
Overlap:	5	%	Class II:	0.0	0
Net Applied Area:	159,433 (Assume Class V only)	$m^2$	Class III:	9 6.0	15,600
Area with Overlap:	175,775	m <sup>2</sup>	_Class IV:	<b>21</b> 14.0	45,500
<u>Fina</u>	Shotcrete Support Class Details		Class V:	0.0	<u>0</u>
Shotcrete Thickness:			Total:		61,100
Classes I and II:	0	mm		Face Scaling	
Class III:	0	mm	Scaling Time:	2 0.0	min / Blast
Classes IV:	50	mm	<u>F</u>	Rockbolt Installation Detail	<u>s</u>
Class V:	100	mm	Rockbolt Length:	3.0	m
Support Arc Length:			Row Spacing:	1.5	m
Class I:	0.0	m	No. Rockbolts Required	d: 61,100	No.
Class II:	0.0	m	Ave. Bolts / Round:	31.0	Bolts / Blast
Class III:	0.0	m	Drilled Length / Round	93	m
Class IV:	24.5	m	Total Drilling Length:	183,300	m
Class V:	24.5	m	Drill Penetration Rate:		m / Min
·	d Final Shotcrete Application Details	3	# of Drills / Booms Use		No.
Net Volume:	5,580	$m^3$	Ave. Drilling Time / Ro		Min
Rebound / Waste:	15	%	Bolt Install Rate	2.0	Min / Bolt
Final Layer Volume:	6,417	m <sup>3</sup>	Ave. Bolt Install Time:		Min
No. of Applications:	(Required Per Bench)	No.	Drill Set-Up Time:	10.0	Min
Ave. Vol. / Application:	5.6	m <sup>3</sup>	Total Bolt Drill/Install		Min
Surface Prep Time:	10.0	Min		<u>Drainhole Details</u>	
Total Surface Prep Time:	11,424	Min	Drainhole Spacing:	3.0	m
Application Rate:	24.0	m³ / Hour	Drainhole Length:	1.1	m
Total Application Time:	16,043	Min	Total Area:	79,716.4	m <sup>2</sup>
Eqpt. Setup Time:	20.0	Min	Total Drainholes:	8,857.4	# / Per Tunnel
Total Setup Time:	22,848	Min	Total Length:	9,743.1	m
Eqpt. Remove Time:	10.0 (Required Per Application)	Min		ut concurrent with other activ	vities.
Total Remove Time:	11,424	Min		ation of Tunneling:	
Total Shotcreting Time:	61,740 (For Final Shotcrete Layer)	Min	Pre-Exc. Grouting Tim		Hours
Equivalent Time / Blast:	31.1	Min / Cycle	_ Drilling Time =	9,932.2	Hours
	Secondary Mucking Details		Charge, Blast, Vent Ti	*	Hours
Req'd during Tunneling:	No (No if loaded directly into trucks	1	Primary Mucking Tim	*	Hours
Ave. LHD Tram Speed:	0.0	km / hour	Scaling Time =	1,988.2	Hours
	Vick Drain Installation Details		Survey / Map Time =	993.9	Hours
Drain Spacing:	0.0	m	Install Steel Sets Time	*	Hours
Installation Time / Row:	0.0	Hours / Drain	_ Initial Shotcreting Tim	,	Hours
Average	Tunneling Productivity Cycle Details		Install Services Time =		Hours
Fauly Dro Evo Croutings	2.7	Hours	Rockbolting (of % Crit Non-Productive Time =	*	Hours
Equiv. Pre-Exc. Grouting: Drilling:	3.7 5.0	Hours Hours	ron-ribuuctive lime =	993.9	Hours
9	5.7	Hours	Total Time =	45 527 0	Hours
Charging: Blast & Venting:	1.0	Hours		45,527.0 62.5	Months
Mucking:	2.8	Hours	(Critical Path Tunnelin		Weeks
Scaling:	0.3	Hours	Activities Only)	1,897.0	Days
Surveying / Mapping:	0.5	Hours		Concurrent Tunneling Act	
Surveying / Mapping: Initial Shotereting:	0.8	Hours	Other	Concurrent Tunnering Act	1,1110
Install Services:	0.5 (Equiv. Time Per Cycle)	Hours	Rockbolting (of % Not Co	ritical) = 2,150.4	Hours
Non-Productive Time:	0.5 (Equiv. Time Per Cycle) 0.5 (Travel in/out, Break)	Hours	Wiremesh Installation		Hours
	, , ,	110010	Final Shotcreting Time	*	Hours
Non-Froductive Time.		`	Drilling Drainholes =	6,495.4	Hours
	Ves (Ves / No as part of Cycle Time		Dinning Diaminutes -	U,+2J.+	110013
Include Rockbolting:	Yes (Yes / No, as part of Cycle Time)  (% Reg'd During Cycle for Poor		=	0.0	Hours
Include Rockbolting: If yes, % of Support Rq'd:	30 (% Req'd During Cycle for Poor	er Ground)	Secondary Mucking =	$0.0$ $\mathbf{n} = 0.0$	Hours Hours
Include Rockbolting:			=	<b>n</b> = 0.0	Hours Hours
Include Rockbolting: If yes, % of Support Rq'd:	30 (% Req'd During Cycle for Poor	er Ground)	Secondary Mucking =		

Estimated by:	PJP
Checked by:	

Resource Type	Resource Name	Unit Rate	Unit	Quantity	Resource Quantity	Total
Labor						
	Miner - Shift Boss	50.68	\$/hr	45,527.0	2.00	4,614,616.4
	Miner - Operator - Journeyman	47.84	\$/hr	45,527.0	11.00	23,958,126.8
	Miner - Foreman	50.68	\$/hr	45,527.0	3.00	6,921,924.6
	Miner - Laborer - Journeyman	47.40	\$/hr	45,527.0	5.00	10,789,898.2
	Miner - Laborer - Apprentice	45.00	\$/hr	45,527.0	5.00	10,243,574.2
	Tunnel Electrician - Journeyman	47.84	\$/hr	45,527.0	4.00	8,712,046.1
					30.00	65,240,186.4
Plant						
	Cable - Fans & Pumps - High Voltage	120.00	\$/m	6,500.0	0.20	156,000.0
	Cable - Lights / Controls - Low Voltage	10.00	\$/m	6,500.0	0.80	52,000.0
	Compressor	121.77	\$/wk	271.0	1.00	33,000.0
	Conveyor - Heading Muck Loading	4,774.09	\$/wk	271.0	1.00	1,293,750.0
	Drill - Jack-Leg	77.49	\$/wk	271.0	4.00	84,000.0
	Drill Jumbo - Rail Mounted - 2 Boom	968.66	\$/wk	271.0	1.00	262,500.0
	Drill Jumbo - Rail Mounted - 6 Boom	2,767.59	\$/wk	271.0	1.00	750,000.0
	Excavator - Rail Mounted	304.43	\$/wk	271.0	1.00	82,500.0
	Generator - Back-Up - 500KW	290.60	\$/wk	271.0	1.00	78,750.0
	Generator - Working - 1000KW	2,169.79	\$/wk	271.0	1.00	588,000.0
	Grout Plant-Consol-D&B-Pump, Hoses	182.66	\$/wk	271.0	1.00	49,500.0
	Lighting (Including Consumables)	7.50	\$/m	6,500.0	1.00	48,750.0
	Locomotive - Diesel - 16T	5,000.00	\$/wk	271.0	4.00	5,419,880.5
	LHD Loader - D&B Tunnel	928.53	\$/wk	271.0	1.00	251,625.0
	Manlift / Platform - Rail Mounted	405.91	\$/wk	271.0	1.00	110,000.0
	Pipe - 50mm (Water Supply)	7.50	\$/m	6,500.0	1.00	48,750.0
	Pipe - 100mm (Air Supply)	15.00	\$/m	6,500.0	1.00	97,500.0
	Pipe - 150mm (DeWatering)	25.00	\$/m	3,250.0	1.00	81,250.0
	Pipe - 250mm (Dewater)	70.00	\$/m	3,250.0	1.00	227,500.0
	Pipe - Dewatering Clamps (<=200mm)	7.00	\$/m	6,500.0	1.00	45,500.0
	Pumps - Dewatering - Tunnel - 50HP	93.16	\$/wk	135.5	15.00	189,337.5
	Rail - 80 lb/yd - Used	101.54	\$/m	13,400.0	0.60	816,369.2
	Rail - California Switch Gear	75,000.00	\$/Nr	1.0	3.00	225,000.0
	Rail Car - Flat	50,000.00	\$/Nr	1.0	3.00	150,000.0
	Rail Car - Man Rider	50,000.00	\$/Nr	1.0	1.00	50,000.0
	Rail Car - Muck Cars	1,900.00	\$/wk	271.0	18.00	9,267,995.7
	Rail Car - Muck Car Tipping System	75,000.00	\$/Nr	1.0	1.00	75,000.0
	Shotcrete Machine - Rail Mounted		\$/wk	271.0	1.00	120,750.0
		445.58				*
	Shotcrete Machine - Tire Mounted	721.42	\$/wk	271.0	2.00	391,000.0
	Small Tools	200.00	\$/wk	271.0	1.00	54,198.8
	Tie Plates, Splice Bars, Bolts	150,000.00	LS	1.0	1.00	150,000.0
	Ties - Wooden - Untreated - 7" x 9" x 40"	23.00	\$/m	6,500.0	1.00	149,500.0
	Transformers & Switch gear - High Voltage	202.96	\$/wk	271.0	1.00	55,000.0
	Transformers-Switchgear-Low Voltage	101.48	\$/wk	271.0	1.00	27,500.0
	Ventilation Duct - Rigid	110.00	\$/m	6,500.0	1.00	715,000.0
	Ventilation Fans - 75HP	57.29	\$/wk	271.0	7.00	108,675.0
	Welder (Plant)	6.37	\$/wk	271.0	1.00	1,725.0
						22,307,806.

22,307,806.90

Resource Type	Resource Name	Unit Rate	Unit	Quantity	Resource Quantity	Total
Consumables						
	Bits, Powder and Caps - Blasting	15.00	\$/m3	569,293.2	1.00	8,539,397.71
	Bits - (Drainholes & Rockbolts)	5.00	\$/m	193,043.1	1.00	965,215.55
	Drill Jumbo Maintenance	100.00	\$/hr	9,466.3	1.00	946,630.96
	Electricity - Tunnel Heading Conveyor	0.22	\$/kwh	150	496.97	16,400.00
	Electricity - Fans & Lighting	0.22	\$/kwh	411	22,763.50	2,058,237.70
	Electricity - Jumbo	0.22	\$/kwh	75	9,466.31	156,194.11
	Electricity - Pumps Dewatering	0.22	\$/kwh	559	31,868.90	3,921,164.59
	Lubricants	2,500.00	\$/wk	271.0	1.00	677,485.07
	Fuels & Lubricants	5,000.00	\$/wk	271.0	1.00	1,354,970.14
	Other Consumables	1,500.00	\$/wk	271.0	1.00	406,491.04
						\$ 19,042,186.89
Materials						
	Grout - Consolidation	50.00	\$/m3	2,000.0	1.00	100,000.00
	Other Materials	2,000.00	\$/wk	271.0	1.00	541,988.06
	Rock Bolts - No.10 - 3.0m - (Non-Galv)	40.00	\$/Nr	61,100	1.00	2,444,000.00
	Shotcrete	180.00	\$/m3	6,417.2	1.00	1,155,090.08
	Steel Sets - W10 x 65	152.75	\$/m	650	24.53	2,435,334.84
	Synthetic Wick Drains	5.00	\$/m	0	1.00	=
	WWF mesh	5.50	\$/m2	175,775	1.00	966,760.17
						\$ 6,576,412.98
Subcontracts	Tunnel Muck - Miscl Surface Handling	20.00	\$/m3	910,869.09	1.00	18,217,381.78
			••	,		\$ 18,217,381.78

Total Estimated Cost: \$ 131,383,975.02

**Per Meter:** \$ 20,212.92 **Per m<sup>3</sup>:** \$ 230.78



## **Tunnel Estimating Database**

Copyright Hatch Mott MacDonald, 2002 Version VANC-1.5

**Detailed Cost Estimate Report** 

Project:

Estimate Description:

Construction Activity:

Tunnel Name:

P:MEMORIAL: 213789/DESC:Cost Estimating & Scheduling:Costs 4 - End Sept Final SingleHighwayD&BRev [Nwfld Cost- Highway-June 11 2004.xls]V-318

Prefeasibility Level

Newfoundland Fixed Link Study

Highway Tunnel - Zones 1,2,4,&5 - Up Drive

Excavation (Drill & Blast) & Initial Support

Project Number: 213789
Parent Estimate ID: V-300

Project Phase: Prefeasibility Design

Geology Type: Poor to Fair Sediments & Volcanics

Construction Activity:	Excavation (Drill & Blast) & Initial S	арроге	Geology Type:	Pool to rail Seulin	ents ee voicumes	
Estimate Definition ID:	V-318		Estimate Date:	June 11 2004		
	Tunnel Characteristics		Sh	nift Details		
Tunnel Length:	13,748.0	m	Shift Arrangement:	3.0	Shifts / Day	
Design Width:	10.0	m		8.0	Hours / Shift	
Design Wall Height (Ave.)	9.0	m		7.0	Days / Week	
Design Wall to Roof:	3.0		Drill, Charge, Blas	st, Vent & Muckin	ng Details	
Design Max Height:	12.0	m	Survey Tunnel / Holes / Map:	30.0	Min / Cycle	
Ave Tunnel Overbreak:	20.0	em	<b>Drilling Blast Holes:</b>			
Tunnel Face Area:	(Includes Overbreak)	$m^2$	Hole Length:	3.9	m / Hole	
Crown Perimeter:	(Includes Overbreak)	m	Perim. Blast Hole Spacing:	0.50	m	
Wall & Crown Perimeter:	31.8 (Includes Overbreak)	m	Interior Blast Hole Spacing:	1.25	m	
Wall & Crown Area:	436,972 (Includes Overbreak)	$m^2$	No. Perimeter Holes:	64	No.	
Neat Tunnel Excav. Vol.:	1,649,458 (Includes Overbreak)	$m^3$	No. Interior Area Holes:	76.8	No.	
Re-Muck / Pull-Out Bays:			No. Blast Initiation Holes:	16	No.	
Bay Length:	10.0	m	Number of Drillholes / Blast:	156	Blastholes / Blast	
Spacing Bttn Bays:	1000.0	m	Blast Hole / Face Area Ratio:	1.30	Holes / m <sup>2</sup>	
Number of Bays:	13	No.	Typical / Check Ratio:	1.05	Holes / m <sup>2</sup>	
Total Length of Bays:	130.0	m	Drill Eqpt Set-Up Time:	40	min / Set-up	
Neat Excavation Vol.:	15,597	m <sup>3</sup>	Drill Penetration Rate:	0.30	m / Min	
Total Tunnel Volume:	1,665,055	$m^3$		18	m/hour	
Muck Bulking Factor:	1.6	Ratio	# of Drills or Booms:	6.0	No.	
Bulked Tunnel Volume:	2,664,089 (Loose Muck Volume)	m <sup>3</sup>	Charging & Blasting:			
	nary Mucking Production Details		Prime & Load Rate / Hole:	2.50	min / Blasthole	
·	ck from face to conveyor & muck cars)		Prep & Hook-up Time:	40.0	min / Set-up	
Muck Volume / Blast:	633.5	$m^3$	Total No. Blasts / Tunnel:	4205	No.	
Mucking Volume / Trip:	5.00	m <sup>3</sup>	Net Blast Break Length:	3.3	m / Blast	
Bucket Fill Factor (%):	90.0	%	Blast & Ventilation Time:	1.0	Hours	
Number of Trips:	141	No.		ntion Grouting De		
Ave. Dist. to Load:		m	% Tunnel to be Grouted:	12.0	%	
	* * * * * * * * * * * * * * * * * * * *					
Ave. Tramming Speed:	8.0	km/hr	Tunnel Length to Grout:	1650 <b>7.0</b>	m	
Load, Dump, Manoever:	1.0 (Time per Trip)	Min	Grout Hole Length:		m	
Face Cleanup / Blast:	15.0	Min	No. of Grouting Applications:	236	No.	
Mucking Time:	3.8	Hours	Perim. Grout Holes Spacing:	1.50	m	
Mucking Rate:	165.5	m <sup>3</sup> / Hour	# Perim. Grout Holes:	21	Holes / Grout Cycl	
-	Funnel Support Class Details		Drilling Penetration Rate:	50	m/hour	
Class I - No Support:	0.0 (%)	0 (m)	No. of Drill Booms:	2	No.	
Class II - Spot Bolts:	0.0 (%)	0 (m)	Drilling Time per Cycle:	350	Min	
Class III - Crown Only:	40.0 (%)	5,499 (m)	Grout Eqpt. Set-Up Time:	1.0	Hours / Grout Cycl	
Class IV - Full Pattern:	50.0 (%)	6,874 (m)	No. of Holes Grouted at Once:	2	Hoses	
Class V - Steel Sets:	<u>10.0</u> (%)	<u>1,375</u> (m)	Grouting Injection Rate:	10	min / Drillhole	
Total	100.0	13,748 (m)	Full Grout Cycle Time:	85.2	Hours	
	itial Shotcrete Support Details			Installation Detail	_	
Support Arc Length:	31.8	m	Steel Set Spacing:	1.0	m	
Thickness:	25.0	mm	Total No. Sets / Tunnel:	1,375	No.	
Volume / Round:	3.0	$m^3$	Ave. Installation Time / Set:	3.0	Hours	

Time: 0.8 (Includes Scaling & Equip Set-up) Hours

Total Installation Time:

4,124

Hours

Estimated by: \_\_\_\_\_PJP\_\_\_\_ Checked by: \_\_\_\_\_

Printed: 9:07 AM on 11/25/04 Page 8 of 12

_	Viremesh Installation Details	2	Rockl	oolt Support Class Deta	<u>ils</u>
Install Rate:	100	m <sup>2</sup> / Hour	(Bolts I		(Bolts Per Supp
Total Install Time:	4,817.6	Hours	Row		<u>Class)</u>
ve. Install Time:	68.7	Min	Class I:	0.0	0
verlap:	5	%	Class II: 0.0	0.0	0
et Applied Area:	436,972 (Assume Class V only)	m <sup>2</sup>	Class III: 6	4.0	21,997
rea with Overlap:	481,762	m <sup>2</sup>	Class IV: 15	10.0	68,740
<u>Final</u>	Shotcrete Support Class Details		Class V:	0.0	<u>0</u>
hotcrete Thickness:			Total:		90,737
Classes I and II:	0	mm		Face Scaling	
Class III:	0	mm	Scaling Time:	20.0	min / Blast
Classes IV:	50	mm	Rock	<u>kbolt Installation Detail</u>	<u>s</u>
Class V:	100	mm	Rockbolt Length:	3.0	m
upport Arc Length:			Row Spacing:	1.5	m
Class I:	0.0	m	No. Rockbolts Required:	90,737	No.
Class II:	0.0	m	Ave. Bolts / Round:	21.8	Bolts / Blast
Class III:	0.0	m	Drilled Length / Round:	65	m
Class IV:	31.8	m	Total Drilling Length:	272,210	m
Class V:	31.8	m	Drill Penetration Rate:	1.5	m / Min
	d Final Shotcrete Application Details		# of Drills / Booms Used:	3	No.
let Volume:	15,294	= m <sup>3</sup>	Ave. Drilling Time / Roun		Min
Rebound / Waste:	15	%	Bolt Install Rate	2.0	Min / Bolt
inal Layer Volume:	17,588	m <sup>3</sup>	Ave. Bolt Install Time:	43.6	Min
To. of Applications:	2416 (Required Per Bench)	No.	Drill Set-Up Time:	10.0	Min
Ave. Vol. / Application:	7.3	m <sup>3</sup>	Total Bolt Drill/Install Tir		Min
ourface Prep Time:	10.0	Min	Total Boit Di in/Instan Til	Drainhole Details	WIIII
Total Surface Prep Time:	24,163	Min	Drainhole Spacing:	3.0	m
=	24.0	m <sup>3</sup> / Hour		1.1	
Application Rate:		Min	Drainhole Length: Total Area:		m m <sup>2</sup>
Total Application Time:	43,970			218,486.1	
Eqpt. Setup Time:	20.0	Min	Total Drainholes:	24,276.2	# / Per Tunnel
Total Setup Time:	48,326 10.0 (Required Per Application)	Min	Total Length:	26,703.9	m 
Eqpt. Remove Time:		Min	Note: Activity carried out c		vities
Total Remove Time:	24,163	Min		on of Tunneling:	
Total Shotcreting Time:	140,623 (For Final Shotcrete Layer)		Pre-Exc. Grouting Time =	*	Hours
Equivalent Time / Blast:	33.4	Min / Cycle	_ Drilling Time =	26,567.2	Hours
	Secondary Mucking Details		Charge, Blast, Vent Time	*	Hours
Req'd during Tunneling:	No (No if loaded directly into truck		Primary Mucking Time =	16,098.5	Hours
Ave. LHD Tram Speed:	0.0	km / hour	Scaling Time =	4,205.8	Hours
	<u>ick Drain Installation Details</u>		Survey / Map Time =	2,102.7	Hours
Orain Spacing:	0.0	m	Install Steel Sets Time =	4,124.4	Hours
nstallation Time / Row:	0.0	Hours / Drain	Initial Shotcreting Time =	3,332.0	Hours
<u>Average</u>	Tunneling Productivity Cycle Details	<u>s</u>	Install Services Time =	2,102.7	Hours
			Rockbolting (of % Critica	l) = 1,431.5	Hours
Equiv. Pre-Exc. Grouting:	4.8	Hours	Non-Productive Time =	<u>2,102.7</u>	Hours
Orilling:	6.3	Hours			
Charging:	7.2	Hours	Total Time =	116,569.1	Hours
Blast & Venting:	1.0	Hours		160.1	Months
Aucking:	3.8	Hours	(Critical Path Tunneling	693.9	Weeks
caling:	0.3	Hours	Activities Only)	4,857.0	Days
urveying / Mapping:	0.5	Hours	Other Co	ncurrent Tunneling Act	•
nitial Shotcreting:	0.8	Hours			<del></del>
nstall Services:	0.5 (Equiv. Time Per Cycle)	Hours	Rockbolting (of % Not Critics	$a_{1} = 3,340.3$	Hours
instant Services.	0.5 (Travel in/out, Break)	Hours	Wiremesh Installation =	4,817.6	Hours
I I COUNTII I IIII C	, , , , , , , , , , , , , , , , , , ,	110010	Final Shotcreting Time =	0.6	Hours
neluda Roakhaltinas	Yes (Yes / No, as part of Cycle Tim	ie)	_		
nclude Rockbolting:			Drilling Drainholes =	17,802.6	Hours
f yes, % of Support Rq'd:		, , , , , , , , , , , , , , , , , , ,	Secondary Mucking =	0.0	Hours
Rockbolting:	0.3	Hours	Wick Drain Installation =	0.0	Hours
			<u>O</u>	verall Advance Rate:	
otal Cycle Time:	26.1	Hours		€ 2.8	m / Day m³ / Day
Total Cycle Time:	26.1	Hours	<u>o</u>	2.8	

Estimated by	y:PJP	
Checked b	y:	

Resource Type	Resource Name	Unit Rate	Unit	Quantity	Resource Quantity	Total
Labor						
	Miner - Shift Boss	50.68	\$/hr	116,569.1	2.00	11,815,445.90
	Miner - Operator - Journeyman	47.84	\$/hr	116,569.1	11.00	61,343,333.16
	Miner - Foreman	50.68	\$/hr	116,569.1	3.00	17,723,168.85
	Miner - Laborer - Journeyman	47.40	\$/hr	116,569.1	5.00	27,626,881.19
	Miner - Laborer - Apprentice	45.00	\$/hr	116,569.1	5.00	26,228,051.76
	Tunnel Electrician - Journeyman	47.84	\$/hr	116,569.1	4.00	22,306,666.60
Plant					30.00	167,043,547.46
	Cable - Fans & Pumps - High Voltage	120.00	\$/m	13,748.0	0.20	329,952.00
	Cable - Lights / Controls - Low Voltage	10.00	\$/m	13,748.0	0.80	109,984.00
	Compressor	121.77	\$/wk	693.9	1.00	84,494.50
	Conveyor - Heading Muck Loading	4,774.09	\$/wk	693.9	1.00	3,312,568.54
	Drill - Jack-Leg	77.49	\$/wk	693.9	4.00	215,076.91
	Drill Jumbo - Rail Mounted - 2 Boom	968.66	\$/wk	693.9	1.00	672,115.36
	Drill Jumbo - Rail Mounted - 3 Boom	2,767.59	\$/wk	693.9	1.00	1,920,329.59
	Excavator - Rail Mounted	304.43	\$/wk	693.9	1.00	211,236.26
	Generator - Back-Up - 500KW	290.60	\$/wk	693.9	1.00	201,634.61
	Generator - Working - 1000KW	2,169.79	\$/wk	693.9	1.00	1,505,538.40
	Grout Plant-Consol-D&B-Pump, Hoses	182.66	\$/wk	693.9	1.00	126,741.75
	Lighting (Including Consumables)	7.50	\$/m	13,748.0	1.00	103,110.00
	Locomotive - Diesel - 16T	5,000.00	\$/wk	693.9	4.00	13,877,276.07
	LHD Loader - D&B Tunnel	928.53	\$/wk	693.9	1.00	644,270.58
	Manlift / Platform - Rail Mounted	405.91	\$/wk	693.9	1.00	281,648.34
	Pipe - 50mm (Water Supply)	7.50	\$/m	13,748.0	1.00	103,110.00
	Pipe - 100mm (Air Supply)	15.00	\$/m	13,748.0	1.00	206,220.00
	Rail - 80 lb/yd - Used	101.54	\$/m	27,896.0	0.60	1,699,510.15
	Rail - California Switch Gear	75,000.00	\$/Nr	1.0	3.00	225,000.00
	Rail Car - Flat	50,000.00	\$/Nr	1.0	3.00	150,000.00
	Rail Car - Man Rider	50,000.00	\$/Nr	1.0	1.00	50,000.00
	Rail Car - Muck Cars	1,900.00	\$/wk	693.9	18.00	23,730,142.07
	Rail Car - Muck Car Tipping System	75,000.00	\$/Nr	1.0	1.00	75,000.00
	Shotcrete Machine - Rail Mounted	445.58	\$/wk	693.9	1.00	309,173.06
	Shotcrete Machine - Tire Mounted	721.42	\$/wk	693.9	2.00	1,001,131.83
	Small Tools	200.00	\$/wk	693.9	1.00	138,772.76
	Tie Plates, Splice Bars, Bolts	150,000.00	LS	1.0	1.00	150,000.00
	Ties - Wooden - Untreated - 7" x 9" x 40"	23.00	\$/m	13,748.0	1.00	316,204.00
	Transformers & Switchgear - High Voltage	202.96	\$/wk	693.9	1.00	140,824.17
	Transformers-Switch gear-Low Voltage	101.48	\$/wk	693.9	1.00	70,412.09
	Ventilation Duct - Rigid	110.00	\$/m	13,748.0	1.00	1,512,280.00
	Ventilation Fans - 75HP	57.29	\$/wk	693.9	7.00	278,255.76
	Welder (Plant)	6.37	\$/wk	693.9	1.00	4,416.76
						53,756,429.56
Consumables	Dis D. L. LG Dist	4.5.00	<b>.</b>	1.665.055	1.00	24.055.000.5
	Bits, Powder and Caps - Blasting	15.00	\$/m3	1,665,055.4	1.00	24,975,830.85
	Bits - (Drainholes & Rockbolts)	5.00	\$/m	298,914.3	1.00	1,494,571.27
	Drill Jumbo Maintenance	100.00	\$/hr	25,266.3	1.00	2,526,627.68
	Electricity - Tunnel Heading Conveyor	0.22	\$/kwh	150	1,051.36	34,695.00
	Electricity - Fans & Lighting	0.22	\$/kwh	433	58,284.56	5,548,807.71
	Electricity - Jumbo	0.22	\$/kwh	75	25,266.28	416,893.57
	Lubricants	2,500.00	\$/wk	693.9	1.00	1,734,659.51
	Fuels & Lubricants	5,000.00	\$/wk	693.9	1.00	3,469,319.02
	Other Consumables	1,500.00	\$/wk	693.9	1.00	1,040,795.70
					Estimated by:	PJP

Printed: 9:07 AM on 11/25/04 Page 10 of 12

Resource Type Resource Name Unit Rate Unit Quantity Resource Quantity Total

\$ 41,242,200.30

Estimated by: \_\_\_\_\_PJP\_\_\_\_ Checked by: \_\_\_\_

Printed: 9:07 AM on 11/25/04 Page 11 of 12

Resource Type	Resource Name	Unit Rate	Unit	Quantity	Resource Quantity	Total
Materials						
	Grout - Consolidation	50.00	\$/m3	2,000.0	1.00	100,000.00
	Other Materials	2,000.00	\$/wk	693.9	1.00	1,387,727.61
	Rock Bolts - No.10 - 3.0m - (Non-Galv)	40.00	\$/Nr	90,737	1.00	3,629,472.00
	Shotcrete	180.00	\$/m3	17,588.1	1.00	3,165,863.32
	Steel Sets - W10 x 65	152.75	\$/m	1,375	31.78	6,674,749.78
	Synthetic Wick Drains	5.00	\$/m	0	1.00	-
	WWF mesh	5.50	\$/m2	481,762	1.00	2,649,689.95
						\$ 14,857,812.70
Subcontracts						
	Tunnel Muck - Miscl Surface Handling	20.00	\$/m3	2,664,088.62	1.00	53,281,772.48
						\$ 53,281,772.48

Total Estimated Cost: \$ 330,181,762.51

**Per Meter:** \$ 24,016.71 **Per m<sup>3</sup>:** \$ 198.30

> Estimated by: \_\_\_\_PJP\_\_\_\_ Checked by: \_\_\_\_


Printed: 9:07 AM on 11/25/04 Page 12 of 12

#### Newfoundland Fixed Link Bridge Option Cost Estimate

#### **Unit Costs**

Suspension Bridge \$ 5,000 /m2 (Rate includes piers & deck)
Substructure Piers Protection \$ 260,000,000 /pier

#### Quantities



Bridge Area= 160,000 m2

Bridge Piers 8 Nr.

#### **Construction Costs**

	Unit	Qty	\$-Rate	\$ - Cost
Suspension Bridge	m2	160,000	5,000	800,000,000
Substructure Piers Protection	Ea	8	260,000,000	2,080,000,000
			Sub-total	2,880,000,000
		25%	Contingency	720,000,000
			Total	3,600,000,000

#### **Pre-Construction and Supervision**

•	Unit	Qty	\$-Rate	\$ - Cost
Feasibility Study	LS	1	11,000,000	11,000,000
<b>Environmental Assessment</b>	LS	1	4,000,000	4,000,000
Design	5%	1	180,000,000	180,000,000
Construction Management	10%	1	360,000,000	360,000,000
Owners Costs	2%	1	72,000,000	72,000,000
				627 000 000


GRAND TOTAL 4,227,000,000

#### **Newfoundland Fixed Link Bridge/Causeway Option Cost Estimate**

#### **Unit Costs**

Suspension Bridge	\$ 5,000	/m2	
Bridge Approach	\$ 2,500	/m2	
Substructure Piers Protection	\$ 260,000,000	/pier	
Fill from shore	\$ 15	/m3	
Fill from barge	\$ 50	/m3	
Large armour stone from shore	\$ 100	/m3	wave zone armour stone
Large armour stone from barge	\$ 200	/m3	wave zone armour stone
Small armour stone from shore	\$ 50	/m3	iceberg zone armour stone
Small armour stone from barge	\$ 100	/m3	iceberg zone armour stone

#### Quantities



00. 0		, o. ago				
		Тор	Slope	Embankment	Calculated	
Section	Length(m)	Width(m)	(1:X)	Depth(m)	Volume (m3)	
1	3800	15	1.8	90	60,534,000	
3	4700	15	1.8	90	74,871,000	
•	135,405,000 m3					

Average

Rockfill from barge			Average			
		Тор	Slope	Embankment	Calculated	
Section	Length(m)	Width(m)	(1:X)	Depth(m)	Volume (m3)	
2	5600	15	1.8	80	71,232,000	
			Total	rockfill from barge	71,232,000 m3	

Large armour stone from shore

		Wave			
		Protection	Armour	Slope	Calculated
Section	Length(m)	Depth(m)	Thickness(m)	(1:X)	Volume (m3)
1	3800	20	2.2	1.8	688,572
3	4700	20	2.2	1.8	851,655
<u>-</u>			Large armou	1,540,226 m3	

## Quantities contd.

Large armour :	stone	from	barge
----------------	-------	------	-------

ur stone fro	om barge				
		Wave			
		Protection	Armour	Slope	Calculated
Section	Length(m)	Depth(m)	Thickness(m)	(1:X)	Volume (m3)
2	5600	20	2.2	1.8	1,014,737
•			Large armour	r stone from barge	1,014,737 m3

## Small armour stone from shore

		Iceberg			
		Protection	Armour	Slope	Calculated
Section	Length(m)	Depth(m)	Thickness(m)	(1:X)	Volume (m3)
1	3800	60	1	1.8	938,961
3	4700	60	1	1.8	1,161,347
•			Small armour	stone from shore	2,100,309 m3

## Small armour stone from barge

		Wave			
		Protection	Armour	Slope	Calculated
Section	Length(m)	Depth(m)	Thickness(m)	(1:X)	Volume (m3)
2	5600	50	1	1.8	1,153,111
' <u>-</u>			Small armour	stone from barge	1,118,000 m3

## **Construction Costs**

Construction Costs				
	Unit	Qty	\$-Rate	\$ - Cost
Suspension Bridge	m2	40,000	5,000	200,000,000
Bridge approaches	m2	10,000	2,500	25,000,000
Substructure Piers Protection	Ea	2	260,000,000	520,000,000
Causeway Fill from Shore	m3	135,405,000	15	2,031,075,000
Causeway Fill in Channel	m3	71,232,000	50	3,561,600,000
Large armour stone from shore	m3	1,540,226	100	154,022,627
Large armour stone from barge	m3	1,014,737	200	202,947,461
Small armour stone from shore	m3	2,100,309	50	105,015,427
Small armour stone from barge	m3	1,118,000	100	111,800,000
			Sub-total	6,911,460,516
		25%	Contingency	1,727,865,129
			Total	8,639,325,645
Pre-Construction and Supervision			_	
•	Unit	Qty	\$-Rate	\$ - Cost
Feasibility Study	LS	1	11,000,000	11,000,000
Farmanantal Assessment	1.0	4	4 000 000	4 000 000

# Ρ

			-	1,483,685,360
Owners Costs	2%	1	172,786,513	172,786,513
Construction Management	10%	1	863,932,564	863,932,564
Design	5%	1	431,966,282	431,966,282
Environmental Assessment	LS	1	4,000,000	4,000,000
Feasibility Study	LS	1	11,000,000	11,000,000
	Unit	Qty	\$-Rate	\$ - Cost

<b>GRAND TOTAL</b>	10,123,011,004
0.0.0.0	, , ,


Newfoundland Fixed Link Pre-feasibility Study Tunnel Drainage Bored Railway Tunnel Drainage Costs

# Page 1 of 1

Calculation by: ANW

**Date:** June 8, 2004

## **Sump Sizing**



# **Piping**

Assume 300 mm diameter steel pipe connecting each sump to the portal areas

Number of pipes= 1

Assume sumps located at 1/3 and 2/3 of tunnel length

Total length of piping= 18967 m

### **Rates**

Sump construction-\$ 17795 /m of sump

Pipe-\$ 265 /m of pipe

Pipe installation labour -\$ 29 /m of pipe (assume 6 man crew installing 100m/day)
Pipe installation equipment-\$ 10 /m of pipe (assume \$1000/day for equipment)

Pumps-\$ 125000 /pump

#### Costs

Item	Unit	Qty	Rate	\$-Cost
Sump construction	m	88	17795	1,565,960
Pipe	m	18967	265	5,026,167
Pipe installation	m	18967	29	546,240
Equipment	m	18967	10	189,667
Pumps	Nr	4	125000	500,000
			Total	7,828,033



## Newfoundland Fixed Link Pre-feasibility - TBM Bored Railway Tunnel - Cost Summary

	ROPED TIII	NNEL CONSTRUCTION COSTS
ITEM		MAIN TUNNEL
MODILIZATION & DEMODILIZATION	UNIT LS	8,000,000
MOBILIZATION & DEMOBILIZATION		· ·
TUNNELLING	LS	356,357,000
TUNNEL FINISHES	LS	75,539,979
NORTH APPROACH STRUCTURES	LS	7,770,000
SOUTH APPROACH STRUCTURES	LS	8,150,000
RAIL TRACK	LS	13,923,100
TUNNEL DRAINAGE	LS	7,820,000
UTILITY DIVERSIONS	LS	1,000,000
MONITORING	LS	1,000,000
SUBTOTAL CIVIL		\$479,560,079
CIVIL CONTINGENCIES		
CONTINGENCY	40%	\$191,824,032
TOTAL CIVIL		\$671,384,111
		RAIL HARDWARE AND FINISHING WORK
ROLLING STOCK, TERMINALS, OCS, ETC	LS	\$48,000,000
VENTILATION EQUIPMENT	LS	\$3,000,000
VENTILATION SHAFTS AND BUILDINGS x 2	LS	\$0
FIRE SUPPRESSION SYSTEM	LS	\$2,000,000
CONTROL CENTRE	LS	\$1,000,000
SIGNALLING	LS	\$1,000,000
LIGHTING	LS	\$1,000,000
CCTV SYSTEM	LS	\$0
GAS DETECTION	LS	\$900,000
SUBSTATION, GENERATORS, UPS	LS	\$2,000,000
SUBTOTAL M&E AND FINISHING		\$58,900,000
CONTINGENCIES	20%	\$11,780,000
TOTAL M&E AND FINISHING		\$70,680,000
TOTAL CIVIL, M&E AND FINISHING		\$742,064,111
ALL OWANGES		
ALLOWANCES		
CONTRACTOR OH	15%	\$111,309,617
CONTRACTOR PROFIT	15%	\$111,309,617
CONSTRUCTION TOTAL		\$965,000,000
	PRE-CONS	TRUCTION AND SUPERVISION
FEASIBILITY STUDY	LS	\$11,000,000
ENVIRONMENTAL ASSESSMENT	LS	\$4,000,000
DESIGN	5%	\$48,250,000
CONSTRUCTION MANAGEMENT	10%	\$96,500,000
OWNERS COSTS	2%	\$19,300,000
PRE-CONSTRUCTION TOTAL		\$179,050,000
CRAND TOTAL		A4 444 0F0 000
GRAND TOTAL		\$1,144,050,000

Hatch Mott MacDonald	Newfoundland Fixed Link Pre-feasibility - TBM Bored Railway Tunnel Civil Costs					
ITEM	UNIT	QTY	RATE	TOTAL		
MOBILIZATION	LS	1.00	\$8,000,000	\$8,000,000		
TUNNELLING						
- TBM ∣aunch shaft	LS	1.00	\$0	\$0		
- Set-up TBM	LS	1.00	\$737,000	\$737,000		
- Tunnel drive	LS	1.00	\$350,470,000	\$350,470,000		
- TBM maintenance	LS	1.00	\$960,000	\$960,000		
- Remove TBM	LS	1.00	\$406,000	\$406,000		
- Clean tunnel	LS	1.00	\$3,784,000	\$3,784,000		
- Structural finishes	LS	1.00	\$75,539,979	\$75,539,979		
- TBM reception shaft	LS	1.00	\$0	\$0		
NORTH APPROACH STRUCTURES						
- Cut and cover approach	LS	1.00	\$7,770,000	\$7,770,000		
SOUTH APPROACH STRUCTURES						
- cut and cover approach	LS	1.00	\$8,150,000	\$8,150,000		
DRAINAGE						
Drainage sumps and piping	LS	1.00	\$7,820,000	\$7,820,000		
RAIL TRACK						
- bored tunnel	m2	40,050.00	\$20	\$801,000		
- north approach	m2	31,150.00	\$20	\$623,000		
- south approach	m2	1,602.00	\$30	\$48,060		
_						

\$465,109,039

SUB-TOTAL



Version 2.6 Copyright Hatch Mott MacDonald, 2004

Project: Newfoundland Fixed Link Pre-feasibility Study

**Estimate Description:** Set-up TBM

Tunnel Name: Single Rail Bored
Construction Activity: Erect TBM Only

Tunnel Technique: EPB TBM - Precast segmental

**Estimate Definition ID: 2636** 

**Estimate Definition ID:** 

2636

Printed by: whit2782, 8/16/04 11:42:50 AM

**Project Number:** 213789

Parent Estimate ID: 1563

Project Phase: Conceptual

Geology Type: Not

Not Applicable

**Estimate Date:** 

May 31, 2004

**Tunnel Characteristics ID: 843** 

#### **Tunnel Characteristics**

Finished Diameter: 7.5 m

#### **Activity Details**

**Shift Arrangement** 3 - 8 hour shifts x 7 days per week

**Duration of Activity** 

4.5 Weeks

**Total Number of Shifts** 

94.5

Estimated by:

Checked by:

	Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Tota
Labor						
	Pit boss	52.29	\$/hr	756.00	1.00	39,53
	Tunnel miner	48.89	\$/hr	756.00	2.00	73,922
	Shaft bottom	48.44	\$/hr	756.00	3.00	109,862
	Tunnel fitter	49.34	\$/hr	756.00	1.00	37,30
	Tunnel electrician	49.34	\$/hr	756.00	1.00	37,30
	Shaft top	47.99	\$/hr	756.00	1.00	36,280
	Crane operator	49.34	\$/hr	756.00	2.00	74,602
	Surface laborer	47.99	\$/hr	756.00	1.00	36,28
	Equipment laborer	48.44	\$/hr	756.00	1.00	36,62
					13.00	\$481,701
Plant						
	Loco	5,000.00	\$/wk	4.50	1.00	22,50
	Muck cars & grout cars	1,900.00	\$/wk	4.50	6.00	51,30
	Flat cars	310.00	\$/wk	4.50	2.00	2,79
	Transformers & switchgear - LV	750.00	\$/wk	4.50	1.00	3,37
	Small tools	2,600.00	\$/wk	4.50	1.00	11,70
	Shaft crane	9,000.00	\$/wk	4.50	1.00	40,50
	Erection crane	10,000.00	\$/wk	4.50	1.00	45,00
	Compressors	950.00	\$/wk	4.50	1.00	4,27
	Generators	2,000.00	\$/wk	4.50	1.00	9,00
	Transformers & switchgear - HV	5,200.00	\$/wk	4.50	1.00	23,40
	Loaders	2,300.00	\$/wk	4.50	1.00	10,35
						\$224,190
Consun	nables					
	Electrical power	0.00	\$/kwh	756.00	300.00	
	Gas oil	0.00	\$/L	0.00	1.00	

Page 1 of 2

Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Lubrication materials	0.00	\$/wk	4.50	1.00	0
Filters etc.	0.00	\$/wk	4.50	1.00	0
Hydraulic oil	0.00	<b>\$</b> /L	0.00	1.00	0
Other consumables	0.00	\$/wk	4.50	1.00	0
					\$0
Materials					
Temporary materials	2,000.00	\$/wk	4.50	1.00	9,000
Thrust frame	5,000.00	\$/wk	4.50	1.00	22,500
					\$31,500
		To	tal Estimated C	ost:	\$737,391

Estimate Definition ID: 2636

Printed by: whit2782, 8/16/04 11:42:50 AM

Page 2 of 2

Checked by:



Version 2.6

Copyright Hatch Mott MacDonald, 2004

Project: Newfoundland Fixed Link Pre-feasibility Study

Tunnel drive **Estimate Description:** Single Rail Bored **Tunnel Name: Construction Activity:** TBM Tunneling

**Tunnel Technique:** EPB TBM - Precast segmental

**Estimate Definition ID:** 

**Project Number:** 213789

**Parent Estimate ID:** 1559

**Project Phase:** Conceptual

Geology Type:

Not Applicable

**Estimate Date:** 

May 21, 2004

**Tunnel Characteristics ID: 843** 

#### **Tunnel Characteristics**

26,322 m **Tunnel Length:** 7.5 m **Finished Diameter:** 

Initial Support Type: Pre-cast concrete segments

**Initial Support Thickness:**  $0 \, \mathrm{m}$ 

0.35 m **Final Lining Thickness:** 

> **Grout Thickness:** 0.1 m

#### **Theoretical Excavation Volumes**

Final Lining Volume:

**Total Neat Excavation:** 1,458,703 Cubic Metres

0 Cubic Metres **Initial Lining Volume:** 

**Theoretical Grout Volume:** 68,635 Cubic Metres

### Normal Excavation/Support Cycle

1.5 Metres **Excavation Cycle Length:** 

24 Minutes Excavate: 27 Minutes **Erect Support: Extend Services:** 0 Minutes

**Total Cycle Time:** 51 Minutes **Difficult Excavation/Support Cycle** 

1400 Metres Length of Difficult Excavation:

**Excavate:** 73 Minutes **Erect Support:** 54 Minutes **Extend Services:** 0 Minutes

**Total Cycle Time:** 127 Minutes

#### **Reduction Factors**

Machine availability: 80 % Back up efficiency: 55 % 5 % Planned maintenance: 40 % Learning curve efficiency:

8 Weeks Learning curve duration time:

**Learning Curve Rate: Experienced Advance Rate:**  7.1 m/day

m/day

Days

56

17.7

227,199 Cubic Metres

**Difficult Advance Rate:** 7.1 m/day

## TBM Skidding Through Excavation

**Duration of skidding:** 

0 Weeks

Metres

Length of skidding: 0 Metres

## **Advance Rate and Shift Details**

**Shift Arrangement:** 3 - 8 hour shifts x 7 days per week

Avg. Drive Advance per Shift: 5.36 Metres 16 Metres Avg. Drive Advance per Day: Avg. Drive Advance per Week: 112 Metres **Duration of Tunneling (Incl. Skid):** 234.04 Weeks

Total number of shifts (Incl. Skid): 4,915

397 **Learning Curve Drive:** 24,525

1,385 **Experienced Drive:** 1,400 197 **Difficult Drive:** 0 0 **Skidding Portion:** 

**Estimate Definition ID:** 2637

Estimated by:

Printed by: whit2782, 8/16/04 11:43:27 AM

Page 1 of 3

Checked by:

	Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Labor						
	Pit boss	52.29		39,322.00	1.00	2,056,147
	Working foreman	52.29	\$/hr	39,322.00	2.00	4,112,295
	Tunnel miner	48.89	\$/hr	39,322.00	3.00	5,767,358
	Tunnel laborer	48.44	\$/hr	39,322.00	4.00	7,619,031
	Loco driver	49.34	\$/hr	39,322.00	5.00	9,700,737
	Shaft bottom	48.44	\$/hr	39,322.00	1.00	1,904,758
	TBM operator	49.34	\$/hr	39,322.00	1.00	1,940,147
	Tunnel fitter	49.34	\$/hr	39,322.00	1.00	1,940,147
	Tunnel electrician	49.34	\$/hr	39,322.00	1.00	1,940,147
	Shaft top	47.99	\$/hr	39,322.00	2.00	3,774,126
	Crane operator	49.34	\$/hr	39,322.00	1.00	1,940,147
	Surface laborer	47.99	\$/hr	39,322.00	4.00	7,548,251
	Equipment laborer	48.44	\$/hr	39,322.00	4.00	7,619,031
DI 4					30.00	\$57,862,323
Plant	TBM	300,000.00	\$/m2	55.42	0.80	13,300,800
	TBM backup	1,430,000.00		1.00	1.00	1,430,000
	Loco	5,000.00		234.04	5.00	5,851,000
	Muck cars & grout cars	1,900.00		234.04	35.00	15,563,660
	Flat cars	310.00		234.04	10.00	725,524
	Manriders	310.00		234.04	2.00	145,105
	Track	130.00		26,322.00	1.00	3,421,860
	Air pipe	30.00		26,322.00	1.00	789,660
	Water pipe	25.00		26,322.00	1.00	658,050
	Pump main	50.00		26,322.00	1.00	1,316,100
	Cabling	80.00		26,322.00	1.00	2,105,760
	Lighting	30.00		26,322.00	1.00	789,660
	Vent ducting	30.00		26,322.00	1.00	789,660
	Grout mixers	7,100.00		234.04	1.00	1,661,684
	Grout pumps	3,400.00		234.04	1.00	795,736
	Grout hoses & pipes	196.00		234.04	2.00	91,744
	Transformers & switchgear - LV	750.00		234.04	2.00	351,060
	Small tools	2,600.00		234.04	1.00	608,504
	Shaft crane	9,000.00		234.04	1.00	2,106,360
	Compressors	950.00		234.04	1.00	222,338
	•					
	Low pressure C/A system	3,800.00 655.00		234.04	1.00	889,352 306,592
	Pipework and controls			234.04	2.00	306,592
	Generators Transformers & quitabaser LIV	2,000.00		234.04	1.00	468,080
	Transformers & switchgear - HV	5,200.00		234.04	1.00	1,217,008
	Surface fans	800.00		234.04	2.00	374,464
	Loaders	2,300.00		234.04	2.00	1,076,584
	Other surface plant	2,600.00	\$/WK	234.04	1.00	608,504
Estimate 1	<b>Definition ID:</b> 2637			Estimated	by:	

Page 2 of 3

Checked by:

Printed by: whit2782, 8/16/04 11:43:27 AM

Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total	
Tunnel C/A system	40,000.00	\$/wk	234.04	1.00	9,361,600	
					\$67,026,449	
Consumables						
Electrical power	0.10	\$/kwh	39,322.00	3,000.00	11,796,600	
Gas oil	0.45	<b>\$</b> /L	48,000.00	1.00	21,600	
Lubrication materials	90.00	\$/wk	234.04	1.00	21,064	
TBM spares, cutters	250.00	\$/m	26,322.00	1.00	6,580,500	
Filters etc.	300.00	\$/wk	234.04	1.00	70,212	
Hydraulic oil	0.90	<b>\$</b> /L	32,000.00	1.00	28,800	
Other consumables	160.00	\$/wk	234.04	1.00	37,446	
Tail seal grease	100.00	\$/m	26,322.00	1.00	2,632,200	
					\$21,188,422	
Materials						
Concrete lining rings	8,300.31	\$/Nr	17,548.00	1.00	145,653,824	
Gaskets	130.00	\$/m	26,322.00	1.00	3,421,860	
Bolts	12.00	\$/Nr	1,765.00	30.00	635,400	
Grout	145.00	\$/m3	68,635.00	1.00	9,952,075	
Grout plugs	0.50	\$/Nr	1,765.00	7.00	6,178	
Packers	10.00	\$/Nr	3,633.00	12.00	435,960	
Temporary materials	2,250.00	\$/wk	234.04	1.00	526,590	
Other materials	0.00	<b>\$</b> /t	0.00	1.00	0	
					\$160,631,886	
Subcontracts						
Soil disposal	20.00	\$/m3	1,458,703.00	1.50	43,761,090	
					\$43,761,090	
		Т	Total Estimated Co	ost:	\$350,470,170	
	Total Estimated Cost per Metre:					
	T	otal Estin	ated Cost per We	ek:	\$1,497,491	
Total Estimated Cost per Shift:						

Estimate Definition ID: 2637

Printed by: whit2782, 8/16/04 11:43:28 AM

Page 3 of 3

Checked by:



Version 2.6

Copyright Hatch Mott MacDonald, 2004

Project: Newfoundland Fixed Link Pre-feasibility Study

**Estimate Description:** Maintain TBM

Tunnel Name: Single Rail Bored
Construction Activity: TBM Maintenance

**Tunnel Technique:** EPB TBM - Precast segmental

**Estimate Definition ID: 2638** 

**Project Number:** 213789

Parent Estimate ID: 1561

Project Phase: Conceptual

Geology Type: Not Applicable

Estimate Date: May 21, 2004

**Tunnel Characteristics ID:** 843

#### **Tunnel Characteristics**

Finished Diameter: 7.5 m

#### **Activity Details**

**Shift Arrangement** 1 - 6 hour shifts x 1 days per week

**Duration of Activity** 234 Weeks

Total Number of Shifts 234

Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Working foreman	52.29	\$/hr	1,404.00	1.50	110,123
Loco driver	49.34	\$/hr	1,404.00	1.50	103,910
Shaft bottom	48.44	\$/hr	1,404.00	1.50	102,015
TBM operator	49.34	\$/hr	1,404.00	1.50	103,910
Tunnel fitter	49.34	\$/hr	1,404.00	1.50	103,910
Tunnel electrician	49.34	\$/hr	1,404.00	1.50	103,910
Shaft top	47.99	\$/hr	1,404.00	1.50	101,067
Surface laborer	47.99	\$/hr	1,404.00	1.50	101,067
				12.00	\$829,911
nables					
Electrical power	0.10	\$/kwh	1,404.00	600.00	84,240
Gas oil	0.45	\$/L	0.00	1.00	(
Other consumables	0.00	\$/wk	234.00	1.00	(
					\$84,240
lls					
Temporary materials	200.00	\$/wk	234.00	1.00	46,800
Other materials	0.00	<b>\$</b> /t	0.00	1.00	(
					\$46,800
	Working foreman Loco driver Shaft bottom TBM operator Tunnel fitter Tunnel electrician Shaft top Surface laborer  nables Electrical power Gas oil Other consumables  Ils Temporary materials	Working foreman 52.29 Loco driver 49.34 Shaft bottom 48.44 TBM operator 49.34 Tunnel fitter 49.34 Tunnel electrician 49.34 Shaft top 47.99 Surface laborer 47.99  nables Electrical power 0.10 Gas oil 0.45 Other consumables 0.00	Working foreman Loco driver Shaft bottom 48.44 \$/hr TBM operator 49.34 \$/hr Tunnel fitter 49.34 \$/hr Tunnel electrician 49.34 \$/hr Shaft top 47.99 \$/hr Surface laborer 47.99 \$/hr Gas oil 0.45 \$/L Other consumables  Temporary materials 200.00 \$/wk	Resource Name         Unit Rate UOM         Quantity           Working foreman         52.29 \$/hr         1,404.00           Loco driver         49.34 \$/hr         1,404.00           Shaft bottom         48.44 \$/hr         1,404.00           TBM operator         49.34 \$/hr         1,404.00           Tunnel fitter         49.34 \$/hr         1,404.00           Tunnel electrician         49.34 \$/hr         1,404.00           Shaft top         47.99 \$/hr         1,404.00           Surface laborer         47.99 \$/hr         1,404.00           nables           Electrical power         0.10 \$/kwh         1,404.00           Gas oil         0.45 \$/L         0.00           Other consumables         0.00 \$/wk         234.00           als         200.00 \$/wk         234.00	Resource Name         Unit Rate UOM         Quantity         Quantity           Working foreman         52.29 \$/hr         1,404.00         1.50           Loco driver         49.34 \$/hr         1,404.00         1.50           Shaft bottom         48.44 \$/hr         1,404.00         1.50           TBM operator         49.34 \$/hr         1,404.00         1.50           Tunnel fitter         49.34 \$/hr         1,404.00         1.50           Tunnel electrician         49.34 \$/hr         1,404.00         1.50           Shaft top         47.99 \$/hr         1,404.00         1.50           Surface laborer         47.99 \$/hr         1,404.00         1.50           12.00           nables           Electrical power         0.10 \$/kwh         1,404.00         600.00           Gas oil         0.45 \$/L         0.00         1.00           Other consumables         0.00 \$/wk         234.00         1.00           Is         1.00         1.00         1.00

**Total Estimated Cost:** \$960,951

Estimate Definition ID: 2638 Estimated by:

Printed by: whit2782, 8/16/04 11:43:51 AM Page 1 of 1 Checked by:



Version 2.6

Copyright Hatch Mott MacDonald, 2004

**Project:** Newfoundland Fixed Link Pre-feasibility Study

Estimate Description: Clean tunnel
Tunnel Name: Single Rail Bored

Construction Activity: Tunnel Clean Up

Tunnel Technique: EPB TBM - Precast segmental

**Estimate Definition ID:** 2639

Project Number: 213789

Parent Estimate ID: 1562

Project Phase: Conceptual

Geology Type: Not Applicable

Estimate Date: May 21, 2004

**Tunnel Characteristics ID: 843** 

### **Tunnel Characteristics**

Tunnel Length: 26,322 m

Finished Diameter: 7.5 m (Circular Tunnels)

Excavated Cross Section: 0 m2 (Non-circular Tunnels)

Excavated Perimeter: 0 m (Non-circular Tunnels)

## Productivity Cycle Reduction Factors

Section Length30 MetresLearning Curve Efficiency:50 %Vent Line Removal Time120 MinutesBack Up Efficiency:80 %Track Removal Time60 MinutesLearning Curve Duration:1 Weeks

**Temp Lighting Removal Time** 60 Minutes

Clean Up Time 120 Minutes

**Total Cycle Time**Shift Arrangement: 3 - 8 hour shifts x 7 days per week

Avg. Advance per Shift:31.58 MetresAvg. Advance per Week:664 Metres

**Shift Details** 

**Total number of hours:** 6,669

### Clean Up Productivity Data

	Average Advance Drive Length		<b>Drive Duration</b>			
Learning Curve Portion:	48.0 m/day	336 Metres	21 Shifts	7 Days	1.00 Weeks	
Experienced Drive Portion:	96.0 m/day	25,986 Metres	812 Shifts	271 Days	38.67 Weeks	
Total:	94.8 m/day	26,322 Metres	834 Shifts 2	278 Days	39.67 Weeks	

	Resource Name	Unit Rate UO	Unit OM Quantity	Resource Quantity	Total
Labor					
	Tunnel laborer	48.44 \$/hı	r 6,668.00	6.00	1,937,988
	Shaft bottom	48.44 \$/hi	r 6,668.00	1.00	322,998
	Shaft top	47.99 \$/hı	r 6,668.00	1.00	319,997
	Crane operator	49.34 \$/hi	r 6,668.00	1.00	328,999
				9.00	\$2,909,982
Plant					
	Transformers & switchgear - LV	750.00 \$/w	yk 39.67	1.00	29,753

Estimate Definition ID: 2639 Estimated by:

Printed by: whit2782, 8/16/04 11:44:17 AM Page 1 of 2 Checked by:

Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Man hoists	2,600.00	\$/wk	39.67	1.00	103,142
Shaft crane	9,000.00	\$/wk	39.67	1.00	357,030
Compressors	950.00	\$/wk	39.67	1.00	37,687
Loaders	2,260.00	\$/wk	39.67	1.00	89,654
Other surface plant	2,600.00	\$/wk	39.67	1.00	103,142
Bobcat	500.00	\$/wk	39.67	1.00	19,835
					\$740,242
Consumables					
Electrical power	0.10	\$/kwh	6,668.00	200.00	133,360
					\$133,360
	Total Estimated Cost:				
	To	\$144			
	To	\$95,377			
	Т	otal Estima	ited Cost per Sh	ift:	\$4,539

Estimate Definition ID: 2639

Printed by: whit2782, 8/16/04 11:44:18 AM

Page 2 of 2

Checked by:



Version 2.6 Copyright Hatch Mott MacDonald, 2004

Project: Newfoundland Fixed Link Pre-feasibility Study

**Estimate Description:** Remove TBM

Tunnel Name: Single Rail Bored
Construction Activity: TBM Removal

Tunnel Technique: EPB TBM - Precast segmental

**Estimate Definition ID: 2640** 

**Estimate Definition ID:** 

2640

Printed by: whit2782, 8/16/04 11:44:45 AM

**Project Number:** 213789

Parent Estimate ID: 1564

Project Phase: Conceptual

Geology Type: Not Applicable

Estimate Date: May 21, 2004

**Tunnel Characteristics ID: 843** 

Estimated by:

Checked by:

#### **Tunnel Characteristics**

Finished Diameter: 7.5 m

### **Activity Details**

**Shift Arrangement** 3 - 8 hour shifts x 7 days per week

**Duration of Activity** 2.2 Weeks

**Total Number of Shifts** 46.2

	Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Labor						
	Pit boss	52.29	\$/hr	370.00	1.00	19,347
	Tunnel miner	48.89	\$/hr	370.00	3.00	54,268
	Shaft bottom	48.44	\$/hr	370.00	2.00	35,846
	Tunnel fitter	49.34	\$/hr	370.00	1.00	18,256
	Tunnel electrician	49.34	\$/hr	370.00	1.00	18,256
	Shaft top	47.99	\$/hr	370.00	2.00	35,513
	Crane operator	49.34	\$/hr	370.00	2.00	36,512
	Surface laborer	47.99	\$/hr	370.00	2.00	35,513
	Equipment laborer	48.44	\$/hr	370.00	1.00	17,923
					15.00	\$271,432
Plant						
	Loco	5,000.00	\$/wk	2.20	1.00	11,000
	Muck cars & grout cars	1,900.00	\$/wk	2.20	6.00	25,080
	Flat cars	310.00	\$/wk	2.20	4.00	2,728
	Manriders	310.00	\$/wk	2.20	1.00	682
	Booster fans	800.00	\$/wk	2.20	1.00	1,760
	Transformers & switchgear - LV	750.00	\$/wk	2.20	1.00	1,650
	Other plant	1,400.00	\$/wk	2.20	1.00	3,080
	Man hoists	2,000.00	\$/wk	2.20	1.00	4,400
	Shaft crane	9,000.00	\$/wk	2.20	1.00	19,800
	50T Crane	3,000.00	\$/wk	2.20	1.00	6,600
	TBM Crane	15,000.00	\$/wk	2.20	1.00	33,000
	Compressors	950.00	\$/wk	2.20	1.00	2,090
	Transformers & switchgear - HV	5,200.00	\$/wk	2.20	1.00	11,440
	Surface fans	800.00	\$/wk	2.20	1.00	1,760
						\$125,070

Page 1 of 2

Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Consumables					
Electrical power	0.00	\$/kwh	370.00	600.00	0
Gas oil	0.40	\$/L	15.00	1,000.00	6,000
Lubrication materials	0.00	\$/wk	2.20	1.00	0
Filters etc.	0.00	\$/wk	2.20	1.00	0
Hydraulic oil	0.00	<b>\$</b> /L	0.00	1.00	0
Other consumables	500.00	\$/wk	2.20	1.00	1,100
					\$7,100
Materials					
Temporary materials	500.00	\$/wk	2.20	1.00	1,100
Thrust frame	0.00	\$/wk	2.20	1.00	0
					\$1,100
<b>General Supplies</b>					
Small tools	700.00	\$/wk	2.20	1.00	1,540
					\$1,540
		То	tal Estimated C	ost:	\$406,242

Estimate Definition ID: 2640 Estimated by:

Printed by: whit2782, 8/16/04 11:44:46 AM Page 2 of 2 Checked by:



Version 2.6 Copyright Hatch Mott MacDonald, 2004

**Project Number:** 

**Estimate Description:** 

**Project:** 

**Tunnel Name:** 

Liner production

**NFLink** 

Single Rail Bored

**Construction Activity:** 

**Precast Linings** 

**Tunnel Technique:** 

EPB TBM - Precast segmental

**Estimate Definition ID:** 

**Parent Estimate ID:** 

213789

**Project Phase:** 

1596 Conceptual

Geology Type:

Not Applicable

**Estimate Date:** 

June 01, 2004

**Tunnel Characteristics ID:** 843

#### **Tunnel Characteristics**

26,322 m **Tunnel Length: Finished Diameter:** 7.5 m Final Lining Thickness:  $0.35 \, m$ 

### **Assumptions**

## A) Duration

Maximum	Minimum	
19	15	Months
3	2	Months
86	81	Months
108	98	Months
6	5	Months
1	1	Months
1	1	Months
100	91	Months
	19 3 86 108 6 1	19 15 3 2 86 81 108 98 6 5 1 1 1 1

## **B)** Production

2 % Allowance for Damage Ring Length 1.5 m 17,899 Number of Rings Required

**Production Rate Required** 49.2 Rings/Week Actual Production Rate Achieved 50 Rings/Week

# Investment on plant, equipment and moulds

\$5,000,000

4 Weeks **Initial Shakedown Time Production Time** 358.0 Weeks

	Shakedown Crew	Production / QC Crew
Shifts per Day	1	2
Hours per Shift	12	12
Days per Week	5	5

**Estimate Definition ID:** 2642 Estimated by: Printed by: whit2782, 7/13/04 2:53:36 PM Page 1 of 3 Checked by:

Concrete	12.95	m3/ring	
Reinforcing Steel	120	kg/m3	
Dunnage Assumption	50	50 % of total required storage	
	\$/Month	Months	Cost
Project Manager Rate	7,000	97	679,000
Plant Manager Rate	5,000	95	475,000
Quality Manager Rate	5,000	93	465,000
Secretary Rate	2,000	97	194,000
Office Building Cost			150,000
Office Equipment and Su	ipplies Cost		0
Finance Assume \$	1,000,000	97	485,000
Financing @	6 %		
Head Office Support @	1 %		1,286,778

\$3,734,778

Profit Margin 10 %

C) Overheads

Printed by: whit2782, 7/13/04 2:53:37 PM

Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Labor					
Shakedown crew	25.00	\$/hr	240.00	30.00	180,000
Production & QC crew	32.00	\$/hr	42,958.00	30.00	41,239,680
				60.00	\$41,419,680
Consumables					
Power	0.06	\$/kwh	43,198.00	1,020.00	2,643,718
Heating	0.11	\$/m2/wk	362.00	10,600.00	422,092
Steam curing	0.54	\$/m2/wk	362.00	2,000.00	390,960
Fuel	0.50	\$/L	362.00	3,000.00	543,000
Water	0.05	\$/L	231,743.00	100.00	1,158,715
					\$5,158,485
Materials					
Concrete	84.00	\$/m3	12.95	17,899.00	19,470,532
Rebar	1.00	\$/kg	1,554.00	17,899.00	27,815,046
Grout nozzles	3.00	\$/Nr	17,899.00	12.00	644,364
Lifting socket	10.00	\$/Nr	17,899.00	12.00	2,147,880
Bolt inserts	5.00	\$/Nr	17,899.00	12.00	1,073,940
Gaskets	100.00	\$/Nr	17,899.00	12.00	21,478,800
Dunnage	2.50	\$/m	18.00	8,949.00	402,705
Site preparation	10.00	\$/m2	12.32	8,949.00	1,102,517
					\$74,135,784
Estimate Definition ID: 2642			Estimated	bv:	

Page 2 of 3

Checked by:

Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Subcontracts					
Delivery	80.00	\$/hr	2.00	17,899.00	2,863,840
Testing	100,000.00	\$/Nr	1.00	1.00	100,000
					\$2,963,840
			Subto	tal:	\$123,677,789
		Ir	vestment on Pla	ant:	\$5,000,000
		To	tal Overhead C	ost:	\$3,734,778
			Subto	tal:	\$132,412,566
			Pro	ofit:	\$13,241,257
		Total P	recast Lining C	ost:	\$145,653,823
		Total Cos	t per Cubic Me	tre:	\$629
		T	otal Cost per Ri	ing:	\$8,138


Estimate Definition ID: 2642

Printed by: whit2782, 7/13/04 2:53:37 PM

Page 3 of 3

Checked by:

Newfoundland Fixed Link Pre-feasibility Study Cost Estimating Single Bored Railway Tunnel Tunnel Structural Finishes Page 1 of 2
Date: June 07, 2004
Calculation by: A.White



# Newfoundland Fixed Link Pre-feasibility Study

**Cost Estimating** 

Single Bored Railway Tunnel Tunnel Structural Finishes

# Page 2 of 2

**Date:** June 07, 2004 Calculation by: A.White

# **Quantity Take-off**

Concrete					Concrete	Rebar
Element	Nr.	L(m)	b(m)	d(m)	Qty(m3)	Qty(m3)
1	1	26320	0.3	5.9	46586	5590.4
2	1	26320	1.2	0.3	9475.2	1137.0
3	1	26320	1.2	0.3	9475.2	1137.0
					65537 m3	6727 t

## Formwork/falsework

Element	Nr.	L(m)	d(m)	Faces	Area(m2)	
1	1	26320	5.9	2	310576	
2	1	26320	1.2	1	31584	
3	1	26320	1.2	1	31584	
					373744	_ m2

## Rates

Concrete	m3	190
Formwork	m2	140
Reinforcement	t	1600

## Costs

Concrete	m3	65537 m3	at	190	=	12,451,992
Formwork	m2	373744 m2	at	140	=	52,324,160
Reinforcement	t	6727 t	at	1600	=	10,763,827
				\$		75,539,979

### Initialisation

Project: Newfoundland Fixed Link Pre-feasibility Study

Section: North Approach
Option: Bored Rail Tunnel

Date: 8-Jun-04

Calculations by: ANW

Surface gradient -0.08 %

+ sloping same way as track/road - sloping against track/road

Track/Road Gradient 1.663 %

Ground elevation at portal 100 m

Bottom of slab elevation at portal 86.95 m

Total length= 748.7091 m


Total Cost=\$ 7.8 M

Newfoundland Fixed Link Pre-feasibility Study	Date:	8-Jun-04
North Approach	Calculations by:	ANW
Bored Rail Tunnel		

## **UNIT RATES**

## **Materials**

Item	unit	Rate
excavation	m3	60
concrete	m3	190
rebar	tonnes	1600
formwork/falsework	m2	140
SP&L<=4.6m deep	m2	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=6.7m>	m2	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0</td></sp&l<=10.6m>	m2	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=13.7m>	m2	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0</td></sp&l<=16.8m>	m2	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0</td></sp&l<=20.0m>	m2	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0</td></sp&l<=25m>	m2	0
backfill + compact	m3	40
surface reinstatement	m2	30




Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	8446.7	60	506803.8
concrete	m3	1952.708	190.0	371014.6
rebar	tonnes	234.3	1600	374920
formwork/falsework	m2	1736.631	140	243128.3
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>1856.4</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	1856.4	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	681.3253	30	20439.76

Total 1516306




Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	7557.6	60	453456.1
concrete	m3	1796.378	190.0	341311.8
rebar	tonnes	215.6	1600	344904.5
formwork/falsework	m2	1541.218	140	215770.5
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>1661.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	1661.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	681.3253	30	20439.76

Total 1375883




Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	6519.2	60	391149.8
concrete	m3	1490.74	190.0	283240.5
rebar	tonnes	178.9	1600	286222
formwork/falsework	m2	1345.805	140	188412.7
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1465.6</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1465.6	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	666.0704	30	19982.11

Total 1169007




Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	5411.4	60	324683.1
concrete	m3	1115.76	190.0	211994.4
rebar	tonnes	133.9	1600	214225.9
formwork/falsework	m2	1150.392	140	161054.8
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1270.2</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1270.2	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	637.947	30	19138.41

Total 931096.7




Newfoundland Fixed Link Pre-feasibility Study North Approach Bored Rail Tunnel Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	4437.0	60	266219.7
concrete	m3	874.1685	190.0	166092
rebar	tonnes	104.9	1600	167840.4
formwork/falsework	m2	954.9785	140	133697
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1074.8</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1074.8	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	618.181	30	18545.43

Total 752394.5




Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	3564.6	60	213875.5
concrete	m3	734.5642	190.0	139567.2
rebar	tonnes	88.1	1600	141036.3
formwork/falsework	m2	759.5654	140	106339.2
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>879.4</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	879.4	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	606.9972	30	18209.92

Total 619028.1




Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	2727.8	60	163669.9
concrete	m3	630.6044	190.0	119814.8
rebar	tonnes	75.7	1600	121076
formwork/falsework	m2	564.1523	140	78981.33
SP&L<=4.6m deep	m2	683.9	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	597.2265	30	17916.8

Total 501458.9




Newfoundland Fixed Link Pre-feasibility Study North Approach Bored Rail Tunnel

Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	1916.6	60	114994.5
concrete	m3	552.1461	190.0	104907.8
rebar	tonnes	66.3	1600	106012
formwork/falsework	m2	368.7392	140	51623.49
SP&L<=4.6m deep	m2	488.5	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	587.4559	30	17623.68

Total 395161.5




Newfoundland Fixed Link Pre-feasibility Study North Approach Bored Rail Tunnel Date: 8-Jun-04

Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	1130.8	60	67849.13
concrete	m3	499.1891	190.0	94845.93
rebar	tonnes	59.9	1600	95844.31
formwork/falsework	m2	173.3262	140	24265.66
SP&L<=4.6m deep	m2	293.1	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	577.6852	30	17330.56

Total 300135.6



Newfoundland Fixed Link Pre-feasibility Study North Approach Bored Rail Tunnel

Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	376.2	60	22570.21
concrete	m3	477.3395	190.0	90694.51
rebar	tonnes	57.3	1600	91649.18
formwork/falsework	m2	-22.08692	140	-3092.169
SP&L<=4.6m deep	m2	97.7	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	576.506	30	17295.18

Total 219116.9

Newfoundland Fixed North Approach Bored Rail Tunnel	a Link Pre-fo	easibility Study Calc		
ummary of Costs		Markup for adjacent	0 %	
	Section  1 2 3 4 5 6 7 8 9 10 Sub-total	Cost 1516306 1375883 1169007 931096.7 752394.5 619028.1 501458.9 395161.5 300135.6 219116.9 7779588		

#### Initialisation

Project: Newfoundland Fixed Link Pre-feasibility Study

Section: South Approach
Option: Bored Rail Tunnel

Date: 8-Jun-04

Calculations by: ANW

Surface gradient 0 %

+ sloping same way as track/road - sloping against track/road

Track/Road Gradient 1.663 %

Ground elevation at portal 100 m

Bottom of slab elevation at portal 86.95 m

Total length= 784.7264 m


Total Cost=\$ 8.2 M

Newfoundland Fixed Link Pre-feasibility Study	Date:	8-Jun-04
South Approach	Calculations by:	ANW
Bored Rail Tunnel		

#### **UNIT RATES**

#### **Materials**

materiale		
Item	unit	Rate
excavation	m3	60
concrete	m3	190
rebar	tonnes	1600
formwork/falsework	m2	140
SP&L<=4.6m deep	m2	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=6.7m>	m2	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0</td></sp&l<=10.6m>	m2	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=13.7m>	m2	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0</td></sp&l<=16.8m>	m2	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0</td></sp&l<=20.0m>	m2	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0</td></sp&l<=25m>	m2	0
backfill + compact	m3	40
surface reinstatement	m2	30




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel

Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	8853.1	60	531184
concrete	m3	2046.645	190.0	388862.5
rebar	tonnes	245.6	1600	392955.8
formwork/falsework	m2	1820.173	140	254824.2
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>1945.7</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	1945.7	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	714.101	30	21423.03

Total 1589250




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	7921.2	60	475269.9
concrete	m3	1882.794	190.0	357730.9
rebar	tonnes	225.9	1600	361496.5
formwork/falsework	m2	1615.359	140	226150.3
SP&L<=4.6m deep	m2	0.0	0	0
4 6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>1740.9</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	1740.9	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	714.101	30	21423.03

Total 1442071




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	6832.8	60	409966.4
concrete	m3	1562.453	190.0	296866
rebar	tonnes	187.5	1600	299990.9
formwork/falsework	m2	1410.546	140	197476.4
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1536.1</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1536.1	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	698.1122	30	20943.37

Total 1225243




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel

Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	5671.7	60	340302.3
concrete	m3	1169.435	190.0	222192.6
rebar	tonnes	140.3	1600	224531.5
formwork/falsework	m2	1205.732	140	168802.5
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1331.3</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1331.3	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	668.6359	30	20059.08

Total 975887.9




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	4650.4	60	279026.4
concrete	m3	916.2211	190.0	174082
rebar	tonnes	109.9	1600	175914.5
formwork/falsework	m2	1000.919	140	140128.6
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1126.5</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1126.5	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	647.9192	30	19437.57

Total 788589




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel Date: 8-Jun-04 Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	3736.1	60	224164.1
concrete	m3	769.901	190.0	146281.2
rebar	tonnes	92.4	1600	147821
formwork/falsework	m2	796.1049	140	111454.7
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>921.7</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	921.7	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	636.1973	30	19085.92

Total 648806.9




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel

Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	2859.1	60	171543.4
concrete	m3	660.9402	190.0	125578.6
rebar	tonnes	79.3	1600	126900.5
formwork/falsework	m2	591.2913	140	82780.79
SP&L<=4.6m deep	m2	716.8	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	625.9566	30	18778.7

Total 525582




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	2008.8	60	120526.4
concrete	m3	578.7075	190.0	109954.4
rebar	tonnes	69.4	1600	111111.8
formwork/falsework	m2	386.4778	140	54106.89
SP&L<=4.6m deep	m2	512.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	615.716	30	18471.48

Total 414171




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel Date: 8-Jun-04 Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	1185.2	60	71113.07
concrete	m3	523.203	190.0	99408.58
rebar	tonnes	62.8	1600	100455
formwork/falsework	m2	181.6642	140	25432.98
SP&L<=4.6m deep	m2	307.2	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	605.4753	30	18164.26

Total 314573.9



Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel

Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	394.3	60	23655.97
concrete	m3	500.3023	190.0	95057.44
rebar	tonnes	60.0	1600	96058.04
formwork/falsework	m2	-23.14943	140	-3240.92
SP&L<=4.6m deep	m2	102.4	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	604.2393	30	18127.18

Total 229657.7

Newfoundland Fixed Link Pre-feasibility Study Date: 8-Jun-04 South Approach Calculations by: ANW Bored Rail Tunnel Summary of Costs Markup for adjacent 0 Section Cost 1 1589250 2 1442071 3 1225243 4 975887.9 5 788589 6 648806.9 7 525582 8 414171 9 314573.9 10 229657.7 Sub-total 8153832

# Newfoundland Fixed Link Pre-feasibility Study Preferred Fixed Link Option - TBM Bored Railway Tunnel Basis of Estimate

#### Scope

#### Estimate includes:

- mobilisation of equipment and materials
- TBM bored tunnel excavation and lining
- TBM bored tunnel finishes
- north and south approaches to TBM bored rail tunnel
- north and south rail terminals including passenger facilities, maintenance facilities, tolling areas
- tunnel trackwork, drainage, ventilation, mechanical & electrical items
- shuttle trains, signalling, and OCS system
- allowances for indirect costs, contractor profit, and risk allowances

#### Estimate does not include:

- land purchase costs
- approach roads to the terminal areas (addressed separately)
- provision for bringing electrical power to the facility

#### **Assumptions**

#### **Principal Assumptions:**

- labour wages in accordance with Local 2003 Collective Agreement for Newfoundland & Labrador
- 7.5 metre internal diameter tunnel driven from Newfoundland side using an EPB type tunnel boring machine configured for rock
- tunnel approximately 26.3 kilometres in length
- 3 eight hour shifts 5 days per week for tunnelling operations
- tunnel lined with bolted precast concrete segmental tunnel liner
- average tunnelling advance rate of 81 metres per week
- tunnel drive encounters 14 faults each 100 metres wide where advance rate decreases by approximately 60%
- rail mounted loco and muck car system used for removal of tunnel spoil
- longitudinal system used for ventilation of the tunnel (permanent facility)

#### Costs

#### Cost assumptions

- All costs in 2004 Canadian dollars
- HST not included

Page 1 of 3

## Newfoundland Fixed Link Pre-feasibility Study Road Connections Cost Estimate Summary

The following is a summary of the costs of road works associated with the project.

1		Road Tunnel Concept	Unit	Quantity	Unit Cost	Total Cost
1A	0.1	Newfoundland Side New Road Construction	km	1.4	\$550,000	\$770,000
	0.1	New Road Construction	KIII	1.4	\$330,000	\$770,000
	0.2	Intersection Construction	allowance	1	\$50,000	\$50,000
	0.3	Marshalling Area	sq meter	36,000	\$45	\$1,620,000
		Sub Total Nfld Side				\$2,440,000
1B		Labrador Side				
	0.1	New Road Construction	km	1	\$600,000	\$600,000
	0.2	Intersection Construction	allowance	1	\$50,000	\$50,000
	0.3	Marshalling Area	sq meter	36,000	\$57	\$2,052,000
		Sub Total Labrador Side				\$2,702,000
2		Rail Tunnel Concept	Unit	Quantity	Unit Cost	Total Cost
2A	0.1	Newfoundland Side New Road Construction	km	1.5	\$550,000	\$825,000
	0.2	Intersection Construction	allowance	1	\$50,000	\$50,000
	0.3	Marshalling Area	sq meter	36,000	\$45	\$1,620,000
		Sub Total Nfld Side				\$2,495,000
2B		Labrador Side				
	0.1	New Road Construction	km	1	\$600,000	\$600,000

# Page 2 of 3

0.2	Intersection Construction	allowance	1	\$50,000	\$50,000
0.3	Marshalling Area	sq meter	36,000	\$57	\$2,052,000
	Sub Total Labrador Side				\$2,702,000

# Page 3 of 3

3	Quebec North Shore				
0.1	New Road Construction	km	350	\$720,000	\$252,000,000
0.2	Road Upgrading	km	40	\$360,000	\$14,400,000
0.3	Branch Roads	km	20	\$312,000	\$6,240,000
0.4	Bridges	ea	9	\$1,200,000	\$10,800,000
	Sub Total Quebec North Shore Roads				\$283,440,000
Total Roa	ad Costs				
	Road Tunnel				\$288,582,000
	Rail Tunnel				\$288,637,000



Newfoundland Fixed Link Pre-feasibility - TBM Bored Railway Tunnel - Cost Summary

	00050 500	NAST CONCERNATION COSTS
		NNEL CONSTRUCTION COSTS
ITEM	UNIT	MAIN TUNNEL
MOBILIZATION & DEMOBILIZATION	LS	8,000,000
TUNNELLING	LS	375,031,000
TUNNEL FINISHES	LS	75,539,979
NORTH APPROACH STRUCTURES	LS	7,770,000
SOUTH APPROACH STRUCTURES	LS	8,150,000
RAIL TRACK	LS	13,923,100
TUNNEL DRAINAGE	LS	7,820,000
UTILITY DIVERSIONS	LS	1,000,000
MONITORING	LS	1,000,000
SUBTOTAL CIVIL		\$498,234,079
CIVIL CONTINGENCIES		
CIVIL CONTINGENCIES		
CONTINGENCY	40%	\$199,293,632
TOTAL CIVIL		\$697,527,711
M&F. ROL	LING STOCK	   RAIL HARDWARE AND FINISHING WORK
ROLLING STOCK, TERMINALS, OCS, ETC	LS	\$48,000,000
VENTILATION EQUIPMENT	LS	\$3,000,000
VENTILATION SHAFTS AND BUILDINGS x 2	LS	\$0
FIRE SUPPRESSION SYSTEM	LS	\$2,000,000
CONTROL CENTRE	LS	\$1,000,000
SIGNALLING	LS	\$1,000,000
LIGHTING	LS	\$1,000,000
		\$1,000,000
CCTV SYSTEM GAS DETECTION	LS LS	\$900,000
SUBSTATION, GENERATORS, UPS	LS	\$2,000,000
SUBTOTAL M&E AND FINISHING		\$58,900,000
CONTINGENCIES	20%	\$11,780,000
TOTAL M&E AND FINISHING		\$70,680,000
TO THE MIGE THE PROPERTY.		<b>V</b> 1.0)000,000
TOTAL CIVIL, M&E AND FINISHING		\$768,207,711
ALLOWANCES		
CONTRACTOR OH	15%	\$115,231,157
CONTRACTOR PROFIT	15%	\$115,231,157
S.III GIGITI	1070	\$110,E01,101
CONSTRUCTION TOTAL		\$999,000,000
TOTAL TOTAL	PRE-CONS	TRUCTION AND SUPERVISION
FEASIBILITY STUDY	LS	\$11,000,000
ENVIRONMENTAL ASSESSMENT	LS	\$4,000,000
DESIGN	5%	\$49,950,000
CONSTRUCTION MANAGEMENT	10%	\$99,900,000
OWNERS COSTS	2%	\$19,980,000
DDE CONCEDUCTION TOTAL		0404 000 000
PRE-CONSTRUCTION TOTAL		\$184,830,000
GRAND TOTAL		\$1,183,830,000
	1	1 -1 1 1 1

Hatch Mott MacDonald	Newfoundland Fixed Link Pre-feasibility - TBM Bored Railway Tunnel Civil Costs					
ITEM	UNIT	QTY	RATE	TOTAL		
MORUIZATION	1.0	4.00	#0.000.000	#0.000.000		
MOBILIZATION	LS	1.00	\$8,000,000	\$8,000,000		
TUNNELLING						
- TBM launch shaft	LS	1.00	\$0	\$0		
- Set-up TBM	LS	1.00	\$1,474,000	\$1,474,000		
- Tunnel drive	LS	1.00	\$368,001,000	\$368,001,000		
- TBM maintenance	LS	1.00	\$960,000	\$960,000		
- Remove TBM	LS	1.00	\$812,000	\$812,000		
- Clean tunnel	LS	1.00	\$3,784,000	\$3,784,000		
- Structural finishes	LS	1.00	\$75,539,979	\$75,539,979		
- TBM reception shaft	LS	1.00	\$0	\$0		
NORTH APPROACH STRUCTURES						
- Cut and cover approach	LS	1.00	\$7,770,000	\$7,770,000		
SOUTH APPROACH STRUCTURES						
- cut and cover approach	LS	1.00	\$8,150,000	\$8,150,000		
DRAINAGE						
Drainage sumps and piping	LS	1.00	\$7,820,000	\$7,820,000		
RAIL TRACK						
- bored tunnel	m2	40,050.00	\$20	\$801,000		
- north approach	m2	31,150.00	\$20	\$623,000		
- south approach	m2	1,602.00	\$30	\$48,060		

\$483,783,039

SUB-TOTAL



Version 2.6 Copyright Hatch Mott MacDonald, 2004

Project: Newfoundland Fixed Link Pre-feasibility Study

**Estimate Description:** Set-up TBM

Tunnel Name: Single Rail Bored
Construction Activity: Erect TBM Only

Tunnel Technique: EPB TBM - Precast segmental

**Estimate Definition ID: 2636** 

**Estimate Definition ID:** 

2636

Printed by: whit2782, 8/16/04 11:42:50 AM

**Project Number:** 213789

Parent Estimate ID: 1563

Project Phase: Conceptual

Geology Type: Not

Not Applicable

**Estimate Date:** 

May 31, 2004

**Tunnel Characteristics ID: 843** 

#### **Tunnel Characteristics**

Finished Diameter: 7.5 m

#### **Activity Details**

**Shift Arrangement** 3 - 8 hour shifts x 7 days per week

**Duration of Activity** 

4.5 Weeks

**Total Number of Shifts** 

94.5

Estimated by:

Checked by:

	Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Tota
Labor						
	Pit boss	52.29	\$/hr	756.00	1.00	39,53
	Tunnel miner	48.89	\$/hr	756.00	2.00	73,922
	Shaft bottom	48.44	\$/hr	756.00	3.00	109,862
	Tunnel fitter	49.34	\$/hr	756.00	1.00	37,30
	Tunnel electrician	49.34	\$/hr	756.00	1.00	37,30
	Shaft top	47.99	\$/hr	756.00	1.00	36,280
	Crane operator	49.34	\$/hr	756.00	2.00	74,602
	Surface laborer	47.99	\$/hr	756.00	1.00	36,28
	Equipment laborer	48.44	\$/hr	756.00	1.00	36,62
					13.00	\$481,701
Plant						
	Loco	5,000.00	\$/wk	4.50	1.00	22,50
	Muck cars & grout cars	1,900.00	\$/wk	4.50	6.00	51,30
	Flat cars	310.00	\$/wk	4.50	2.00	2,79
	Transformers & switchgear - LV	750.00	\$/wk	4.50	1.00	3,37
	Small tools	2,600.00	\$/wk	4.50	1.00	11,70
	Shaft crane	9,000.00	\$/wk	4.50	1.00	40,50
	Erection crane	10,000.00	\$/wk	4.50	1.00	45,00
	Compressors	950.00	\$/wk	4.50	1.00	4,27
	Generators	2,000.00	\$/wk	4.50	1.00	9,00
	Transformers & switchgear - HV	5,200.00	\$/wk	4.50	1.00	23,40
	Loaders	2,300.00	\$/wk	4.50	1.00	10,35
						\$224,190
Consun	nables					
	Electrical power	0.00	\$/kwh	756.00	300.00	
	Gas oil	0.00	\$/L	0.00	1.00	

Page 1 of 2

Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Lubrication materials	0.00	\$/wk	4.50	1.00	0
Filters etc.	0.00	\$/wk	4.50	1.00	0
Hydraulic oil	0.00	<b>\$</b> /L	0.00	1.00	0
Other consumables	0.00	\$/wk	4.50	1.00	0
					\$0
Materials					
Temporary materials	2,000.00	\$/wk	4.50	1.00	9,000
Thrust frame	5,000.00	\$/wk	4.50	1.00	22,500
					\$31,500
		To	tal Estimated C	ost:	\$737,391

Estimate Definition ID: 2636

Printed by: whit2782, 8/16/04 11:42:50 AM

Page 2 of 2

Checked by:



Version 2.6

Copyright Hatch Mott MacDonald, 2004

Project: Newfoundland Fixed Link Pre-feasibility Study

Drive from Newfland **Estimate Description:** Rail Bored 2 TBM NF **Tunnel Name:** 

**Construction Activity:** TBM Tunneling

**Tunnel Technique:** EPB TBM - Precast segmental

**Estimate Definition ID:** 

**Project Number:** 213789

**Parent Estimate ID:** 2728

**Project Phase:** Conceptual Geology Type: Not Applicable

**Estimate Date:** September 13, 2004

**Tunnel Characteristics ID: 885** 

#### **Tunnel Characteristics**

13,161 m **Tunnel Length:** 7.5 m **Finished Diameter:** 

Initial Support Type: Not Applicable

**Initial Support Thickness:** 0 m

0.35 m **Final Lining Thickness: Grout Thickness:** 0.1 m

#### **Theoretical Excavation Volumes**

**Total Neat Excavation:** 729,352 Cubic Metres 0 Cubic Metres **Initial Lining Volume:** 

113,599 Cubic Metres Final Lining Volume:

**Theoretical Grout Volume:** 34,318 Cubic Metres

### Normal Excavation/Support Cycle

1.5 Metres **Excavation Cycle Length:** 

24 Minutes Excavate: 27 Minutes **Erect Support: Extend Services:** 0 Minutes **Total Cycle Time:** 51 Minutes

## **Difficult Excavation/Support Cycle**

1400 Metres Length of Difficult Excavation: **Excavate:** 73 Minutes

> **Erect Support:** 54 Minutes **Extend Services:** 0 Minutes **Total Cycle Time:** 127 Minutes

> > 7.1

17.7

Metres

397

11,364

m/day

m/day

7.1 m/day

#### **Reduction Factors**

Machine availability: 80 % Back up efficiency: 55 % 5 % Planned maintenance: 40 % Learning curve efficiency:

**Difficult Advance Rate:** 

**Learning Curve Rate:** 

TBM Skidding Through Excavation

**Experienced Advance Rate:** 

0 Weeks **Duration of skidding:** Length of skidding: 0 Metres

#### **Advance Rate and Shift Details**

Learning curve duration time:

Avg. Drive Advance per Shift: 4.90 Metres 15 Metres Avg. Drive Advance per Day: Avg. Drive Advance per Week: 103 Metres **Duration of Tunneling (Incl. Skid):** 

127.84 Weeks

Total number of shifts (Incl. Skid): 2,685

**Shift Arrangement:** 3 - 8 hour shifts x 7 days per week

8 Weeks

**Skidding Portion:** 

**Experienced Drive:** 

**Difficult Drive:** 

**Learning Curve Drive:** 

1,400 197 0 0

Days

56

642

**Estimate Definition ID:** 2736

Printed by: whit2782, 9/13/04 3:15:33 PM

Page 1 of 3

Estimated by:

Checked by:

	Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Labor						
Lubor	Pit boss	52.29	\$/hr	21,481.00	1.00	1,123,241
	Working foreman	52.29	\$/hr	21,481.00	2.00	2,246,483
	Tunnel miner	48.89	\$/hr	21,481.00	3.00	3,150,618
	Tunnel laborer	48.44	\$/hr	21,481.00	4.00	4,162,159
	Loco driver	49.34	\$/hr	21,481.00	3.00	3,179,618
	Shaft bottom	48.44	\$/hr	21,481.00	1.00	1,040,540
	TBM operator	49.34	\$/hr	21,481.00	1.00	1,059,873
	Tunnel fitter	49.34	\$/hr	21,481.00	1.00	1,059,873
	Tunnel electrician	49.34	\$/hr	21,481.00	1.00	1,059,873
	Shaft top	47.99	\$/hr	21,481.00	2.00	2,061,746
	Crane operator	49.34	\$/hr	21,481.00	1.00	1,059,873
	Surface laborer	47.99	\$/hr	21,481.00	4.00	4,123,493
	Equipment laborer	48.44	\$/hr	21,481.00	4.00	4,162,159
				,	28.00	\$29,489,546
Plant						
	TBM	300,000.00	\$/m2	55.42	0.80	13,300,800
	TBM backup	1,430,000.00	\$/Nr	1.00	1.00	1,430,000
	Loco	5,000.00	\$/wk	127.84	3.00	1,917,600
	Muck cars & grout cars	1,900.00	\$/wk	127.84	21.00	5,100,816
	Flat cars	310.00	\$/wk	127.84	6.00	237,782
	Manriders	310.00	\$/wk	127.84	2.00	79,261
	Track	130.00	\$/m	13,161.00	1.00	1,710,930
	Air pipe	30.00	\$/m	13,161.00	1.00	394,830
	Water pipe	25.00	\$/m	13,161.00	1.00	329,025
	Pump main	50.00	\$/m	13,161.00	1.00	658,050
	Cabling	80.00	\$/m	13,161.00	1.00	1,052,880
	Lighting	30.00	\$/m	13,161.00	1.00	394,830
	Vent ducting	30.00	\$/m	13,161.00	1.00	394,830
	Grout mixers	7,100.00	\$/wk	127.84	1.00	907,664
	Grout pumps	3,400.00	\$/wk	127.84	1.00	434,656
	Grout hoses & pipes	196.00	\$/wk	127.84	2.00	50,113
	Transformers & switchgear - LV	750.00	\$/wk	127.84	2.00	191,760
	Small tools	2,600.00	\$/wk	127.84	1.00	332,384
	Shaft crane	9,000.00	\$/wk	127.84	1.00	1,150,560
	Compressors	950.00	\$/wk	127.84	1.00	121,448
	Low pressure C/A system	3,800.00	\$/wk	127.84	1.00	485,792
	Pipework and controls	655.00	\$/wk	127.84	2.00	167,470
	Generators	2,000.00		127.84	1.00	255,680
	Transformers & switchgear - HV	5,200.00		127.84	1.00	664,768
	Surface fans	800.00		127.84	2.00	204,544
	Loaders	2,300.00		127.84	2.00	588,064
	Other surface plant	2,600.00		127.84	1.00	332,384
Estimate	<b>Definition ID:</b> 2736			T	,	
Listimate	Deminion ID. 2730			Estimated	by:	

Page 2 of 3

Checked by:

Printed by: whit2782, 9/13/04 3:15:34 PM

Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Tunnel C/A system	40,000.00	\$/wk	127.84	1.00	5,113,600
					\$38,002,522
Consumables					
Electrical power	0.10	\$/kwh	21,481.00	3,000.00	6,444,300
Gas oil	0.45	<b>\$</b> /L	48,000.00	1.00	21,600
Lubrication materials	90.00	\$/wk	127.84	1.00	11,506
TBM spares, cutters	250.00	\$/m	13,161.00	1.00	3,290,250
Filters etc.	300.00	\$/wk	127.84	1.00	38,352
Hydraulic oil	0.90	<b>\$</b> /L	32,000.00	1.00	28,800
Other consumables	160.00	\$/wk	127.84	1.00	20,454
Tail seal grease	100.00	\$/m	13,161.00	1.00	1,316,100
					\$11,171,362
<b>laterials</b>					
Concrete lining rings	8,300.31	\$/Nr	8,774.00	1.00	72,826,912
Gaskets	130.00	\$/m	13,161.00	1.00	1,710,930
Bolts	12.00	\$/Nr	1,765.00	30.00	635,400
Grout	145.00	\$/m3	34,318.00	1.00	4,976,110
Grout plugs	0.50	\$/Nr	1,765.00	7.00	6,178
Packers	10.00	\$/Nr	3,633.00	12.00	435,960
Temporary materials	2,250.00	\$/wk	127.84	1.00	287,640
Other materials	0.00	<b>\$</b> /t	0.00	1.00	0
					\$80,879,129
ubcontracts					
Soil disposal	20.00	\$/m3	729,352.00	1.50	21,880,560
					\$21,880,560
		Te	otal Estimated Co	ost:	\$181,423,120
	To	otal Estima	ted Cost per Me	tre:	\$13,785
	T	Total Estimated Cost per Week:			
	7	Total Estim	ated Cost per Sh	ift:	\$67,567

Estimate Definition ID: 2736

Printed by: whit2782, 9/13/04 3:15:35 PM

Page 3 of 3

Checked by:



Version 2.6

Copyright Hatch Mott MacDonald, 2004

Project: Newfoundland Fixed Link Pre-feasibility Study

Drive from Labrador **Estimate Description:** Rail Bored 2 TBM LB **Tunnel Name: Construction Activity:** TBM Tunneling

EPB TBM - Precast segmental **Tunnel Technique:** 

**Estimate Definition ID:** 

**Project Number:** 213789

**Parent Estimate ID:** 2728

**Project Phase:** Conceptual Geology Type: Not Applicable

**Estimate Date:** September 13, 2004

**Tunnel Characteristics ID: 886** 

**Tunnel Characteristics** 

13,161 m **Tunnel Length:** 

7.5 m **Finished Diameter:** 

Initial Support Type: Not Applicable

**Initial Support Thickness:** 0 m

0.35 m **Final Lining Thickness:** 

> **Grout Thickness:** 0.1 m

**Theoretical Excavation Volumes** 

**Total Neat Excavation:** 729,352 Cubic Metres

0 Cubic Metres **Initial Lining Volume:** 

113,599 Cubic Metres Final Lining Volume:

**Theoretical Grout Volume:** 34,318 Cubic Metres

Normal Excavation/Support Cycle

1.5 Metres **Excavation Cycle Length:** 

> 24 Minutes Excavate: 27 Minutes **Erect Support: Extend Services:** 0 Minutes

**Total Cycle Time:** 51 Minutes **Difficult Excavation/Support Cycle** 

1400 Metres Length of Difficult Excavation:

> **Excavate:** 73 Minutes **Erect Support:** 54 Minutes

**Extend Services:** 0 Minutes

**Total Cycle Time:** 127 Minutes

**Reduction Factors** 

Machine availability: 80 % Back up efficiency: 55 % 5 % Planned maintenance: 40 % Learning curve efficiency:

8 Weeks Learning curve duration time:

**Learning Curve Rate: Experienced Advance Rate:** 

7.1 m/day 17.7 m/day

**Difficult Advance Rate:** 7.1 m/day

TBM Skidding Through Excavation

**Duration of skidding:** 

0 Weeks

Length of skidding: 0 Metres

**Advance Rate and Shift Details** 

**Shift Arrangement:** 3 - 8 hour shifts x 7 days per week

Avg. Drive Advance per Shift: 4.90 Metres 15 Metres Avg. Drive Advance per Day: Avg. Drive Advance per Week: 103 Metres

Total number of shifts (Incl. Skid):

**Learning Curve Drive: Experienced Drive:** 

**Difficult Drive:** 

**Skidding Portion:** 

397 11,364

Metres

1,400 197

0

Days

56

642

0

**Duration of Tunneling (Incl. Skid):** 

127.84 Weeks

2,685

**Estimate Definition ID:** 2737

Printed by: whit2782, 9/13/04 3:21:15 PM

Estimated by:

Page 1 of 3

Checked by:

	Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Labor						
Lubor	Pit boss	52.29	\$/hr	21,481.00	1.00	1,123,241
	Working foreman	52.29	\$/hr	21,481.00	2.00	2,246,483
	Tunnel miner	48.89	\$/hr	21,481.00	3.00	3,150,618
	Tunnel laborer	48.44	\$/hr	21,481.00	4.00	4,162,159
	Loco driver	49.34	\$/hr	21,481.00	3.00	3,179,618
	Shaft bottom	48.44	\$/hr	21,481.00	1.00	1,040,540
	TBM operator	49.34	\$/hr	21,481.00	1.00	1,059,873
	Tunnel fitter	49.34	\$/hr	21,481.00	1.00	1,059,873
	Tunnel electrician	49.34	\$/hr	21,481.00	1.00	1,059,873
	Shaft top	47.99	\$/hr	21,481.00	2.00	2,061,746
	Crane operator	49.34	\$/hr	21,481.00	1.00	1,059,873
	Surface laborer	47.99	\$/hr	21,481.00	4.00	4,123,493
	Equipment laborer	48.44	\$/hr	21,481.00	4.00	4,162,159
					28.00	\$29,489,546
Plant	TD1 (	•••	<b>.</b>			42.200.000
	TBM	300,000.00		55.42	0.80	13,300,800
	TBM backup	1,430,000.00		1.00	1.00	1,430,000
	Loco	5,000.00		127.84	3.00	1,917,600
	Muck cars & grout cars	1,900.00		127.84	21.00	5,100,816
	Flat cars	310.00		127.84	6.00	237,782
	Manriders	310.00		127.84	2.00	79,261
	Track	130.00		13,161.00	1.00	1,710,930
	Air pipe	30.00		13,161.00	1.00	394,830
	Water pipe	25.00		13,161.00	1.00	329,025
	Pump main	50.00		13,161.00	1.00	658,050
	Cabling	80.00		13,161.00	1.00	1,052,880
	Lighting	30.00	•	13,161.00	1.00	394,830
	Vent ducting	30.00		13,161.00	1.00	394,830
	Grout mixers	7,100.00		127.84	1.00	907,664
	Grout pumps	3,400.00		127.84	1.00	434,656
	Grout hoses & pipes	196.00		127.84	2.00	50,113
	Transformers & switchgear - LV	750.00		127.84	2.00	191,760
	Small tools	2,600.00		127.84	1.00	332,384
	Shaft crane	9,000.00		127.84	1.00	1,150,560
	Compressors	950.00		127.84	1.00	121,448
	Low pressure C/A system	3,800.00	\$/wk	127.84	1.00	485,792
	Pipework and controls	655.00		127.84	2.00	167,470
	Generators	2,000.00	\$/wk	127.84	1.00	255,680
	Transformers & switchgear - HV	5,200.00	\$/wk	127.84	1.00	664,768
	Surface fans	800.00	\$/wk	127.84	2.00	204,544
	Loaders	2,300.00	\$/wk	127.84	2.00	588,064
	Other surface plant	2,600.00	\$/wk	127.84	1.00	332,384
Estimate	<b>Definition ID:</b> 2737			Estimated	hv:	
				Estimateu	~j•	

Page 2 of 3

Checked by:

Printed by: whit2782, 9/13/04 3:21:16 PM

Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Tunnel C/A system	40,000.00	\$/wk	127.84	1.00	5,113,600
					\$38,002,522
Consumables					
Electrical power	0.18	\$/kwh	21,481.00	3,000.00	11,599,740
Gas oil	0.45	<b>\$</b> /L	48,000.00	1.00	21,600
Lubrication materials	90.00	\$/wk	127.84	1.00	11,506
TBM spares, cutters	250.00	\$/m	13,161.00	1.00	3,290,250
Filters etc.	300.00	\$/wk	127.84	1.00	38,352
Hydraulic oil	0.90	<b>\$</b> /L	32,000.00	1.00	28,800
Other consumables	160.00	\$/wk	127.84	1.00	20,454
Tail seal grease	100.00	\$/m	13,161.00	1.00	1,316,100
					\$16,326,802
Materials					
Concrete lining rings	8,300.31	\$/Nr	8,774.00	1.00	72,826,912
Gaskets	130.00	\$/m	13,161.00	1.00	1,710,930
Bolts	12.00	\$/Nr	1,765.00	30.00	635,400
Grout	145.00	\$/m3	34,318.00	1.00	4,976,110
Grout plugs	0.50	\$/Nr	1,765.00	7.00	6,178
Packers	10.00	\$/Nr	3,633.00	12.00	435,960
Temporary materials	2,250.00	\$/wk	127.84	1.00	287,640
Other materials	0.00	\$/t	0.00	1.00	0
					\$80,879,129
Subcontracts					
Soil disposal	20.00	\$/m3	729,352.00	1.50	21,880,560
					\$21,880,560
		T	otal Estimated C	ost:	\$186,578,560
	To	tal Estima	ited Cost per Me	tre:	\$14,177
	T	otal Estim	ated Cost per We	ek:	\$1,459,508
	7	otal Estin	nated Cost per Sh	ift:	\$69,487

Estimate Definition ID: 2737

Estimated by:

Printed by: whit2782, 9/13/04 3:21:16 PM

Page 3 of 3

Checked by:



Version 2.6

\$521,542

Copyright Hatch Mott MacDonald, 2004

**Project:** Newfoundland Fixed Link Pre-feasibility Study

**Estimate Description:** Maintain TBM

**Tunnel Name:** Rail Bored 2 TBM **Construction Activity:** TBM Maintenance

**Tunnel Technique:** EPB TBM - Precast segmental

**Estimate Definition ID:** 

**Project Number:** 213789

**Parent Estimate ID:** 2638

**Project Phase:** Conceptual

Geology Type:

Not Applicable

**Estimate Date:** 

August 17, 2004

**Tunnel Characteristics ID: 879** 

#### **Tunnel Characteristics**

**Finished Diameter:** 7.5 m

#### **Activity Details**

1 - 6 hour shifts x 1 days per week Shift Arrangement

**Total Estimated Cost:** 

**Duration of Activity** 

127 Weeks

**Total Number of Shifts** 

127

	Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Labor						
	Working foreman	52.29	\$/hr	762.00	1.50	59,767
	Loco driver	49.34	\$/hr	762.00	1.50	56,396
	Shaft bottom	48.44	\$/hr	762.00	1.50	55,367
	TBM operator	49.34	\$/hr	762.00	1.50	56,396
	Tunnel fitter	49.34	\$/hr	762.00	1.50	56,396
	Tunnel electrician	49.34	\$/hr	762.00	1.50	56,396
	Shaft top	47.99	\$/hr	762.00	1.50	54,853
	Surface laborer	47.99	\$/hr	762.00	1.50	54,853
					12.00	\$450,422
Consun	nables					
	Electrical power	0.10	\$/kwh	762.00	600.00	45,720
	Gas oil	0.45	<b>\$</b> /L	0.00	1.00	0
	Other consumables	0.00	\$/wk	127.00	1.00	0
						\$45,720
Materia	als					
	Temporary materials	200.00	\$/wk	127.00	1.00	25,400
	Other materials	0.00	<b>\$</b> /t	0.00	1.00	0
						\$25,400

**Estimate Definition ID: 2729** Estimated by:

Printed by: whit2782, 8/17/04 10:24:45 AM Page 1 of 1 Checked by:



Version 2.6

Copyright Hatch Mott MacDonald, 2004

**Project:** Newfoundland Fixed Link Pre-feasibility Study

Estimate Description: Clean tunnel
Tunnel Name: Single Rail Bored

Construction Activity: Tunnel Clean Up

Tunnel Technique: EPB TBM - Precast segmental

**Estimate Definition ID:** 2639

Project Number: 213789

Parent Estimate ID: 1562

Project Phase: Conceptual

Geology Type: Not Applicable

Estimate Date: May 21, 2004

**Tunnel Characteristics ID: 843** 

### **Tunnel Characteristics**

Tunnel Length: 26,322 m

Finished Diameter: 7.5 m (Circular Tunnels)

Excavated Cross Section: 0 m2 (Non-circular Tunnels)

Excavated Perimeter: 0 m (Non-circular Tunnels)

## Productivity Cycle Reduction Factors

Section Length30 MetresLearning Curve Efficiency:50 %Vent Line Removal Time120 MinutesBack Up Efficiency:80 %Track Removal Time60 MinutesLearning Curve Duration:1 Weeks

**Temp Lighting Removal Time** 60 Minutes

Clean Up Time 120 Minutes

**Total Cycle Time**Shift Arrangement: 3 - 8 hour shifts x 7 days per week

Avg. Advance per Shift:31.58 MetresAvg. Advance per Week:664 Metres

**Shift Details** 

**Total number of hours:** 6,669

### Clean Up Productivity Data

	Average Advance	<b>Drive Length</b>	<b>Drive Duration</b>			
Learning Curve Portion:	48.0 m/day	336 Metres	21 Shifts	7 Days	1.00 Weeks	
Experienced Drive Portion:	96.0 m/day	25,986 Metres	812 Shifts	271 Days	38.67 Weeks	
Total:	94.8 m/day	26,322 Metres	834 Shifts 2	278 Days	39.67 Weeks	

	Resource Name	Unit Rate UO	Unit OM Quantity	Resource Quantity	Total
Labor					
	Tunnel laborer	48.44 \$/hı	r 6,668.00	6.00	1,937,988
	Shaft bottom	48.44 \$/hi	r 6,668.00	1.00	322,998
	Shaft top	47.99 \$/hı	r 6,668.00	1.00	319,997
	Crane operator	49.34 \$/hi	r 6,668.00	1.00	328,999
				9.00	\$2,909,982
Plant					
	Transformers & switchgear - LV	750.00 \$/w	yk 39.67	1.00	29,753

Estimate Definition ID: 2639 Estimated by:

Printed by: whit2782, 8/16/04 11:44:17 AM Page 1 of 2 Checked by:

Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Man hoists	2,600.00	\$/wk	39.67	1.00	103,142
Shaft crane	9,000.00	\$/wk	39.67	1.00	357,030
Compressors	950.00	\$/wk	39.67	1.00	37,687
Loaders	2,260.00	\$/wk	39.67	1.00	89,654
Other surface plant	2,600.00	\$/wk	39.67	1.00	103,142
Bobcat	500.00	\$/wk	39.67	1.00	19,835
					\$740,242
Consumables					
Electrical power	0.10	\$/kwh	6,668.00	200.00	133,360
					\$133,360
		To	tal Estimated Co	ost:	\$3,783,584
	To	tal Estimat	ed Cost per Met	tre:	\$144
	To	otal Estima	ted Cost per We	ek:	\$95,377
	Т	otal Estima	ited Cost per Sh	ift:	\$4,539

Estimate Definition ID: 2639

Printed by: whit2782, 8/16/04 11:44:18 AM

Page 2 of 2

Checked by:



Version 2.6 Copyright Hatch Mott MacDonald, 2004

Project: Newfoundland Fixed Link Pre-feasibility Study

**Estimate Description:** Remove TBM

Tunnel Name: Single Rail Bored
Construction Activity: TBM Removal

Tunnel Technique: EPB TBM - Precast segmental

**Estimate Definition ID: 2640** 

**Estimate Definition ID:** 

2640

Printed by: whit2782, 8/16/04 11:44:45 AM

**Project Number:** 213789

Parent Estimate ID: 1564

Project Phase: Conceptual

Geology Type: Not Applicable

Estimate Date: May 21, 2004

**Tunnel Characteristics ID: 843** 

Estimated by:

Checked by:

#### **Tunnel Characteristics**

Finished Diameter: 7.5 m

### **Activity Details**

**Shift Arrangement** 3 - 8 hour shifts x 7 days per week

**Duration of Activity** 2.2 Weeks

**Total Number of Shifts** 46.2

	Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Labor						
	Pit boss	52.29	\$/hr	370.00	1.00	19,347
	Tunnel miner	48.89	\$/hr	370.00	3.00	54,268
	Shaft bottom	48.44	\$/hr	370.00	2.00	35,846
	Tunnel fitter	49.34	\$/hr	370.00	1.00	18,256
	Tunnel electrician	49.34	\$/hr	370.00	1.00	18,256
	Shaft top	47.99	\$/hr	370.00	2.00	35,513
	Crane operator	49.34	\$/hr	370.00	2.00	36,512
	Surface laborer	47.99	\$/hr	370.00	2.00	35,513
	Equipment laborer	48.44	\$/hr	370.00	1.00	17,923
					15.00	\$271,432
Plant						
	Loco	5,000.00	\$/wk	2.20	1.00	11,000
	Muck cars & grout cars	1,900.00	\$/wk	2.20	6.00	25,080
	Flat cars	310.00	\$/wk	2.20	4.00	2,728
	Manriders	310.00	\$/wk	2.20	1.00	682
	Booster fans	800.00	\$/wk	2.20	1.00	1,760
	Transformers & switchgear - LV	750.00	\$/wk	2.20	1.00	1,650
	Other plant	1,400.00	\$/wk	2.20	1.00	3,080
	Man hoists	2,000.00	\$/wk	2.20	1.00	4,400
	Shaft crane	9,000.00	\$/wk	2.20	1.00	19,800
	50T Crane	3,000.00	\$/wk	2.20	1.00	6,600
	TBM Crane	15,000.00	\$/wk	2.20	1.00	33,000
	Compressors	950.00	\$/wk	2.20	1.00	2,090
	Transformers & switchgear - HV	5,200.00	\$/wk	2.20	1.00	11,440
	Surface fans	800.00	\$/wk	2.20	1.00	1,760
						\$125,070

Page 1 of 2

Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Consumables					
Electrical power	0.00	\$/kwh	370.00	600.00	0
Gas oil	0.40	\$/L	15.00	1,000.00	6,000
Lubrication materials	0.00	\$/wk	2.20	1.00	0
Filters etc.	0.00	\$/wk	2.20	1.00	0
Hydraulic oil	0.00	<b>\$</b> /L	0.00	1.00	0
Other consumables	500.00	\$/wk	2.20	1.00	1,100
					\$7,100
Materials					
Temporary materials	500.00	\$/wk	2.20	1.00	1,100
Thrust frame	0.00	\$/wk	2.20	1.00	0
					\$1,100
<b>General Supplies</b>					
Small tools	700.00	\$/wk	2.20	1.00	1,540
					\$1,540
		То	tal Estimated C	ost:	\$406,242

Estimate Definition ID: 2640 Estimated by:

Printed by: whit2782, 8/16/04 11:44:46 AM Page 2 of 2 Checked by:



Version 2.6 Copyright Hatch Mott MacDonald, 2004

**Project Number:** 

**Estimate Description:** 

**Project:** 

**Tunnel Name:** 

Liner production

**NFLink** 

Single Rail Bored

**Construction Activity:** 

**Precast Linings** 

**Tunnel Technique:** 

EPB TBM - Precast segmental

**Estimate Definition ID:** 

**Parent Estimate ID:** 

213789

**Project Phase:** 

1596 Conceptual

Geology Type:

Not Applicable

**Estimate Date:** 

June 01, 2004

**Tunnel Characteristics ID:** 843

#### **Tunnel Characteristics**

26,322 m **Tunnel Length: Finished Diameter:** 7.5 m Final Lining Thickness:  $0.35 \, m$ 

### **Assumptions**

## A) Duration

Maximum	Minimum	
19	15	Months
3	2	Months
86	81	Months
108	98	Months
6	5	Months
1	1	Months
1	1	Months
100	91	Months
	19 3 86 108 6 1	19 15 3 2 86 81 108 98 6 5 1 1 1 1

### **B)** Production

2 % Allowance for Damage Ring Length 1.5 m 17,899 Number of Rings Required

**Production Rate Required** 49.2 Rings/Week Actual Production Rate Achieved 50 Rings/Week

## Investment on plant, equipment and moulds

\$5,000,000

4 Weeks **Initial Shakedown Time Production Time** 358.0 Weeks

	Shakedown Crew	Production / QC Crew
Shifts per Day	1	2
Hours per Shift	12	12
Days per Week	5	5

**Estimate Definition ID:** 2642 Estimated by: Printed by: whit2782, 7/13/04 2:53:36 PM Page 1 of 3 Checked by:

Concrete	12.95	m3/ring	
Reinforcing Steel	120	kg/m3	
Dunnage Assumption	50	% of total requ	ired storage
	\$/Month	Months	Cost
Project Manager Rate	7,000	97	679,000
Plant Manager Rate	5,000	95	475,000
Quality Manager Rate	5,000	93	465,000
Secretary Rate	2,000	97	194,000
Office Building Cost			150,000
Office Equipment and Su	ipplies Cost		0
Finance Assume \$	1,000,000	97	485,000
Financing @	6 %		
Head Office Support @	1 %		1,286,778

\$3,734,778

Profit Margin 10 %

C) Overheads

Printed by: whit2782, 7/13/04 2:53:37 PM

Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Labor					
Shakedown crew	25.00	\$/hr	240.00	30.00	180,000
Production & QC crew	32.00	\$/hr	42,958.00	30.00	41,239,680
				60.00	\$41,419,680
Consumables					
Power	0.06	\$/kwh	43,198.00	1,020.00	2,643,718
Heating	0.11	\$/m2/wk	362.00	10,600.00	422,092
Steam curing	0.54	\$/m2/wk	362.00	2,000.00	390,960
Fuel	0.50	\$/L	362.00	3,000.00	543,000
Water	0.05	\$/L	231,743.00	100.00	1,158,715
					\$5,158,485
Materials					
Concrete	84.00	\$/m3	12.95	17,899.00	19,470,532
Rebar	1.00	\$/kg	1,554.00	17,899.00	27,815,046
Grout nozzles	3.00	\$/Nr	17,899.00	12.00	644,364
Lifting socket	10.00	\$/Nr	17,899.00	12.00	2,147,880
Bolt inserts	5.00	\$/Nr	17,899.00	12.00	1,073,940
Gaskets	100.00	\$/Nr	17,899.00	12.00	21,478,800
Dunnage	2.50	\$/m	18.00	8,949.00	402,705
Site preparation	10.00	\$/m2	12.32	8,949.00	1,102,517
					\$74,135,784
Estimate Definition ID: 2642			Estimated	bv:	

Page 2 of 3

Checked by:

Resource Name	Unit Rate	UOM	Unit Quantity	Resource Quantity	Total
Subcontracts					
Delivery	80.00	\$/hr	2.00	17,899.00	2,863,840
Testing	100,000.00	\$/Nr	1.00	1.00	100,000
					\$2,963,840
			Subto	tal:	\$123,677,789
		Ir	vestment on Pla	ant:	\$5,000,000
		To	tal Overhead C	ost:	\$3,734,778
			Subto	tal:	\$132,412,566
			Pro	ofit:	\$13,241,257
		Total P	recast Lining C	ost:	\$145,653,823
		Total Cos	t per Cubic Me	tre:	\$629
		T	otal Cost per Ri	ing:	\$8,138


Estimate Definition ID: 2642

Printed by: whit2782, 7/13/04 2:53:37 PM

Page 3 of 3

Checked by:

Newfoundland Fixed Link Pre-feasibility Study Cost Estimating Single Bored Railway Tunnel Tunnel Structural Finishes Page 1 of 2
Date: June 07, 2004
Calculation by: A.White



# Newfoundland Fixed Link Pre-feasibility Study

**Cost Estimating** 

Single Bored Railway Tunnel Tunnel Structural Finishes

# Page 2 of 2

**Date:** June 07, 2004 Calculation by: A.White

# **Quantity Take-off**

Concrete					Concrete	Rebar
Element	Nr.	L(m)	b(m)	d(m)	Qty(m3)	Qty(m3)
1	1	26320	0.3	5.9	46586	5590.4
2	1	26320	1.2	0.3	9475.2	1137.0
3	1	26320	1.2	0.3	9475.2	1137.0
					65537 m3	6727 t

## Formwork/falsework

Element	Nr.	L(m)	d(m)	Faces	Area(m2)	
1	1	26320	5.9	2	310576	
2	1	26320	1.2	1	31584	
3	1	26320	1.2	1	31584	
					373744	_ m2

## Rates

Concrete	m3	190
Formwork	m2	140
Reinforcement	t	1600

## Costs

Concrete	m3	65537 m3	at	190	=	12,451,992
Formwork	m2	373744 m2	at	140	=	52,324,160
Reinforcement	t	6727 t	at	1600	=	10,763,827
				\$		75,539,979

### Initialisation

Project: Newfoundland Fixed Link Pre-feasibility Study

Section: North Approach
Option: Bored Rail Tunnel

Date: 8-Jun-04

Calculations by: ANW

Surface gradient -0.08 %

+ sloping same way as track/road - sloping against track/road

Track/Road Gradient 1.663 %

Ground elevation at portal 100 m

Bottom of slab elevation at portal 86.95 m

Total length= 748.7091 m


Total Cost=\$ 7.8 M

Newfoundland Fixed Link Pre-feasibility Study	Date:	8-Jun-04
North Approach	Calculations by:	ANW
Bored Rail Tunnel		

## **UNIT RATES**

## **Materials**

Item	unit	Rate
excavation	m3	60
concrete	m3	190
rebar	tonnes	1600
formwork/falsework	m2	140
SP&L<=4.6m deep	m2	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=6.7m>	m2	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0</td></sp&l<=10.6m>	m2	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=13.7m>	m2	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0</td></sp&l<=16.8m>	m2	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0</td></sp&l<=20.0m>	m2	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0</td></sp&l<=25m>	m2	0
backfill + compact	m3	40
surface reinstatement	m2	30




Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	8446.7	60	506803.8
concrete	m3	1952.708	190.0	371014.6
rebar	tonnes	234.3	1600	374920
formwork/falsework	m2	1736.631	140	243128.3
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>1856.4</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	1856.4	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	681.3253	30	20439.76

Total 1516306




Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	7557.6	60	453456.1
concrete	m3	1796.378	190.0	341311.8
rebar	tonnes	215.6	1600	344904.5
formwork/falsework	m2	1541.218	140	215770.5
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>1661.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	1661.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	681.3253	30	20439.76

Total 1375883




Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	6519.2	60	391149.8
concrete	m3	1490.74	190.0	283240.5
rebar	tonnes	178.9	1600	286222
formwork/falsework	m2	1345.805	140	188412.7
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1465.6</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1465.6	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	666.0704	30	19982.11

Total 1169007




Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	5411.4	60	324683.1
concrete	m3	1115.76	190.0	211994.4
rebar	tonnes	133.9	1600	214225.9
formwork/falsework	m2	1150.392	140	161054.8
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1270.2</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1270.2	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	637.947	30	19138.41

Total 931096.7




Newfoundland Fixed Link Pre-feasibility Study North Approach Bored Rail Tunnel Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	4437.0	60	266219.7
concrete	m3	874.1685	190.0	166092
rebar	tonnes	104.9	1600	167840.4
formwork/falsework	m2	954.9785	140	133697
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1074.8</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1074.8	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	618.181	30	18545.43

Total 752394.5




Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	3564.6	60	213875.5
concrete	m3	734.5642	190.0	139567.2
rebar	tonnes	88.1	1600	141036.3
formwork/falsework	m2	759.5654	140	106339.2
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>879.4</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	879.4	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	606.9972	30	18209.92

Total 619028.1




Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	2727.8	60	163669.9
concrete	m3	630.6044	190.0	119814.8
rebar	tonnes	75.7	1600	121076
formwork/falsework	m2	564.1523	140	78981.33
SP&L<=4.6m deep	m2	683.9	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	597.2265	30	17916.8

Total 501458.9




Newfoundland Fixed Link Pre-feasibility Study North Approach Bored Rail Tunnel

Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	1916.6	60	114994.5
concrete	m3	552.1461	190.0	104907.8
rebar	tonnes	66.3	1600	106012
formwork/falsework	m2	368.7392	140	51623.49
SP&L<=4.6m deep	m2	488.5	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	587.4559	30	17623.68

Total 395161.5




Newfoundland Fixed Link Pre-feasibility Study North Approach Bored Rail Tunnel Date: 8-Jun-04

Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	1130.8	60	67849.13
concrete	m3	499.1891	190.0	94845.93
rebar	tonnes	59.9	1600	95844.31
formwork/falsework	m2	173.3262	140	24265.66
SP&L<=4.6m deep	m2	293.1	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	577.6852	30	17330.56

Total 300135.6



Newfoundland Fixed Link Pre-feasibility Study North Approach Bored Rail Tunnel

Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	376.2	60	22570.21
concrete	m3	477.3395	190.0	90694.51
rebar	tonnes	57.3	1600	91649.18
formwork/falsework	m2	-22.08692	140	-3092.169
SP&L<=4.6m deep	m2	97.7	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	576.506	30	17295.18

Total 219116.9

Newfoundland Fixed North Approach Bored Rail Tunnel	a Link Pre-fo	easibility Study Calc		
ummary of Costs		Markup for adjacent	0 %	
	Section  1 2 3 4 5 6 7 8 9 10 Sub-total	Cost 1516306 1375883 1169007 931096.7 752394.5 619028.1 501458.9 395161.5 300135.6 219116.9 7779588		

#### Initialisation

Project: Newfoundland Fixed Link Pre-feasibility Study

Section: South Approach
Option: Bored Rail Tunnel

Date: 8-Jun-04

Calculations by: ANW

Surface gradient 0 %

+ sloping same way as track/road - sloping against track/road

Track/Road Gradient 1.663 %

Ground elevation at portal 100 m

Bottom of slab elevation at portal 86.95 m

Total length= 784.7264 m


Total Cost=\$ 8.2 M

Newfoundland Fixed Link Pre-feasibility Study	Date:	8-Jun-04
South Approach	Calculations by:	ANW
Bored Rail Tunnel		

#### **UNIT RATES**

#### **Materials**

materiale		
Item	unit	Rate
excavation	m3	60
concrete	m3	190
rebar	tonnes	1600
formwork/falsework	m2	140
SP&L<=4.6m deep	m2	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=6.7m>	m2	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0</td></sp&l<=10.6m>	m2	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=13.7m>	m2	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0</td></sp&l<=16.8m>	m2	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0</td></sp&l<=20.0m>	m2	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0</td></sp&l<=25m>	m2	0
backfill + compact	m3	40
surface reinstatement	m2	30




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel

Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	8853.1	60	531184
concrete	m3	2046.645	190.0	388862.5
rebar	tonnes	245.6	1600	392955.8
formwork/falsework	m2	1820.173	140	254824.2
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>1945.7</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	1945.7	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	714.101	30	21423.03

Total 1589250




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	7921.2	60	475269.9
concrete	m3	1882.794	190.0	357730.9
rebar	tonnes	225.9	1600	361496.5
formwork/falsework	m2	1615.359	140	226150.3
SP&L<=4.6m deep	m2	0.0	0	0
4 6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>1740.9</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	1740.9	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	714.101	30	21423.03

Total 1442071




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	6832.8	60	409966.4
concrete	m3	1562.453	190.0	296866
rebar	tonnes	187.5	1600	299990.9
formwork/falsework	m2	1410.546	140	197476.4
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1536.1</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1536.1	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	698.1122	30	20943.37

Total 1225243




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel

Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	5671.7	60	340302.3
concrete	m3	1169.435	190.0	222192.6
rebar	tonnes	140.3	1600	224531.5
formwork/falsework	m2	1205.732	140	168802.5
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1331.3</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1331.3	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	668.6359	30	20059.08

Total 975887.9




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	4650.4	60	279026.4
concrete	m3	916.2211	190.0	174082
rebar	tonnes	109.9	1600	175914.5
formwork/falsework	m2	1000.919	140	140128.6
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1126.5</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1126.5	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	647.9192	30	19437.57

Total 788589




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel Date: 8-Jun-04 Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	3736.1	60	224164.1
concrete	m3	769.901	190.0	146281.2
rebar	tonnes	92.4	1600	147821
formwork/falsework	m2	796.1049	140	111454.7
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>921.7</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	921.7	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	636.1973	30	19085.92

Total 648806.9




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel

Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	2859.1	60	171543.4
concrete	m3	660.9402	190.0	125578.6
rebar	tonnes	79.3	1600	126900.5
formwork/falsework	m2	591.2913	140	82780.79
SP&L<=4.6m deep	m2	716.8	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	625.9566	30	18778.7

Total 525582




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	2008.8	60	120526.4
concrete	m3	578.7075	190.0	109954.4
rebar	tonnes	69.4	1600	111111.8
formwork/falsework	m2	386.4778	140	54106.89
SP&L<=4.6m deep	m2	512.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	615.716	30	18471.48

Total 414171




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel Date: 8-Jun-04 Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	1185.2	60	71113.07
concrete	m3	523.203	190.0	99408.58
rebar	tonnes	62.8	1600	100455
formwork/falsework	m2	181.6642	140	25432.98
SP&L<=4.6m deep	m2	307.2	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	605.4753	30	18164.26

Total 314573.9



Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel

Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	394.3	60	23655.97
concrete	m3	500.3023	190.0	95057.44
rebar	tonnes	60.0	1600	96058.04
formwork/falsework	m2	-23.14943	140	-3240.92
SP&L<=4.6m deep	m2	102.4	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	604.2393	30	18127.18

Total 229657.7

Newfoundland Fixed Link Pre-feasibility Study Date: 8-Jun-04 South Approach Calculations by: ANW Bored Rail Tunnel Summary of Costs Markup for adjacent 0 Section Cost 1 1589250 2 1442071 3 1225243 4 975887.9 5 788589 6 648806.9 7 525582 8 414171 9 314573.9 10 229657.7 Sub-total 8153832


Newfoundland Fixed Link Pre-feasibility Study Tunnel Drainage Bored Railway Tunnel Drainage Costs

# Page 1 of 1

Calculation by: ANW

**Date:** June 8, 2004

#### **Sump Sizing**



#### **Piping**

Assume 300 mm diameter steel pipe connecting each sump to the portal areas

Number of pipes= 1

Assume sumps located at 1/3 and 2/3 of tunnel length

Total length of piping= 18967 m

#### **Rates**

Sump construction-\$ 17795 /m of sump

Pipe-\$ 265 /m of pipe

Pipe installation labour -\$ 29 /m of pipe (assume 6 man crew installing 100m/day)
Pipe installation equipment-\$ 10 /m of pipe (assume \$1000/day for equipment)

Pumps-\$ 125000 /pump

#### Costs

Item	Unit	Qty	Rate	\$-Cost
Sump construction	m	88	17795	1,565,960
Pipe	m	18967	265	5,026,167
Pipe installation	m	18967	29	546,240
Equipment	m	18967	10	189,667
Pumps	Nr	4	125000	500,000
			Total	7,828,033

# Newfoundland Fixed Link Estimation of Capital Cost of Rail System

Table  $\overline{\mathbf{z}}$  - Estimated Capital Cost, not including Real Estate

	/cent	Qty	Unit	UnitPrice	Cosr
A	Rolling Stock			500000000000000000000000000000000000000	uganogani
	Locomotile -	5	Еа	2,750,000	13,750,000
	Transfer cars (\$td + 25% for mods)	1	Ea	162,671	1,138,699
	Auto/truck carriers &td + 25% form ods)	42	Ea	214,041	8,989,726
	Track III oblik	1	Еа	75,000	75,000
8	Track work				
	Track attern hals (hcl.subgrade&ballast)	5,060	m	500	2,530,000
	#20 Trinorts		Еа	150,000	امر 800 م
C	OCS System				
	OCS in tunnel	1	Ea	4,062,629	↓Д62,629
	OCS at 16 m hak	2	Еа	1,068,271	2,136,543
	OCS at Maint, Facility	1	EA	28,214	28,214
	Substations	2	Еа	1,535,714	3,071,429
D	Train Signal System			- Sive Some b	
	Microprocessor Based Signalling System	330	Еа	4,472,000	4,472,000
	Powered de 🗷 🎉	2	Еа	60,000	120,000
	Power seruice to bungalows and ways ide cabinets	1	Ea	500,000	500,00C
	Fibre optical cable and correspondance equipment		Ea	1,000,000	0 م م م م 1
	Radio system	1 14	Еа	500,000	500,000
Е	Loading/Unloading Facility				
	Staging area ducil, ramps, liquiting	50,000	Mi <sup>2</sup>	25	1,250,000
	Loading control system (Incl. CCTV)	2	Еа	250,000	500,000
	Operations building (complete)	120	m <sup>2</sup>	1,800	216,000
	Public tacilities building (complete)	50	m <sup>2</sup>	1,600	200,00
F	Wali terance & Emergency Response	JU.	10 7 8 7	1,000	יטע, טיי
	Train maintenance bidg	1,200	m <sup>2</sup>	2,000	2 100 000
					2,400,000
	Site maintenance bidg	144	m <sup>2</sup>	1,500	216,000
	Emergency enactation bus w/highrali gear	2	Ea	100,000	200,000
	Stow plow	2	Ea	100,000	200,000
	Pick-up truck with high all gear	2	Еа	60,000	120,000
	SUV	2	Еа	50,000	100,000
	Tunnel fire engine () ightalim ourted)	2	Еа	180,000	360,000

#### Estimation of annual operating and maintenance costs

A. Energy Costs					
1. Tunnel lighting	3000000 kWh/yr @	0.1	\$/kWh= \$	300000	/yr
2. Ventilation fans	400000 kWh/yr @	0.1	\$/kWh= \$	40000	/yr
3. Sump pumps	20000 kWh/yr @	0.1	\$/kWh= \$	2000	/yr
					•
		Su	b-total A - \$	342000	/vr

#### **B. Electrical Maintenance Costs**

1. Labour (Assume 1 electricians for 5 days per week throughout year)

```
Electrician 1 2080 hrs/yr @ 65 $/hr= $ 135200 /yr
```


2. Materials/replacement of equipment (assume electrical equipment replaced once every 40 years)

#### C. Mechanical Maintenance Costs

1. Labour (Assume 1 mechanic/maintenance technician for 5 days per week throughout year)

```
Mechanic 2080 hrs/yr @ 65 $/hr= $ 135200 /yr
```

2. Materials/replacement of equipment (assume mechanical equipment replaced every 40 years)



contd.

#### Estimation of annual operating costs

#### **D. Structure Maintenance Costs**

1. Inspection (assume 3 man inspection crew for 10 weeks once every 4 years)

Senior engineer	100	hrs/yr @	130	\$/hr=	\$ 13000	/yr
Engineer 1	100	hrs/yr @	100	\$/hr=	\$ 10000	/yr
Engineer 2	100	hrs/yr @	100	\$/hr=	\$ 10000	/yr

2. Tunnel Cleaning (Assume 4 man crew for 13 weeks once a year)

```
Labourers 2080 hrs/yr @ 60 $/hr= $ 124800 /yr
```

3. Sump clean-up (Assume 2 man crew for 2 days twice a year)

```
Labourers 64 hrs/yr @ 50 $/hr= $ 3200 /yr
```


4. Structure maintenance (Assume 4 man crew for 13 weeks once a year)

```
Labourers 2080 hrs/yr @ 50 $/hr= $ 104000 /yr
```

5. Permanent Way Inspection (Assume 2 men inspect track 3 times per week)

```
Labourers 312 hrs/yr @ 50 $/hr= $ 15600 /yr
```

6. Permanent way maintenance (Assume 4 man crew for 12 weeks once a year)



Sub-total D - \$ 215600 /yr

Total estimated maintenance cost=\$ 895,500 /yr

# Newfoundland Fixed Link Rail System – Estimation of Annual Operating Cost

Table  $\overline{\mathbf{3}}$  - Estimated Shutifle Service Annual Operating Cost

	/cem				Annual Cos
	rlss umptions			3 5	
	Facility operates 17 hours fday, 7 days (week, 50 per cent of this time the facility is fully staffed with toll collectors, the remainder of the time only 1 toll booth is operating on each side.				
٩	Salarled Staff	Mart.	Unit	Rate	
	Tittel Marager	1.40	Year	100,000	140,000
	Tennel Operator	1.40	Year	100,000	140,000
	Apprestice Operator	1.40	Year	60,000	84,00
	Sitte Maintenance Mgr	1.40	Year	50,000	70,00
8	Hourty Statf	Quant	Unit	Rate	
	Toll collectors - (2 FT, 4 PT, 1 PT Spare)	7,000	16	50	350,000
	Sitte Labor	4,000	1	35	140,000
	Electricians	6,000	- 1	65	390,000
	Mechanics	6,000	- 10	60	360,000
	Train drive s	8,000	- 1	85	680,000
	Loading to reman	4,000	- 1	55	220,000
	Laborers	20,000	- 1	40	800,000
0	Subcontracted Work	- 5- 5		3 5	115
	Locomothe maintenance	1	LS	120,000	120,000
	Rolling s took maintenance	. 1	LS	25,000	25,00
	Facility clearing	52	W	250	13,000
	Landscaping	52	₩	500	26,000
	Bit liding miainte nance		LS	10,000	10,00
D	Power	Quant	Unit	Rate	200,000,000
		8,922	MOU-h	60	535,324
E	Equipment Depreciation (straight-line)	LHe	Unit	Cap. Cost	10 10000000
	Locomothes (20 years)	20	Year	13,750,000	687,500
	Rolling s tock (20 years)	20	Year	10,128,425	506,42
	B + lidings	30	Year	2,912,000	97,06
	Roads	30	Year	1,250,000	41,66
	Trackwook	25	Year	3,130,000	125,200
	OCS system	15	Year	9,298,814	619,92
	Signal system	15	Year	6,592,000	439,461
	Train loading system	12	Year	500,000	€1,667
	Heatry ue li loles	12	Year	560,000	46,66
	Light trucks	7	Year	220,000	31,42
	TAL ANNUAL OPERATING COST OF SHUTTLE TR	(6.10)		(C)	\$ 6,740,328

# Newfoundland Fixed Link Pre-feasibility Study Preferred Fixed Link Option - TBM Bored Railway Tunnel Basis of Estimate

#### Scope

#### Estimate includes:

- mobilisation of equipment and materials
- TBM bored tunnel excavation and lining
- TBM bored tunnel finishes
- north and south approaches to TBM bored rail tunnel
- north and south rail terminals including passenger facilities, maintenance facilities, tolling areas
- tunnel trackwork, drainage, ventilation, mechanical & electrical items
- shuttle trains, signalling, and OCS system
- allowances for indirect costs, contractor profit, and risk allowances

#### Estimate does not include:

- land purchase costs
- approach roads to the terminal areas (addressed separately)
- provision for bringing electrical power to the facility

#### **Assumptions**

#### **Principal Assumptions:**

- labour wages in accordance with Local 2003 Collective Agreement for Newfoundland & Labrador
- 7.5 metre internal diameter tunnel driven from Newfoundland side using an EPB type tunnel boring machine configured for rock
- tunnel approximately 26.3 kilometres in length
- 3 eight hour shifts 5 days per week for tunnelling operations
- tunnel lined with bolted precast concrete segmental tunnel liner
- average tunnelling advance rate of 81 metres per week
- tunnel drive encounters 14 faults each 100 metres wide where advance rate decreases by approximately 60%
- rail mounted loco and muck car system used for removal of tunnel spoil
- longitudinal system used for ventilation of the tunnel (permanent facility)

#### Costs

#### Cost assumptions

- All costs in 2004 Canadian dollars
- HST not included

Newfoundland Fixed Link Pre-feasibility Study Cost Estimating Drill & Blast Railway Tunnel Tunnel Structural Finishes Page 1 of 2
Date: June 07, 2004
Calculation by: A.White

Tunnel length= 30667 m

Element 1

Element 2

# Newfoundland Fixed Link Pre-feasibility Study

**Cost Estimating** 

Drill & Blast Railway Tunnel

**Tunnel Structural Finishes** 

## Page 2 of 2

**Date:** June 07, 2004 **Calculation by:** A.White

## **Quantity Take-off**

Concrete					Concrete	Rebar
Element	Nr.	L(m)	b(m)	d(m)	Qty(m3)	Qty(m3)
1	1	30667	0.3	6.9	63481	7617.7
2	1	30667	1.5	0.3	13800	1656.0
3	1	30667	1.5	0.3	13800	1656.0
4	1	30667	5.5	1.0	168669	20240.2
					259749 m3	31170 t

#### Formwork/falsework

Element	Nr.	L(m)	d(m)	Faces	Area(m2)
1	1	30667	6.9	2	423204.6
2	1	30667	1.5	1	46000.5
3	1	30667	1.5	1	46000.5
4	1	30667	0	0	0
					515205.6 m2

#### Rates

Concrete	m3	190
Formwork	m2	140
Reinforcement	t	1600

#### Costs

Concrete	m3	259749 m3	at	190	=	49,352,403
Formwork	m2	515206 m2	at	140	=	72,128,784
Reinforcement	t	31170 t	at	1600	=	49,871,902
				\$		171,353,089

#### **Newfoundland Fixed Link Pre-feasibility Study Drill and Blast Rail Tunnel Tunnel Final Liner Cost Estimate**

Tunnel length= 30667 m Liner cross section area= 13.5 m2

## Shift pattern

Shifts	Hours	Days
3	8	5

Advance rate= 10 m/day

t/m3 of concrete Rebar ratio= 0.12

Concrete supply=\$ 135 /m3

Rebar supply=\$ 900

Initial form set-up time= weeks 4

#### **Durations**

Number of days= 3087 days Number of hours= 74081 hours Number of weeks= 617 weeks

#### Labour

Crew size 20 Average labour rate \$ 47 /hour

Total labour cost=\$ 69,635,952

#### **Equipment**

Form \$ 1000000 Weekly cost of other equipment \$ 15000 (see TED 2370)

Total equipment cost=\$ 10,260,100

#### **Materials Cost Summary**

Concrete= 414004.5 m3 Rebar= 49680.54

Concrete cost=\$ 55,890,608 Rebar cost=\$ 44,712,486

Total material cost=\$ 100,603,094

Labour 69,635,952 Equipment 10,260,100 Materials 100,603,094

Total 180,499,146

#### Initialisation

Project: Newfoundland Fixed Link Pre-feasibility Study

Section: North Approach
Option: D&B Rail Tunnel

Date: 8-Jun-04

Calculations by: ANW

Surface gradient 0 %

+ sloping same way as track/road
- sloping against track/road

Track/Road Gradient 1.663 %

Ground elevation at portal 100 m

Bottom of slab elevation at portal 86.95 m

Total length= 784.7264 m


Total Cost=\$ 8.2 M

Newfoundland Fixed Link Pre-feasibility Study	Date:	8-Jun-04
North Approach	Calculations by:	ANW
D&B Rail Tunnel		

#### **UNIT RATES**


#### **Materials**

Item	unit	Rate
excavation	m3	60
concrete	m3	190
rebar	tonnes	1600
formwork/falsework	m2	140
SP&L<=4.6m deep	m2	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=6.7m>	m2	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0</td></sp&l<=10.6m>	m2	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=13.7m>	m2	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0</td></sp&l<=16.8m>	m2	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0</td></sp&l<=20.0m>	m2	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0</td></sp&l<=25m>	m2	0
backfill + compact	m3	40
surface reinstatement	m2	30




## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	8853.1	60	531184
concrete	m3	2046.645	190.0	388862.5
rebar	tonnes	245.6	1600	392955.8
formwork/falsework	m2	1820.173	140	254824.2
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>1945.7</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	1945.7	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	714.101	30	21423.03




## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	7921.2	60	475269.9
concrete	m3	1882.794	190.0	357730.9
rebar	tonnes	225.9	1600	361496.5
formwork/falsework	m2	1615.359	140	226150.3
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>1740.9</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	1740.9	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	714.101	30	21423.03



## Calculated costs


Item	Unit	Quantity	Rate	Cost
excavation	m3	6832.8	60	409966.4
concrete	m3	1562.453	190.0	296866
rebar	tonnes	187.5	1600	299990.9
formwork/falsework	m2	1410.546	140	197476.4
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1536.1</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1536.1	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	698.1122	30	20943.37



## Calculated costs


Item	Unit	Quantity	Rate	Cost
excavation	m3	5671.7	60	340302.3
concrete	m3	1169.435	190.0	222192.6
rebar	tonnes	140.3	1600	224531.5
formwork/falsework	m2	1205.732	140	168802.5
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1331.3</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1331.3	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	668.6359	30	20059.08

Total 975887.9



## Calculated costs


Item	Unit	Quantity	Rate	Cost
excavation	m3	4650.4	60	279026.4
concrete	m3	916.2211	190.0	174082
rebar	tonnes	109.9	1600	175914.5
formwork/falsework	m2	1000.919	140	140128.6
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1126.5</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1126.5	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	647.9192	30	19437.57



## Calculated costs


Item	Unit	Quantity	Rate	Cost
excavation	m3	3736.1	60	224164.1
concrete	m3	769.901	190.0	146281.2
rebar	tonnes	92.4	1600	147821
formwork/falsework	m2	796.1049	140	111454.7
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>921.7</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	921.7	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	636.1973	30	19085.92

Total 648806.9




## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	2859.1	60	171543.4
concrete	m3	660.9402	190.0	125578.6
rebar	tonnes	79.3	1600	126900.5
formwork/falsework	m2	591.2913	140	82780.79
SP&L<=4.6m deep	m2	716.8	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	625.9566	30	18778.7



## Calculated costs


Item	Unit	Quantity	Rate	Cost
excavation	m3	2008.8	60	120526.4
concrete	m3	578.7075	190.0	109954.4
rebar	tonnes	69.4	1600	111111.8
formwork/falsework	m2	386.4778	140	54106.89
SP&L<=4.6m deep	m2	512.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	615.716	30	18471.48



## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	1185.2	60	71113.07
concrete	m3	523.203	190.0	99408.58
rebar	tonnes	62.8	1600	100455
formwork/falsework	m2	181.6642	140	25432.98
SP&L<=4.6m deep	m2	307.2	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	605.4753	30	18164.26

Total 314573.9



## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	394.3	60	23655.97
concrete	m3	500.3023	190.0	95057.44
rebar	tonnes	60.0	1600	96058.04
formwork/falsework	m2	-23.14943	140	-3240.92
SP&L<=4.6m deep	m2	102.4	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	604.2393	30	18127.18

Total 229657.7

Newfoundland Fixed North Approach D&B Rail Tunnel	d Link Pre-f	easibility Study Calc	Date: 8-Jun-04 ulations by: ANW
Summary of Costs		Markup for adjacent	0 %
	Section	Cost	,
	1	1589250	
	2	1442071	
	3 4	1225243 975887.9	
	5	788589	
	6	648806.9	
	7 8	525582 414171	
	9	314573.9	
	10 Sub-total	229657.7 8153832	
	oub total	0100002	

#### Initialisation

Project: Newfoundland Fixed Link Pre-feasibility Study

Section: South Approach
Option: Bored Rail Tunnel

Date: 8-Jun-04

Calculations by: ANW

Surface gradient 0 %

+ sloping same way as track/road - sloping against track/road

Track/Road Gradient 1.663 %

Ground elevation at portal 100 m

Bottom of slab elevation at portal 86.95 m

Total length= 784.7264 m


Total Cost=\$ 8.2 M

Newfoundland Fixed Link Pre-feasibility Study	Date:	8-Jun-04
South Approach	Calculations by:	ANW
Bored Rail Tunnel		

#### **UNIT RATES**

#### **Materials**

Item	unit	Rate
excavation	m3	60
concrete	m3	190
rebar	tonnes	1600
formwork/falsework	m2	140
SP&L<=4.6m deep	m2	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=6.7m>	m2	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0</td></sp&l<=10.6m>	m2	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=13.7m>	m2	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0</td></sp&l<=16.8m>	m2	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0</td></sp&l<=20.0m>	m2	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0</td></sp&l<=25m>	m2	0
backfill + compact	m3	40
surface reinstatement	m2	30



Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel


Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	8853.1	60	531184
concrete	m3	2046.645	190.0	388862.5
rebar	tonnes	245.6	1600	392955.8
formwork/falsework	m2	1820.173	140	254824.2
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>1945.7</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	1945.7	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	714.101	30	21423.03

Total 1589250

Date: 8-Jun-04




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	7921.2	60	475269.9
concrete	m3	1882.794	190.0	357730.9
rebar	tonnes	225.9	1600	361496.5
formwork/falsework	m2	1615.359	140	226150.3
SP&L<=4.6m deep	m2	0.0	0	0
4 6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>1740.9</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	1740.9	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	714.101	30	21423.03

Total 1442071

Date: 8-Jun-04




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	6832.8	60	409966.4
concrete	m3	1562.453	190.0	296866
rebar	tonnes	187.5	1600	299990.9
formwork/falsework	m2	1410.546	140	197476.4
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1536.1</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1536.1	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	698.1122	30	20943.37

Total 1225243

Date: 8-Jun-04




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel

Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	5671.7	60	340302.3
concrete	m3	1169.435	190.0	222192.6
rebar	tonnes	140.3	1600	224531.5
formwork/falsework	m2	1205.732	140	168802.5
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1331.3</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1331.3	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	668.6359	30	20059.08


Total 975887.9



# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	4650.4	60	279026.4
concrete	m3	916.2211	190.0	174082
rebar	tonnes	109.9	1600	175914.5
formwork/falsework	m2	1000.919	140	140128.6
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1126.5</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1126.5	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	647.9192	30	19437.57

Total 788589




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel Date: 8-Jun-04 Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	3736.1	60	224164.1
concrete	m3	769.901	190.0	146281.2
rebar	tonnes	92.4	1600	147821
formwork/falsework	m2	796.1049	140	111454.7
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>921.7</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	921.7	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	636.1973	30	19085.92

Total 648806.9




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel

Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	2859.1	60	171543.4
concrete	m3	660.9402	190.0	125578.6
rebar	tonnes	79.3	1600	126900.5
formwork/falsework	m2	591.2913	140	82780.79
SP&L<=4.6m deep	m2	716.8	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	625.9566	30	18778.7


Total 525582



# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	2008.8	60	120526.4
concrete	m3	578.7075	190.0	109954.4
rebar	tonnes	69.4	1600	111111.8
formwork/falsework	m2	386.4778	140	54106.89
SP&L<=4.6m deep	m2	512.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	615.716	30	18471.48

Total 414171




Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel Date: 8-Jun-04 Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	1185.2	60	71113.07
concrete	m3	523.203	190.0	99408.58
rebar	tonnes	62.8	1600	100455
formwork/falsework	m2	181.6642	140	25432.98
SP&L<=4.6m deep	m2	307.2	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	605.4753	30	18164.26

Total 314573.9



Newfoundland Fixed Link Pre-feasibility Study South Approach Bored Rail Tunnel

Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	394.3	60	23655.97
concrete	m3	500.3023	190.0	95057.44
rebar	tonnes	60.0	1600	96058.04
formwork/falsework	m2	-23.14943	140	-3240.92
SP&L<=4.6m deep	m2	102.4	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	604.2393	30	18127.18

Total 229657.7

Newfoundland Fixed South Approach Bored Rail Tunnel	d Link Pre-feasibility Study Date: 8-Jun-04 Calculations by: ANW			
Summary of Costs		Markup for adjacent	0 %	
	Section     1     2     3     4     5     6     7     8     9     10 Sub-total	Cost 1589250 1442071 1225243 975887.9 788589 648806.9 525582 414171 314573.9 229657.7 8153832		



Newfoundland Fixed Link Pre-feasibility - Drill & Blast Railway Tunnel - Cost Summary

	BORED TUI	NNEL CONSTRUCTION COSTS
ITEM	UNIT	MAIN TUNNEL
MOBILIZATION & DEMOBILIZATION	LS	8,000,000
DRILL & BLAST TUNNELLING	LS	606,989,049
TUNNEL FINAL LINER	LS	180,499,146
TUNNEL FINISHES	LS	171,353,089
NORTH APPROACH STRUCTURES	LS	8,153,832
SOUTH APPROACH STRUCTURES	LS	8,153,832
RAIL TRACK	LS	16,086,400
TUNNEL DRAINAGE	LS	7,820,000
UTILITY DIVERSIONS	LS	1,000,000
MONITORING	LS	1,000,000
SUBTOTAL CIVIL		\$1,009,055,348
CIVIL CONTINGENCIES		
CONTINGENCY	40%	\$403,622,139
TOTAL CIVIL		\$1,412,677,487
M&E, ROL	LING STOCK	, RAIL HARDWARE AND FINISHING WORK
ROLLING STOCK, TERMINALS, OCS, ETC	LS	\$48,000,000
VENTILATION EQUIPMENT	LS	\$3,000,000
VENTILATION SHAFTS AND BUILDINGS x 2	LS	\$0
FIRE SUPPRESSION SYSTEM	LS	\$2,000,000
CONTROL CENTRE	LS	\$1,000,000
SIGNALLING	LS	\$1,000,000
LIGHTING	LS	\$1,000,000
CCTV SYSTEM	LS	\$0
GAS DETECTION	LS	\$900,000
SUBSTATION, GENERATORS, UPS	LS	\$2,000,000
		¥-1555(555
SUBTOTAL M&E AND FINISHING		\$58,900,000
		***************************************
CONTINGENCIES	20%	\$11,780,000
CONTINUENCIES	2070	\$11,100,000
TOTAL M&E AND FINISHING		\$70,680,000
TOTAL MIGLAND I MIOTING		<b>V. 3,500,500</b>
TOTAL CIVIL, M&E AND FINISHING		\$1,483,357,487
TOTAL SIVIL, IIIGL AND TIMOTIMO		<b>V</b> 1,100,001,101
ALLOWANCES		
ALLOWATOLO		
CONTRACTOR OH	15%	\$222,503,623
CONTRACTOR PROFIT	15%	\$222,503,623
	1570	Ψ222,000,020
CONSTRUCTION TOTAL		\$1,929,000,000
CONTROL TO TAL	PRF_CONS	TRUCTION AND SUPERVISION
FEASIBILITY STUDY	LS	\$11,000,000
ENVIRONMENTAL ASSESSMENT	LS	\$4,000,000
DESIGN	5%	\$96,450,000
CONSTRUCTION MANAGEMENT	10%	\$192,900,000
OWNERS COSTS	2%	\$38,580,000
OVVINEING GOOTS	Z 70	φου,ουυ,ουυ
DDE CONSTRUCTION TOTAL		\$342,930,000
PRE-CONSTRUCTION TOTAL		\$342'A20'000
CDAND TOTAL		\$2.274.020.000
GRAND TOTAL	l	\$2,271,930,000



# **Tunnel Estimating Database**

Copyright Hatch Mott MacDonald, 2002 Version VANC-1.0

P:MEMORIAL 21 3789 | DES C | Cost Estimating & Scheduling Costs 4 - End Sept Final SingleRailD&Brev [Nwfld Cost - Rail - June 1 | 2004 xls] TED Title Page

Project Number: 213789

**Estimate Description:** 

Project:

Newfoundland Fixed Link Study Prefeasibility Level

Project Phase: Prefeasibility Design

Estimate Date: June 11 2004

# Newfoundland Fixed Link Study Prefeasibility Level

213789

Prefeasibility Design

June 11 2004

STRUCTION AND SUPERVISION

Printed: 9:14 AM on 11/25/04



# **Tunnel Estimating Database**

Copyright Hatch Mott MacDonald, 2002 Version VANC-1.5

**Detailed Cost Estimate Report** 

P:MEMORIALI213789/DESC/Cost Estimating & Scheduling/Costs 4 - End SeptFinal/SingleRailD&BRev/[Nwfld Cost - Rail - June 11 2004.xls]V-315

Project:Newfoundland Fixed Link StudyProject Number:213789Estimate Description:Prefeasibility LevelParent Estimate ID:V-300

Tunnel Name: Railway Tunnel - Down Drive Project Phase: Prefeasibility Design

Construction Activity: Excavation (Drill & Blast) & Initial Support Geology Type: Poor to Fair Sediments & Volcanics

Construction Activity:	Excavati	on (Drill & Blast) & Initial Su	аррогі	Geology Type:	roof to rail Sedillio	ints & volcanies
Estimate Definition ID:	V-315			Estimate Date:	June 11 2004	
	Tunnel	<u>Characteristics</u>		Sh	ift Details	
Tunnel Length:	15,333.0		m	Shift Arrangement:	3.0	Shifts / Day
Design Width:	6.4		m		8.0	Hours / Shift
Design Wall Height (Ave.)	6.6		m		7.0	Days / Week
Design Wall to Roof:	2.5			Drill, Charge, Blas	st, Vent & Muckin	g Details
Design Max Height :	9.1		m	Survey Tunnel / Holes / Map:	30.0	Min / Cycle
Ave Tunnel Overbreak:	20.0		cm	<b>Drilling Blast Holes:</b>		
Tunnel Face Area:	59.3	(Includes Overbreak)	$m^2$	Hole Length:	3.9	m / Hole
Crown Perimeter:	9.6	(Includes Overbreak)	m	Perim. Blast Hole Spacing:	0.50	m
Wall & Crown Perimeter:	23.2	(Includes Overbreak)	m	Interior Blast Hole Spacing:	1.25	m
Wall & Crown Area:	355,933	(Includes Overbreak)	$m^2$	No. Perimeter Holes:	46	No.
Neat Tunnel Excav. Vol.:	909,246	(Includes Overbreak)	$m^3$	No. Interior Area Holes:	38.0	No.
Re-Muck / Pull-Out Bays:				No. Blast Initiation Holes:	14	No.
Bay Length:	10.0		m	Number of Drillholes / Blast:	99	Blastholes / Blast
Spacing Bttn Bays:	1000.0		m	Blast Hole / Face Area Ratio:	1.67	Holes / m <sup>2</sup>
Number of Bays:	15		No.	Typical / Check Ratio:	<u>1.56</u>	Holes / m <sup>2</sup>
Total Length of Bays:	150.0		m	Drill Eqpt Set-Up Time:	40	min / Set-up
Neat Excavation Vol.:	8,895		$m^3$	Drill Penetration Rate:	0.30	m / M in
Total Tunnel Volume:	918,141		$m^3$		18	m/hour
Muck Bulking Factor:	1.6		Ratio	# of Drills or Booms:	3.0	No.
Bulked Tunnel Volume:	1,469,02	5 (Loose Muck Volume)	$m^3$	Charging & Blasting:		
Prin	ary Muck	ing Production Details		Prime & Load Rate / Hole:	2.50	min / Blasthole
Activity to remove blast muc	k from fac	e to conveyor & muck cars)		Prep & Hook-up Time:	40.0	min / Set-up
Muck Volume / Blast:	313.1	,	$m^3$	Total No. Blasts / Tunnel:	4692	No.
Mucking Volume / Trip:	5.00		$m^3$	Net Blast Break Length:	3.3	m / Blast
Bucket Fill Factor (%):	90.0		%	Blast & Ventilation Time:	1.0	Hours
Number of Trips:	70		No.	Pre-Excavava	tion Grouting De	tails
Ave. Dist. to Load:		(Ave Distance One Way)	m	% Tunnel to be Grouted:	10.0	%
Ave. Tramming Speed:	8.0	27	km/hr	Tunnel Length to Grout:	1533	m
Load, Dump, Manoever:		ime per Trip)	Min	Grout Hole Length:	7.0	m
Face Cleanup / Blast:	15.0		Min	No. of Grouting Applications:	219	No.
Mucking Time:	2.0		Hours	Perim. Grout Holes Spacing:	1.50	m
Mucking Rate:	155.1		m <sup>3</sup> / Hour	# Perim. Grout Holes:	15	Holes / Grout Cycl
		pport Class Details		Drilling Penetration Rate:	50	m/hour
		%)	0 (m)	No. of Drill Booms:	2	No.
Class II - Spot Bolts:		%)	0 (m)	Drilling Time per Cycle:	237	Min
Class III - Crown Only:		(%)	6,133 (m)	Grout Eqpt. Set-Up Time:	1.0	Hours / Grout Cyc
Class IV - Full Pattern:		%)	7,667 (m)	No. of Holes Grouted at Once:	2	Hoses
Class V - Steel Sets:	`	%)	1,533 (m)	Grouting Injection Rate:	10	min / Drillhole
Total	100.0		15,333 (m)	Full Grout Cycle Time:	122.7	Hours
		rete Support Details	10,000 ()	•	nstallation Details	
Support Arc Length:	23.2		m	Steel Set Spacing:	1.0	m
Thickness:	25.0		mm	Total No. Sets / Tunnel:	1,533	No.
I HICKHUSS.						

Time: 0.8 (Includes Scaling & Equip Set-up) Hours

Total Installation Time:

4,600

Hours

Estimated by: \_\_\_\_PJP\_\_\_\_ Checked by: \_\_\_\_

Printed: 9:14 AM on 11/25/04 Page 4 of 11

	<u>Viremesh Installation Details</u>	2	Roc	kbolt Support Class Deta	<u>ils</u>
Install Rate:	100	m <sup>2</sup> / Hour	(Bolt	s Per	(Bolts Per Suppo
Total Install Time:	3,924.2	Hours	<u>Ro</u>	w) (Bolts Per m)	<u>Class</u> )
Ave. Install Time:	50.2	Min	Class I:	0.0	0
Overlap:	5	%	Class II:	0.0	0
Net Applied Area:	355,933 (Assume Class V only)	m <sup>2</sup>	Class III:	4.0	24,533
Area with Overlap:	392,416	m <sup>2</sup>	_Class IV: 1	5 10.0	76,665
<u>Final</u>	Shotcrete Support Class Details		Class V:	0.0	<u>0</u>
hotcrete Thickness:			Total:		101,198
Classes I and II:	0	mm		Face Scaling	
Class III:	0	mm	Scaling Time:	20.0	min / Blast
Classes IV:	50	mm	<u>Ro</u>	ockbolt Installation Detail	<u>ls</u>
Class V:	100	mm	Rockbolt Length:	3.0	m
upport Arc Length:			Row Spacing:	1.5	m
Class I:	0.0	m	No. Rockbolts Required	: 101,198	No.
Class II:	0.0	m	Ave. Bolts / Round:	21.8	Bolts / Blast
Class III:	0.0	m	Drilled Length / Round:	65	m
Class IV:	23.2	m	Total Drilling Length:	303,593	m
Class V:	23.2	m	Drill Penetration Rate:	1.5	m / Min
<u>Initial an</u>	d Final Shotcrete Application Details		# of Drills / Booms Used	: 3	No.
et Volume:	12,458	$m^3$	Ave. Drilling Time / Rou	ınd: 14.5	Min
ebound / Waste:	15	%	Bolt Install Rate	2.0	Min / Bolt
inal Layer Volume:	14,326	$m^3$	Ave. Bolt Install Time:	43.6	Min
o. of Applications:	2695 (Required Per Bench)	No.	Drill Set-Up Time:	10.0	Min
ve. Vol. / Application:	5.3	$m^3$	Total Bolt Drill/Install T	ime: 68.1	Min
urface Prep Time:	10.0	Min		Drainhole Details	
otal Surface Prep Time:	26,949	Min	Drainhole Spacing:	3.0	m
pplication Rate:	24.0	m <sup>3</sup> / Hour	Drainhole Length:	1.1	m
otal Application Time:	35,816	Min	Total Area:	177,966.3	$m^2$
qpt. Setup Time:	20.0	Min	Total Drainholes:	19,774.0	# / Per Tunnel
otal Setup Time:	53,898	Min	Total Length:	21,751.4	m
apt. Remove Time:	10.0 (Required Per Application)	Min	0	t concurrent with other acti	
otal Remove Time:	26,949	Min		tion of Tunneling:	
otal Shotcreting Time:	143,611 (For Final Shotcrete Layer)	Min	Pre-Exc. Grouting Time		Hours
quivalent Time / Blast:	30.6	Min / Cycle	Drilling Time =	36,596.4	Hours
-	Secondary Mucking Details	min / cy ele	Charge, Blast, Vent Tim	· · · · · · · · · · · · · · · · · · ·	Hours
teq'd during Tunneling:	No (No if loaded directly into truck	s in tunnel)	Primary Mucking Time	,	Hours
ve. LHD Tram Speed:	0.0	km / hour	Scaling Time =	4,692.2	Hours
•	ick Drain Installation Details	,	Survey / Map Time =	2,345.9	Hours
rain Spacing:	0.0	m	Install Steel Sets Time =		Hours
nstallation Time / Row:	0.0	Hours / Drain	Initial Shotcreting Time	,	Hours
	Funneling Productivity Cycle Details	Hours / Brain	Install Services Time =	2,345.9	Hours
Average	runnenng i roudenvity cycle Detans		Rockbolting (of % Criti		Hours
Equiv. Pre-Exc. Grouting:	5.7	Hours	Non-Productive Time =	$\frac{2,345.9}{2}$	Hours
rilling:	7.8	Hours	110H-1 IOUUCHYC IIMC -	<u> 4,543.7</u>	110015
Charging:	4.8	Hours	Total Time =	121,547.3	Hours
Sharging: Blast & Venting:	1.0	Hours		121,347.3	Months
Jucking:			(Critical Path Tunneling		
лискіng: caling:	2.0 0.3	Hours Hours	Activities Only)	5,064.5	Weeks Days
	0.5			5,064.5 Concurrent Tunneling Ac	•
urveying / Mapping:		Hours	Other C	oncurrent runnening AC	<u> </u>
nitial Shotcreting:	0.8	Hours	Doolsholding / cos st - = :	2 706 C	Цоцес
istall Services:	0.5 (Equiv. Time Per Cycle) 0.5 (Travel in/out, Break)	Hours	Rockbolting (of % Not Crit		Hours
on-Productive Time:	0.5 (Travel in/out, Break)	Hours	Wiremesh Installation =	*	Hours
ld. D. 11 10	V (Vec / N CC 1 T	.)	Final Shotcreting Time:		Hours
nclude Rockbolting:	Yes (Yes / No, as part of Cycle Time		Drilling Drainholes =	29,001.9	Hours
f yes, % of Support Rq'd:	30 ( % Req'd During Cycle for Poo		Secondary Mucking =	0.0	Hours
Rockbolting:	0.3	Hours	Wick Drain Installation		Hours
				Overall Advance Rate:	
Total Cycle Time:	24.3	Hours		3.0	m / Day
				179.5	m³ / Day

Estimated by:	PJP
Checked by:	

Resource Type	Resource Name	Unit Rate	Unit	Quantity	Resource Quantity	Total
Labor						
	Miner - Shift Boss	50.68	\$/hr	121,547.3	2.00	12,320,036.24
	Miner - Operator - Journeyman	47.84	\$/hr	121,547.3	11.00	63,963,061.0
	Miner - Foreman	50.68	\$/hr	121,547.3	3.00	18,480,054.3
	Miner - Laborer - Journeyman	47.40	\$/hr	121,547.3	5.00	28,806,714.50
	Miner - Laborer - Apprentice	45.00	\$/hr	121,547.3	5.00	27,348,146.7
	Tunnel Electrician - Journeyman	47.84	\$/hr	121,547.3	4.00	23,259,294.93
					30.00	174,177,307.87
Plant		120.00	Φ./	15 222 0	0.20	267.002.0
	Cable - Fans & Pumps - High Voltage	120.00	\$/m	15,333.0	0.20	367,992.0
	Cable - Lights / Controls - Low Voltage	10.00	\$/m	15,333.0	0.80	122,664.0
	Compressor	45.61	\$/wk	723.5	1.00	33,000.0
	Conveyor - Heading Muck Loading	1,788.19	\$/wk	723.5	1.00	1,293,750.00
	Drill - Jack-Leg	29.03	\$/wk	723.5	4.00	84,000.00
	Drill Jumbo - Rail Mounted - 2 Boom	362.82	\$/wk	723.5	1.00	262,500.0
	Drill Jumbo - Rail Mounted - 3 Boom	518.32	\$/wk	723.5	1.00	375,000.0
	Excavator - Rail Mounted	114.03	\$/wk	723.5	1.00	82,500.0
	Generator - Back-Up - 500KW	108.85	\$/wk	723.5	1.00	78,750.0
	Generator - Working - 1000KW	8 12 . 72	\$/wk	723.5	1.00	588,000.0
	Grout Plant-Consol-D&B-Pump, Hoses	68.42	\$/wk	723.5	1.00	49,500.0
	Lighting (Including Consumables)	7.50	\$/m	15,333.0	1.00	114,997.5
	Locomotive - Diesel - 16T	5,000.00	\$/wk	723.5	4.00	14,469,918.9
	LHD Loader - D&B Tunnel	347.79	\$/wk	723.5	1.00	251,625.0
	Manlift / Platform - Rail Mounted	152.04	\$/wk	723.5	1.00	110,000.0
	Pipe - 50mm (Water Supply)	7.50	\$/m	15,333.0	1.00	114,997.5
	Pipe - 100mm (Air Supply)	15.00	\$/m	15,333.0	1.00	229,995.0
	Pipe - 150mm (DeWatering)	25.00	\$/m	7,666.5	1.00	191,662.5
	Pipe - 250mm (Dewater)	70.00	\$/m	7,666.5	1.00	536,655.0
	Pipe - Dewatering Clamps (<=200mm)	7.00	\$/m	15,333.0	1.00	107,331.0
	Pumps - Dewatering - Tunnel - 50HP	34.89	\$/wk	361.7	15.00	189,337.5
	Rail - 80 lb/yd - Used	101.54	\$/m	31,066.0	0.60	1,892,636.3
	Rail - California Switch Gear	75,000.00	\$/Nr	1.0	3.00	225,000.0
	Rail Car - Flat	50,000.00	\$/Nr	1.0	3.00	150,000.0
	Rail Car - Man Rider	50,000.00	\$/Nr	1.0	1.00	50,000.0
	Rail Car - Muck Cars	1,900.00	\$/wk	723.5	18.00	24,743,5613
	Rail Car - Muck Car Tipping System	75,000.00	\$/Nr	1.0	1.00	75,000.0
	Shotcrete Machine - Rail Mounted	166.90	\$/wk	723.5	1.00	120,750.0
	Shotcrete Machine - Tire Mounted	270.22	\$/wk	723.5	2.00	391,000.0
	Small Tools	200.00	\$/wk	723.5	1.00	144,699.1
	Tie Plates, Splice Bars, Bolts	150,000.00	LS	1.0	1.00	150,000.0
	Ties - Wooden - Untreated - 7" x 9" x 40"	23.00	\$/m	15,333.0	1.00	352,659.0
	Transformers & Switch gear - High Voltage	76.02	\$/mk	723.5	1.00	55,000.0
	Transformers-Switch gear-Low Voltage	38.01	\$/wk	723.5	1.00	
	Ventilation Duct - Rigid	110.00	\$/wk \$/m		1.00	27,500.0 1 686 630.0
				15,333.0		1,686,630.0
	Ventilation Fans - 75HP	21.46	\$/wk	723.5	7.00	108,675.0
	Welder (Plant)	2.38	\$/wk	723.5	1.00	1,725.0

49,829,011.74

Resource Type	Resource Name	Unit Rate	Unit	Quantity	Resource Quantity	Total
Consumables						
	Bits, Powder and Caps - Blasting	15.00	\$/m3	918,140.5	1.00	13,772,107.66
	Bits - (Drainholes & Rockbolts)	5.00	\$/m	325,344.8	1.00	1,626,724.21
	Drill Jumbo Maintenance	100.00	\$/hr	34,995.8	1.00	3,499,575.81
	Electricity - Tunnel Heading Conveyor	0.22	\$/kwh	150	1,172.95	38,707.50
	Electricity - Fans & Lighting	0.22	\$/kwh	437	60,773.66	5,849,350.37
	Electricity - Jumbo	0.22	\$/kwh	75	34,995.76	577,430.01
	Electricity - Pumps Dewatering	0.22	\$/kwh	559	85,083.12	10,468,668.61
	Lubricants	2,500.00	\$/wk	723.5	1.00	1,808,739.86
	Fuels & Lubricants	5,000.00	\$/wk	723.5	1.00	3,617,479.73
	Other Consumables	1,500.00	\$/wk	723.5	1.00	1,085,243.92
						\$ 42,344,027.69
Materials	Grout - Consolidation	50.00	\$/m3	2,000.0	1.00	100,000.00
	Other Materials	2,000.00	\$/m5	723.5	1.00	1,446,991.89
	Rock Bolts - No.10 - 3.0m - (Non-Galv)	40.00	\$/Nr	101,198	1.00	4,047,912.00
	Shotcrete	180.00	\$/m3	14,326.3	1.00	2,578,732.41
	Steel Sets - W10 x 65	152.75	\$/m	1,533	23.21	5,436,871.99
	Synthetic Wick Drains	5.00	\$/m	0	1.00	5,450,671.55
	WWF mesh	5.50	\$/m2	392,416	1.00	2,158,286.91
	w wi mesn	3.30	<b>⊅</b> /111∠	392,410	1.00	\$ 13,510,508.29
Subcontracts						\$ 13,310,308.28
Subcontracts	Tunnel Muck - Miscl Surface Handling	20.00	\$/m3	1,469,024.82	1.00	29,380,496.35
	ranner widek - wilser surface franting	20.00	ψ/1113	1,407,024.02	1.00	\$ 29,380,496.35

Total Estimated Cost: \$ 309,241,351.93

 Per Meter:
 \$ 20,168.35

 Per m³:
 \$ 336.81



# **Tunnel Estimating Database**

Copyright Hatch Mott MacDonald, 2002

P:IMEMORIAL 213 789 DESIC Cost Estimating & Scheduling Costs 4 - End Sept Final SingleRailD&BRev[NwfM Cost - Rail - June 11 2004.ds]V-316

pyright Hatch Mott MacDonald, 2002

Version VANC-1.5

Project:	Newfoundland Fixed Link Study		Project Number:	213789	
Estimate Description:	Prefeasibility Level		Parent Estimate ID:	V-300	
Tunnel Name:	Railway Tunnel - Up Drive		Project Phase:	Prefeasibility Desi	gn
Construction Activity:	Excavation (Drill & Blast) & Initial Su	pport	Geology Type:	Poor to Fair Sedim	ents & Volcanics
Estimate Definition ID:	V-316		Estimate Date:	June 11 2004	
	Tunnel Characteristics		S	hift Details	
Tunnel Length:	15,333.0	m	Shift Arrangement:	3.0	Shifts / Day
Design Width:	6.4	m		8.0	Hours / Shift
Design Wall Height (Ave.)	6.6	m		7.0	Days / Week
Design Wall to Roof:	2.5		Drill, Charge, Bla	st, Vent & Muckin	g Details
Design Max Height:	9.1	m	Survey Tunnel / Holes / Map:	30.0	Min / Cycle
Ave Tunnel Overbreak:	20.0	cm	<b>Drilling Blast Holes:</b>		
Tunnel Face Area:	59.3 (Includes Overbreak)	$m^2$	Hole Length:	3.9	m / Hole
Crown Perimeter:	9.6 (Includes Overbreak)	m	Perim. Blast Hole Spacing:	0.50	m
Wall & Crown Perimeter:	23 2 (Includes Overbreak)	m	Interior Blast Hole Spacing:	1.25	m
Wall & Crown Area:	355,933 (Includes Overbreak)	$m^2$	No. Perimeter Holes:	46	No.
Neat Tunnel Excav. Vol.:	909,246 (Includes Overbreak)	$m^3$	No. Interior Area Holes:	38.0	No.
Re-Muck / Pull-Out Bays:			No. Blast Initiation Holes:	14	No.
Bay Length:	10.0	m	Number of Drillholes / Blast:	99	Blastholes / Blast
Spacing Bttn Bays:	1000.0	m	Blast Hole / Face Area Ratio:	1.67	Holes / m <sup>2</sup>
Number of Bays:	15	No.	Typical / Check Ratio:	<u>1.56</u>	Holes / m <sup>2</sup>
Total Length of Bays:	150.0	m	Drill Eqpt Set-Up Time:	40	min / Set-up
Neat Excavation Vol.:	8,895	$m^3$	Drill Penetration Rate:	0.30	m / Min
Total Tunnel Volume:	918,141	$m^3$		18	m/hour
Muck Bulking Factor:	1.6	Ratio	# of Drills or Booms:	3.0	No.
Bulked Tunnel Volume:	1,469,025 (Loose Muck Volume)	$m^3$	Charging & Blasting:		
Prim	nary Mucking Production Details		Prime & Load Rate / Hole:	2.50	min / Blasthole
(Activity to remove blast mu-	ck from face to conveyor & muck cars)		Prep & Hook-up Time:	40.0	min / Set-up
Muck Volume / Blast:	313.1	$m^3$	Total No. Blasts / Tunnel:	4692	No.
Mucking Volume / Trip:	5.00	$m^3$	Net Blast Break Length:	3.3	m / Blast
Bucket Fill Factor (%):	90.0	%	Blast & Ventilation Time:	1.0	Hours
Number of Trips:	70	No.	Pre-Excavav	ation Grouting Det	ails
Ave. Dist. to Load:	35.0 (Ave Distance One Way)	m	% Tunnel to be Grouted:	10.0	%
Ave. Tramming Speed:	8.0	km/hr	Tunnel Length to Grout:	1533	m
Load, Dump, Manoever:	1.0 (Time per Trip)	Min	Grout Hole Length:	7.0	m
Face Cleanup / Blast:	15.0	Min	No. of Grouting Applications:	219	No.
Mucking Time:	2.0	Hours	Perim. Grout Holes Spacing:	1.50	m
Mucking Rate:	155.1	m³ / Hour	# Perim. Grout Holes:	15	Holes / Grout Cycle
]	Tunnel Support Class Details		<b>Drilling Penetration Rate:</b>	50	m/hour
Class I - No Support:	0.0 (%)	0 (m)	No. of Drill Booms:	2	No.
Class II - Spot Bolts:	0.0 (%)	0 (m)	Drilling Time per Cycle:	237	Min
Class III - Crown Only:	40.0 (%)	6,133 (m)	Grout Eqpt. Set-Up Time:	1.0	Hours / Grout Cycle
Class IV - Full Pattern:	50.0 (%)	7,667 (m)	No. of Holes Grouted at Once:	2	Hoses
Class V - Steel Sets:	<u>10.0</u> (%)	<u>1,533</u> (m)	Grouting Injection Rate:	10	min / Drillhole
Total	100.0	15,333 (m)	Full Grout Cycle Time:	122.7	Hours
<u>In</u>	itial Shotcrete Support Details		Steel Set	Installation Details	1
Support Arc Length:	23.2	m	Steel Set Spacing:	1.0	m
Thickness:	25.0	mm	Total No. Sets / Tunnel:	1,533	No.
Volume / Round:	2.2	$m^3$	Ave. Installation Time / Set:	3.0	Hours
Time:	0.8 (Includes Scaling & Equip Set-up)	Hours	Total Installation Time:	4,600	Hours

<u> </u>	Viremesh Installation Details			Rockbolt S	upport Class Detai	<u>ls</u>
Install Rate:	100	m² / Hour	(	Bolts Per		(Bolts Per Support
Total Install Time:	3,924.2	Hours		Row)	(Bolts Per m)	<u>Class</u> )
Ave. Install Time:	50.2	Min	Class I:	0	0.0	0
Overlap:	5	%	Class II:	0.0	0.0	0
Net Applied Area:	355,933 (Assume Class V only)	$m^2$	Class III:	6	4.0	24,533
Area with Overlap:	392,416	m <sup>2</sup>	Class IV:	15	10.0	76,665
<u>Fina</u>	l Shotcrete Support Class Details		Class V:	0	0.0	<u>0</u>
Shotcrete Thickness:			Total:			101,198
Classes I and II:	0	mm		<u>F:</u>	ace Scaling	
Class III:	0	mm	Scaling Time:		20.0	min / Blast
Classes IV:	50	mm		Rockbolt	Installation Details	
Class V:	100	mm	Rockbolt Length:		3.0	m
Support Arc Length:			Row Spacing:		1.5	m
Class I:	0.0	m	No. Rockbolts Requi	red:	101,198	No.
Class II:	0.0	m	Ave. Bolts / Round:		21.8	Bolts / Blast
Class III:	0.0	m	Drilled Length / Rou	nd:	65	m
Class IV:	23.2	m	Total Drilling Lengtl	h:	303,593	m
Class V:	23.2	m	Drill Penetration Ra	te:	1.5	m / Min
<u>Initial an</u>	d Final Shotcrete Application Details		# of Drills / Booms U	sed:	3	No.
Net Volume:	12,458	$m^3$	Ave. Drilling Time /	Round:	14.5	Min
Rebound / Waste:	15	%	Bolt Install Rate		2.0	Min / Bolt
Final Layer Volume:	14,326	$m^3$	Ave. Bolt Install Tim	ie:	43.6	Min
No. of Applications:	2695 (Required Per Bench)	No.	Drill Set-Up Time:		10.0	Min
Ave. Vol. / Application:	5.3	$m^3$	Total Bolt Drill/Insta	ıll Time:	68.1	Min
Surface Prep Time:	10.0	Min		Drai	inhole Details	
Total Surface Prep Time:	26,949	Min	Drainhole Spacing:		3.0	m
Application Rate:	24.0	m³ / Hour	Drainhole Length:		1.1	m
Total Application Time:	35,816	Min	Total Area:		177,966.3	$m^2$
Eqpt. Setup Time:	20.0	Min	Total Drainholes:		19,774.0	# / Per Tunnel
Total Setup Time:	53,898	Min	Total Length:		21,7514	m
Eqpt. Remove Time:	10.0 (Required Per Application)	Min	Note: Activity carried	l out concurr	ent with other activ	ities.
Total Remove Time:	26,949	Min	<u>D</u>	uration of T	Tunneling:	
Total Shotcreting Time:	143,611 (For Final Shotcrete Layer)	Min	Pre-Exc. Grouting T	ime =	26,866.9	Hours
Equivalent Time / Blast:	30.6	Min / Cycle	Drilling Time =		36,596.4	Hours
	Secondary Mucking Details		Charge, Blast, Vent	Time =	27,128.5	Hours
Req'd during Tunneling:	No (No if loaded directly into trucks	in tunnel)	Primary Mucking Ti	me =	9,470.2	Hours
Ave. LHD Tram Speed:	0.0	km / hour	Scaling Time =		4,692.2	Hours
<u>w</u>	ick Drain Installation Details		Survey / Map Time =	=	2,345.9	Hours
Drain Spacing:	0.0	m	Install Steel Sets Tim	ne =	4,599.9	Hours
Installation Time / Row:	0.0	Hours / Drain	Initial Shotcreting T	ime =	3,558.4	Hours
Average	Tunneling Productivity Cycle Details		Install Services Time	e =	2,345.9	Hours
			Rockbolting (of % C	ritical) =	1,597.1	Hours
Equiv. Pre-Exc. Grouting:	5.7	Hours	Non-Productive Tim	e =	2,345.9	Hours
Drilling:	7.8	Hours				
Charging:	4.8	Hours	Total Time =		121,547.3	Hours
Blast & Venting:	1.0	Hours			167.0	Months
Mucking:	2.0	Hours	(Critical Path Tunne	eling <	723.5	Weeks
Scaling:	0.3	Hours	Activities Only)		5,064.5	Days
Surveying / Mapping:	0.5	Hours	Oth	er Concurr	ent Tunneling Acti	<u>vities</u>
Initial Shotcreting:	0.8	Hours				
Install Services:	0.5 (Equiv. Time Per Cycle)	Hours	Rockbolting (of % Not	Critical) =	3,726.6	Hours
Non-Productive Time:	0.5 (Travel in/out, Break)	Hours	Wiremesh Installation	n =	3,924.2	Hours
			Final Shotcreting Ti	me =	0.5	Hours
Include Rockbolting:	Yes (Yes / No, as part of Cycle Time	)	Drilling Drainholes =	=	29,001.9	Hours
If yes, % of Support Rq'd:	30 (% Req'd During Cycle for Poor	er Ground)	Secondary Mucking		0.0	Hours
Rockbolting:	0.3	Hours	Wick Drain Installat		0.0	Hours
<u>g</u>					l Advance Rate:	
	24.2	**			3.0	m / Davi
Total Cycle Time:	24.3	Hours		_	3.0	m / Day $\supset$

Estimated by:	PJP
Checked by:	

Resource Type	Resource Name	Unit Rate	Unit	Quantity	Resource Quantity	Total
Labor						
	Miner - Shift Boss	50.68	\$/hr	121,547.3	2.00	12,320,036.2
	Miner - Operator - Journeyman	47.84	\$/hr	121,547.3	11.00	63,963,061.0
	Miner - Foreman	50.68	\$/hr	121,547.3	3.00	18,480,054.3
	Miner - Laborer - Journeyman	47.40	\$/hr	121,547.3	5.00	28,806,714.5
	Miner - Laborer - Apprentice	45.00	\$/hr	121,547.3	5.00	27,348,146.7
	Tunnel Electrician - Journeyman	47.84	\$/hr	121,547.3	4.00	23,259,294.9
					30.00	174,177,307.8
lant	Cable - Fans & Pumps - High Voltage	120.00	\$/m	15,333.0	0.20	367,992.0
	Cable - Lights / Controls - Low Voltage	10.00	\$/m	15,333.0	0.80	122,664.0
	Compressor	45.61	\$/wk	723.5	1.00	33,000.0
	Conveyor - Heading Muck Loading	1,788.19	\$/wk	723.5	1.00	1,293,750.0
	Drill - Jack-Leg	29.03	\$/wk	723.5	4.00	84,000.0
	Drill Jumbo - Rail Mounted - 2 Boom	362.82	\$/wk	723.5	1.00	262,500.0
	Drill Jumbo - Rail Mounted - 2 Boom	518.32	\$/wk	723.5	1.00	375,000.0
	Excavator - Rail Mounted	114.03	\$/wk	723.5	1.00	82,500.0
	Generator - Back-Up - 500KW	108.85	\$/wk	723.5	1.00	78,750.0
	Generator - Working - 1000KW	812.72	\$/wk	723.5	1.00	588,000.0
	Grout Plant-Consol-D&B-Pump, Hoses	68.42	\$/wk	723.5	1.00	49,500.0
	Lighting (Including Consumables)	7.50	\$/m	15,333.0	1.00	114,997
	Locomotive - Diesel - 16T	5,000.00	\$/wk	723.5	4.00	14,469,918.
	LHD Loader - D&B Tunnel	347.79	\$/wk	723.5	1.00	251,625.
	Manlift / Platform - Rail Mounted	152.04	\$/wk	723.5	1.00	110,000
	Pipe - 50mm (Water Supply)	7.50	\$/m	15,333.0	1.00	114,997.
	Pipe - 100mm (Air Supply)	15.00	\$/m	15,333.0	1.00	229,995.
	Rail - 80 lb/yd - Used	101.54	\$/m	31,066.0	0.60	1,892,636.
	Rail - California Switch Gear	75,000.00	\$/Nr	1.0	3.00	225,000
	Rail Car - Flat	50,000.00	\$/Nr	1.0	3.00	150,000.0
	Rail Car - Man Rider	50,000.00	\$/Nr	1.0	1.00	50,000.0
	Rail Car - Muck Cars	1,900.00	\$/Nr	723.5	18.00	24,743,561.3
	Rail Car - Muck Car Tipping System	75,000.00	\$/Nr	1.0	1.00	75,000.0
	Shotcrete Machine - Rail Mounted	166.90	\$/wk	723.5	1.00	120,750.0
	Shotcrete Machine - Tire Mounted	270.22	\$/wk	723.5	2.00	391,000.0
	Small Tools	200.00	\$/wk	723.5	1.00	144,699.1
	Tie Plates, Splice Bars, Bolts	150,000.00	LS	1.0	1.00	150,000.0
	Ties - Wooden - Untreated - 7" x 9" x 40"	23.00	\$/m	15,333.0	1.00	352,659.0
	Transformers & Switch gear - High Voltage	76.02	\$/wk	723.5	1.00	55,000.0
	Transformers-Switchgear-Low Voltage	38.01	\$/wk	723.5	1.00	27,500.0
	Ventilation Duct - Rigid	110.00	\$/m	15,333.0	1.00	1,686,630.0
	Ventilation Fans - 75HP	21.46	\$/wk	723.5	7.00	108,675
	Welder (Plant)	2.38	\$/wk	723.5	1.00	1,725.0
			77 1112		_	48,804,025.7
Consumables						
	Bits, Powder and Caps - Blasting	15.00	\$/m3	918,140.5	1.00	13,772,107.0
	Bits - (Drainholes & Rockbolts)	5.00	\$/m	325,344.8	1.00	1,626,724.2
	Drill Jumbo Maintenance	100.00	\$/hr	34,995.8	1.00	3,499,575
	Electricity - Tunnel Heading Conveyor	0.22	\$/kwh	150	1,172.95	38,707
	Electricity - Fans & Lighting	0.22	\$/kwh	437	60,773.66	5,849,350.
	Electricity - Jumbo	0.22	\$/kwh	75	34,995.76	577,430
	Lubricants	2,500.00	\$/wk	723.5	1.00	1,808,739.
	Fuels & Lubricants	5,000.00	\$/wk	723.5	1.00	3,617,479
	Other Consumables	1,500.00	\$/wk	723.5	1.00	1,085,243.9

Printed: 9:14 AM on 11/25/04 Page 10 of 11

Resource Type	Resource Name	Unit Rate	Unit	Quantity	Resource Quantity	Total
Materials						
	Grout - Consolidation	50.00	\$/m3	2,000.0	1.00	100,000.00
	Other Materials	2,000.00	\$/wk	723.5	1.00	1,446,991.89
	Rock Bolts - No.10 - 3.0m - (Non-Galv)	40.00	\$/Nr	101,198	1.00	4,047,912.00
	Shotcrete	180.00	\$/m3	14,326.3	1.00	2,578,732.41
	Steel Sets - W10 x 65	152.75	\$/m	1,533	23.21	5,436,871.99
	Synthetic Wick Drains	5.00	\$/m	0	1.00	-
	WWF mesh	5.50	\$/m2	392,416	1.00	2,158,286.91
						\$ 13,510,508.29
Subcontracts						
	Tunnel Muck - Miscl Surface Handling	20.00	\$/m3	1,469,024.82	1.00	29,380,496.35
						\$ 29,380,496.35

Total Estimated Cost: \$ 297,747,697.32

 Per Meter:
 \$ 19,418.75

 Per m³:
 \$ 324.29

Estimated by: \_\_\_\_PJP\_\_\_\_ Checked by: \_\_\_\_

Printed: 9:14 AM on 11/25/04 Page 11 of 11

#### Initialisation

Project: Newfoundland Fixed Link Pre-feasibility Study

Section: South Approach

**Option:** Immersed Tube Rail Tunnel

Date: 8-Jun-04

Calculations by: ANW

Surface gradient 0 %

+ sloping same way as track/road

Track/Road Gradient 1.83 %

Ground elevation at portal 100 m

Bottom of slab elevation at portal 86.95 m

Total length= 713.1148 m

Total Cost=\$ 6.1 M


- sloping against track/road

Newfoundland Fixed Link Pre-feasibility Study	Date:	8-Jun-04
South Approach	Calculations by:	ANW
Immersed Tube Rail Tunnel		

#### **UNIT RATES**

#### **Materials**


ltem	unit	Rate
excavation	m3	60
concrete	m3	190
rebar	tonnes	1600
formwork/falsework	m2	140
SP&L<=4.6m deep	m2	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=6.7m>	m2	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0</td></sp&l<=10.6m>	m2	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=13.7m>	m2	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0</td></sp&l<=16.8m>	m2	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0</td></sp&l<=20.0m>	m2	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0</td></sp&l<=25m>	m2	0
backfill + compact	m3	40
surface reinstatement	m2	30



# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	8045.2	60	482709.9
concrete	m3	1859.875	190.0	353376.2
rebar	tonnes	223.2	1600	357095.9
formwork/falsework	m2	1654.07	140	231569.8
SP&L<=4.6m deep	m2	0.0	0	0
4 6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>1768.2</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	1768.2	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	648.9344	30	19468.03


Total 1444220



# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	7198.3	60	431898.3
concrete	m3	1710.976	190.0	325085.5
rebar	tonnes	205.3	1600	328507.4
formwork/falsework	m2	1467.947	140	205512.5
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>1582.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	1582.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	648.9344	30	19468.03


Total 1310472



# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	6209.2	60	372554.2
concrete	m3	1419.868	190.0	269775
rebar	tonnes	170.4	1600	272614.7
formwork/falsework	m2	1281.824	140	179455.3
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1395.9</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1395.9	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	634.4047	30	19032.14


Total 1113431



# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	5154.1	60	309247.4
concrete	m3	1062.716	190.0	201916
rebar	tonnes	127.5	1600	204041.4
formwork/falsework	m2	1095.701	140	153398.1
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1209.8</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1209.8	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	607.6183	30	18228.55


Total 886831.5



# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	4226.1	60	253563.3
concrete	m3	832.6097	190.0	158195.8
rebar	tonnes	99.9	1600	159861.1
formwork/falsework	m2	909.5779	140	127340.9
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>1023.7</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	1023.7	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	588.7921	30	17663.76


Total 716624.9



# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	3395.1	60	203707.6
concrete	m3	699.6423	190.0	132932
rebar	tonnes	84.0	1600	134331.3
formwork/falsework	m2	723.4549	140	101283.7
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>837.6</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	837.6	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	578.14	30	17344.2


Total 589598.9



# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	2598.1	60	155888.9
concrete	m3	600.6249	190.0	114118.7
rebar	tonnes	72.1	1600	115320
formwork/falsework	m2	537.332	140	75226.48
SP&L<=4.6m deep	m2	651.4	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	568.8338	30	17065.01


Total 477619.1



# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	1825.5	60	109527.5
concrete	m3	525.8965	190.0	99920.34
rebar	tonnes	63.1	1600	100972.1
formwork/falsework	m2	351.209	140	49169.26
SP&L<=4.6m deep	m2	465.3	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	559.5277	30	16785.83


Total 376375.1



# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	1077.1	60	64623.52
concrete	m3	475.4572	190.0	90336.86
rebar	tonnes	57.1	1600	91287.78
formwork/falsework	m2	165.0861	140	23112.05
SP&L<=4.6m deep	m2	279.2	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	550.2215	30	16506.65

Total 285866.9



# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	358.3	60	21497.2
concrete	m3	454.6463	190.0	86382.8
rebar	tonnes	54.6	1600	87292.09
formwork/falsework	m2	-21.03689	140	-2945.164
SP&L<=4.6m deep	m2	93.1	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	549.0984	30	16472.95

Total 208699.9

Newfoundland Fixed Li South Approach Immersed Tube Rail Tu		easibility Study Calc	Date: 8-Jun-04 ulations by: ANW	
Summary of Costs				
Summary of Costs		Markup for adjacent	0 %	
\$	5ection 1 2 3 4 5 6 7 8	Cost 1444220 1310472 1113431 886831.5 716624.9 589598.9 477619.1 376375.1		
Su	9 10 ub-total	285866.9 208699.9 6061178		



# **Tunnel Estimating Database**

Copyright Hatch Mott MacDonald, 2002 Version VANC-1.5

**Detailed Cost Estimate Report** 

P:MEMORIAL/213789/DE S/C/Cost Estimating & Scheduling/IT - Rail/[North D&B Approach June 11 2004 xls]V-315

Project:Newfoundland Fixed Link StudyProject Number:213789Estimate Description:Prefeasibility LevelParent Estimate ID:V-300

Tunnel Name: North Drill & Blast Approach Project Phase: Prefeasibility Design

Construction Activity: Excavation (Drill & Blast) & Initial Support Geology Type: Poor to Fair Sediments & Volcanics

Constitution Activity.	Excavation (Dir	ii & Biast) & Illitiai Bu	ррог	Geology Type.	oor to run beaning	into ee v oleanies	
Estimate Definition ID:	V-315			Estimate Date: June 11 2004			
	Tunnel Charac	<u>cteristics</u>		Sh	Shift Details		
Tunnel Length:	6,550.0		m	Shift Arrangement:	3.0	Shifts / Day	
Design Width:	6.4		m		8.0	Hours / Shift	
Design Wall Height (Ave.)	6.6		m		5.0	Days / Week	
Design Wall to Roof:	2.5			Drill, Charge, Blas	st, Vent & Muckin	g Details	
Design Max Height :	9.1		m	Survey Tunnel / Holes / Map:	30.0	Min / Cycle	
Ave Tunnel Overbreak:	20.0		cm	<b>Drilling Blast Holes:</b>			
Tunnel Face Area:	59.3 (Inclu	des Overbreak)	$m^2$	Hole Length:	3.9	m / Hole	
Crown Perimeter:	9.6 (Inclu	des Overbreak)	m	Perim. Blast Hole Spacing:	0.50	m	
Wall & Crown Perimeter:	23.2 (Inclu	des Overbreak)	m	Interior Blast Hole Spacing:	1.25	m	
Wall & Crown Area:	152,048 (Inclu	des Overbreak)	$m^2$	No. Perimeter Holes:	46	No.	
Neat Tunnel Excav. Vol.:	388,414 (Inclu	des Overbreak)	$m^3$	No. Interior Area Holes:	38.0	No.	
Re-Muck / Pull-Out Bays:				No. Blast Initiation Holes:	14	No.	
Bay Length:	10.0		m	Number of Drillholes / Blast:	99	Blastholes / Blast	
Spacing Bttn Bays:	1000.0		m	Blast Hole / Face Area Ratio:	1.67	Holes / m <sup>2</sup>	
Number of Bays:	6		No.	Typical / Check Ratio:	<u>1.56</u>	Holes / m <sup>2</sup>	
Total Length of Bays:	60.0		m	Drill Eqpt Set-Up Time:	20	min / Set-up	
Neat Excavation Vol.:	3,558		$m^3$	Drill Penetration Rate:	1.50	m / Min	
Total Tunnel Volume:	391,972		$m^3$		90	m/hour	
Muck Bulking Factor:	1.6		Ratio	# of Drills or Booms:	3.0	No.	
Bulked Tunnel Volume:	627,156 (Lo	ose Muck Volume)	$m^3$	Charging & Blasting:			
<u>Prin</u>	nary Mucking Pro	duction Details		Prime & Load Rate / Hole:	1.25	min / Blasthole	
(Activity to remove blast mu	ck from face to con	veyor & muck cars)		Prep & Hook-up Time:	20.0	min / Set-up	
Muck Volume / Blast:	313.1		$m^3$	Total No. Blasts / Tunnel:	2003	No.	
Mucking Volume / Trip:	5.00		$m^3$	Net Blast Break Length:	3.3	m / Blast	
Bucket Fill Factor (%):	90.0		%	Blast & Ventilation Time:	0.5	Hours	
Number of Trips:	70		No.	Pre-Excavava	tion Grouting Det	tails	
Ave. Dist. to Load:	<b>35.0</b> (Ave Dist	ance One Way)	m	% Tunnel to be Grouted:	5.0	%	
Ave. Tramming Speed:	8.0	2,7	km/hr	Tunnel Length to Grout:	328	m	
Load, Dump, Manoever:	1.0 (Time per	Trip)	Min	Grout Hole Length:	7.0	m	
Face Cleanup / Blast:	15.0	.,	Min	No. of Grouting Applications:	47	No.	
Mucking Time:	2.0		Hours	Perim. Grout Holes Spacing:	1.50	m	
Mucking Rate:	155.1		m <sup>3</sup> / Hour	# Perim. Grout Holes:	15	Holes / Grout Cycle	
	Funnel Support C	Class Details		Drilling Penetration Rate:	50	m/hour	
Class I - No Support:	0.0 (%)		0 (m)	No. of Drill Booms:	2	No.	
Class II - Spot Bolts:	<b>0.0</b> (%)		0 (m)	Drilling Time per Cycle:	51	Min	
Class III - Crown Only:	40.0 (%)		2,620 (m)	Grout Eqpt. Set-Up Time:	1.0	Hours / Grout Cycle	
Class IV - Full Pattern:	50.0 (%)		3,275 (m)	No. of Holes Grouted at Once:	2	Hoses	
Class V - Steel Sets:	<u>10.0</u> (%)		<u>655</u> (m)	Grouting Injection Rate:	10	min / Drillhole	
Total	100.0		6,550 (m)	Full Grout Cycle Time:	26.4	Hours	
<u>In</u>	itial Shotcrete Su	<u>pport Details</u>		Steel Set 1	nstallation Details	•	
<del>-</del>	itial Shotcrete Su 23.2	pport Details	m	Steel Set Spacing:	1.0	m	
In Support Arc Length: Thickness:		pport Details	m mm	·			

Estimated by: \_\_\_\_PJP\_\_\_\_ Checked by: \_\_\_\_ Time: 0.8 (Includes Scaling & Equip Set-up) Hours Total Installation Time: 1,965 Hours

Estimated by: \_\_\_\_\_PJP\_\_\_\_ Checked by: \_\_\_\_\_

Printed: 3:48 PM on 7/28/04 Page 2 of 5

_	Viremesh Installation Details	2	Rockh	olt Support Class Deta	<u>ils</u>
Install Rate:	100	m <sup>2</sup> / Hour	(Bolts F	<del></del>	(Bolts Per Suppo
Total Install Time:	1,676.3	Hours	Row	(Bolts Per m)	<u>Class</u> )
Ave. Install Time:	50.2	Min	Class I:	0.0	0
Overlap:	5	%	Class II: 0.0	0.0	0
let Applied Area:	152,048 (Assume Class V only	$(m)$ $m^2$	Class III: 6	4.0	10,480
rea with Overlap:	167,633	m <sup>2</sup>	Class IV: 15	10.0	32,750
<u>Fin al</u>	Shotcrete Support Class Deta	<u>ils</u>	Class V:	0.0	<u>0</u>
hotcrete Thickness:			Total:		43,230
Classes I and II:	0	mm		Face Scaling	
Class III:	0	mm	Scaling Time:	20.0	min / Blast
Classes IV:	50	mm	Rock	bolt Installation Detail	<u>s</u>
Class V:	100	mm	Rockbolt Length:	3.0	m
upport Arc Length:			Row Spacing:	1.5	m
Class I:	0.0	m	No. Rockbolts Required:	43,230	No.
Class II:	0.0	m	Ave. Bolts / Round:	21.8	Bolts / Blast
Class III:	0.0	m	Drilled Length / Round:	65	m
Class IV:	23.2	m	Total Drilling Length:	129,690	m
Class V:	23.2	m	Drill Penetration Rate:	1.5	m / M in
	d Final Shotcrete Application l		# of Drills / Booms Used:	3	No.
et Volume:	5,322	m <sup>3</sup>	Ave. Drilling Time / Round		Min
ebound / Waste:	15	%	Bolt Install Rate	2.0	Min / Bolt
inal Layer Volume:	6,120	m <sup>3</sup>	Ave. Bolt Install Time:	43.6	Min
o. of Applications:	1151 (Required Per Bench)		Drill Set-Up Time:	10.0	Min
ve. Vol. / Application:	5.3	m <sup>3</sup>	Total Bolt Drill/Install Tin		Min
urface Prep Time:			Total Bolt Di III/ Ilistali Tili		IVI III
	10.0	Min	Desirbala Carada as	Drainhole Details	
otal Surface Prep Time:	11,512	Min m³ / Hour	Drainhole Spacing:	3.0	m
pplication Rate:	24.0		Drainhole Length:	1.1	m 2
otal Application Time:	15,300	Min	Total Area:	76,024.2	m <sup>2</sup>
qpt. Setup Time:	20.0	Min	Total Drainholes:	8,447.1	# / Per Tunnel
otal Setup Time:	23,024	Min	Total Length:	9,291.9	m
qpt. Remove Time:	10.0 (Required Per Applic		Note: Activity carried out c		vities
otal Remove Time:	11,512	Min		on of Tunneling:	
otal Shotereting Time:	61,348 (For Final Shotcrete		Pre-Exc. Grouting Time =	1,233.4	Hours
quivalent Time / Blast:	30.6	Min / Cycle	Drilling Time =	3,525.4	Hours
	Secondary Mucking Details		Charge, Blast, Vent Time	= 5,790.8	Hours
teq'd during Tunneling:	No (No if loaded directly int	o trucks in tunnel)	Primary Mucking Time =	4,043.0	Hours
ve. LHD Tram Speed:	0.0	km / hour	Scaling Time =	2,003.4	Hours
<u>W</u>	ick Drain Installation Details		Survey / Map Time =	1,001.5	Hours
rain Spacing:	0.0	m	Install Steel Sets Time =	1,965.0	Hours
nstallation Time / Row:	0.0	Hours / Drain	_ Initial Shotcreting Time =	1,519.2	Hours
Average	<b>Funneling Productivity Cycle I</b>	<u>Details</u>	Install Services Time =	1,001.5	Hours
			Rockbolting (of % Critical	1) = 681.8	Hours
Equiv. Pre-Exc. Grouting:	0.6	Hours	Non-Productive Time =	<u>1,001.5</u>	Hours
Prilling:	1.8	Hours			
Charging:	2.4	Hours	Total Time =	23,766.5	Hours
Blast & Venting:	0.5	Hours		45.7	Months
Aucking:	2.0	Hours	(Critical Path Tunneling	198.1	Weeks
caling:	0.3	Hours	Activities Only)	990.3	Days
urveying / Mapping:	0.5	Hours	Other Co.	ncurrent Tunneling Act	
nitial Shotcreting:	0.8	Hours	Silvi Col	The same of the sa	
ntial Shotereting.		Hours	Rockbolting (of % Not Critica	n = 1,590.9	Hours
on-Productive Time:	0.5 (Equiv. Time Per Cycle) 0.5 (Travel in/out, Break)		Wiremesh Installation =		Hours
on-rivuucuve iime:	U.J (1.a. of III. oat, Dieux)	Hours		1,676.3	
adada Badak 10	Var (Vag / Na array a C.C.	la Tima)	Final Shotcreting Time =	0.5	Hours
nclude Rockbolting:	Yes (Yes / No, as part of Cyc		Drilling Drainholes =	2,477.8	Hours
f yes, % of Support Rq'd:	30 (% Req'd During Cycle	*	Secondary Mucking =	0.0	Hours
Rockbolting:	0.3	Hours	Wick Drain Installation =	0.0	Hours
			<u>0</u>	verall Advance Rate:	
otal Cycle Time:	10.2	Hours		6.6	m / Day
				392.2	m <sup>3</sup> / Day

Estimated by: _	PJP
Checked by:	

Resource Type	Resource Name	Unit Rate	Unit	Quantity	Resource Quantity	Total
Labor						
	Miner - Shift Boss	50.68	\$/hr	23,766.5	2.00	2,408,975.6
	Miner - Operator - Journeyman	47.84	\$/hr	23,766.5	11.00	12,506,899.5
	Miner - Foreman	50.68	\$/hr	23,766.5	3.00	3,613,463.4
	Miner - Laborer - Journeyman	47.40	\$/hr	23,766.5	5.00	5,632,667.9
	Miner - Laborer - Apprentice	45.00	\$/hr	23,766.5	5.00	5,347,469.5
	Tunnel Electrician - Journeyman	47.84	\$/hr	23,766.5	4.00	4,547,963.4
					30.00	34,057,439.6
lant	Cable - Fans & Pumps - High Voltage	120.00	\$/m	6,550.0	0.20	157,200.0
	Cable - Fairs & Furifies - Fright Voltage  Cable - Lights / Controls - Low Voltage	10.00	\$/m	6,550.0	0.80	
				*		52,400.0
	Compressor	166.62	\$/wk	198.1	1.00	33,000.0
	Conveyor - Heading Muck Loading	6,532.30	\$/wk	198.1	1.00	1,293,750.0
	Drill - Jack-Leg	106.03	\$/wk	198.1	4.00	84,000.0
	Drill Jumbo - Rail Mounted - 2 Boom	1,325.39	\$/wk	198.1	1.00	262,500.0
	Drill Jumbo - Rail Mounted - 3 Boom	1,893.42	\$/wk	198.1	1.00	375,000.0
	Excavator - Rail Mounted	416.55	\$/wk	198.1	1.00	82,500.
	Generator - Back-Up - 500KW	397.62	\$/wk	198.1	1.00	78,750.
	Generator - Working - 1000KW	2,968.88	\$/wk	198.1	1.00	588,000.
	Grout Plant-Consol-D&B-Pump, Hoses	249.93	\$/wk	198.1	1.00	49,500.
	Lighting (Including Consumables)	7.50	\$/m	6,550.0	1.00	49,125.
	Locomotive - Diesel - 16T	591.50	\$/wk	198.1	4.00	468,600.
	LHD Loader - D&B Tunnel	1,270.48	\$/wk	198.1	1.00	251,625.
	Manlift / Platform - Rail Mounted	555.40	\$/wk	198.1	1.00	110,000
	Pipe - 50mm (Water Supply)	7.50	\$/m	6,550.0	1.00	49,125.
	Pipe - 100mm (Air Supply)	15.00	\$/m	6,550.0	1.00	98,250.
	Pipe - 150mm (DeWatering)	25.00	\$/m	3,275.0	1.00	81,875.
	Pipe - 250mm (Dewater)	70.00	\$/m	3,275.0	1.00	229,250.
	Pipe - Dewatering Clamps (<=200mm)	7.00	\$/m	6,550.0	1.00	45,850.
	Pumps - Dewatering - Tunnel - 50HP	127.46	\$/wk	99.0	15.00	189,337.
	Rail - 80 lb/yd - Used	101.54	\$/m	13,500.0	0.60	822,461.
	Rail - California Switch Gear	75,000.00	\$/Nr	1.0	3.00	225,000.
	Rail Car - Flat	50,000.00	\$/Nr	1.0	3.00	150,000
	Rail Car - Man Rider	50,000.00	\$/Nr	1.0	1.00	50,000
	Rail Car - Muck Cars	25,000.00	\$/Nr	1.0	18.00	450,000
	Rail Car - Muck Car Tipping System	75,000.00	\$/Nr	1.0	1.00	75,000.
	Shotcrete Machine - Rail Mounted	609.68	\$/wk	198.1	1.00	120,750.
	Shotcrete Machine - Tire Mounted	987.10	\$/wk	198.1	2.00	391,000.
	Small Tools	200.00	\$/wk	198.1	1.00	39,610
	Tie Plates, Splice Bars, Bolts	150,000.00	LS	1.0	1.00	150,000.
	Ties - Wooden - Untreated - 7" x 9" x 40"	23.00	\$/m	6,550.0	1.00	150,650.
	Transformers & Switchgear - High Voltage	277.70	\$/wk	198.1	1.00	55,000.
	Transformers-Switch gear-Low Voltage	138.85	\$/wk	198.1	1.00	27,500.
	Ventilation Duct - Rigid	110.00	\$/m	6,550.0	1.00	720,500.
	Ventilation Fans - 75HP	78.39	\$/wk	198.1	7.00	108,675.
	Welder (Plant)	8.71	\$/wk	198.1	1.00	1,725.
	weider (rialit)	0./1	ψ/ WK	170.1	1.00	8 167 509

8,167,509.92

Estimated by: \_\_\_\_PJP\_\_\_\_ Checked by: \_\_\_\_

Resource Type	Resource Name	Unit Rate	Unit	Quantity	Resource Quantity	Total
Consumables						
	Bits, Powder and Caps - Blasting	15.00	\$/m3	391,972.4	1.00	5,879,586.10
	Bits - (Drainholes & Rockbolts)	5.00	\$/m	138,981.9	1.00	694,909.25
	Drill Jumbo Maintenance	100.00	\$/hr	3,372.4	1.00	337,242.39
	Electricity - Tunnel Heading Conveyor	0.22	\$/kwh	150	500.76	16,525.00
	Electricity - Fans & Lighting	0.22	\$/kwh	411	11,883.27	1,074,857.29
	Electricity - Jumbo	0.22	\$/kwh	75	3,372.42	55,644.99
	Electricity - Pumps Dewatering	0.22	\$/kwh	559	16,636.57	2,046,971.87
	Lubricants	2,500.00	\$/wk	198.1	1.00	495,136.07
	Fuels & Lubricants	5,000.00	\$/wk	198.1	1.00	990,272.15
	Other Consumables	1,500.00	\$/wk	198.1	1.00	297,081.64
						\$ 11,888,226.76
Materials	Grout - Consolidation	50.00	\$/m3	2,000.0	1.00	100,000.00
	Other Materials	2,000.00	\$/wk	198.1	1.00	396,108.86
	Rock Bolts - No.10 - 3.0m - (Non-Galv)	40.00	\$/Nr	43,230	1.00	1,729,200.00
	Shotcrete	180.00	\$/m3	6,120.0	1.00	1,101,591.16
	Steel Sets - W10 x 65	152.75	\$/m	655	23.21	2,322,540.37
	Synthetic Wick Drains	5.00	\$/m	0	1.00	, ,
	WWF mesh	5.50	\$/m2	167,633	1.00	921,983.91
			Ψ	,		\$ 5,549,440.39
Subcontracts	Tunnel Muck - Miscl Surface Handling	20.00	\$/m3	627,155.85	1.00	12,543,117.02
	Tunner Muck - Misci Surface Handling	20.00	<b>D</b> /1113	027,133.83	1.00	\$ 12,543,117.02

Total Estimated Cost: \$ 72,205,733.74

 Per Meter:
 \$ 11,023.78

 Per m³:
 \$ 184.21

Estimated by: \_\_\_\_PJP\_\_\_\_ Checked by: \_\_\_\_

#### Newfoundland Fixed Link Pre-feasibility Study Immersed Tube Rail Option North D&B Approach Final Liner Tunnel Final Liner Cost Estimate

Tunnel length= 6535 m Liner cross section area= 13.5 m2

#### Shift pattern

Shifts	Hours	Days
3	8	5

Advance rate= 10 m/day

Rebar ratio= 0.12 t/m3 of concrete

Concrete supply=\$ 135 /m3

Rebar supply=\$ 900 /t

Initial form set-up time= 4 weeks

#### **Durations**

Number of days= 674 days
Number of hours= 16164 hours
Number of weeks= 135 weeks

#### Labour

Crew size 20
Average labour rate \$ 47 /hour

Total labour cost=\$ 15,194,160

#### **Equipment**

Form \$ 1000000
Weekly cost of other equipment \$ 15000 (see TED 2370)

Total equipment cost=\$ 3,020,500

#### Materials Cost Summary

Concrete= 88222.5 m3 Labour 15,194,160 Rebar= 10586.7 Equipment 3,020,500

Materials 21,438,068
Concrete cost=\$ 11,910,038

Total 39,652,728


Total material cost=\$ 21,438,068

Rebar cost=\$ 9,528,030

Newfoundland Fixed Link Pre-feasibility Study
Cost Estimating Immersed Tube Rail Option
North Drill & Blast Approach Finishes

**Tunnel Structural Finishes** 

Page 1 of 2
Date: June 07, 2004
Calculation by: A.White



# Newfoundland Fixed Link Pre-feasibility Study

Cost Estimating Immersed Tube Rail Option

North Drill & Blast Approach Finishes

**Tunnel Structural Finishes** 

Page 2 of 2

**Date:** June 07, 2004 **Calculation by:** A.White

# **Quantity Take-off**

Concrete					Concrete	Rebar
Element	Nr.	L(m)	b(m)	d(m)	Qty(m3)	Qty(m3)
1	1	6550	0.3	6.9	13559	1627.0
2	1	6550	1.5	0.3	2947.5	353.7
3	1	6550	1.5	0.3	2947.5	353.7
4	1	6550	5.5	1.0	36025	4323.0
					55479 m3	6657 t

#### Formwork/falsework

Element	Nr.	L(m)	d(m)	Faces	Area(m2)	
1	1	6550	6.9	2	90390	
2	1	6550	1.5	1	9825	
3	1	6550	1.5	1	9825	
4	1	6550	0	0	0	
					110040	m2

#### **Rates**


Concrete	m3	190
Formwork	m2	140
Reinforcement	t	1600

#### Costs

Concrete	m3	55479 m3	at	190	=	10,540,915
Formwork	m2	110040 m2	at	140	=	15,405,600
Reinforcement	t	6657 t	at	1600	=	10,651,872
				\$		36,598,387

Newfoundland Fixed Link Pre-feasibility Study
Cost Estimating Immersed Tube Rail Option
Single Lane Bored Railway Tunnel
Tunnel Structural Finishes

Page 1 of 2
Date: June 07, 2004
Calculation by: A.White



# Newfoundland Fixed Link Pre-feasibility Study Cost Estimating Single Lane Bored Pailway Tuppel

Single Lane Bored Railway Tunnel Tunnel Structural Finishes

Page 2 of 2 Date: June 07, 2004

Calculation by: A.White

# **Quantity Take-off**

Concrete					Concrete	Rebar
Element	Nr.	L(m)	b(m)	d(m)	Qty(m3)	Qty(m3)
1	1	6535	0.3	5.9	11567	1388.0
2	1	6535	1.2	0.3	2352.6	282.3
3	1	6535	1.2	0.3	2352.6	282.3
					16272 m3	1670 t

## Formwork/falsework

Element	Nr.	L(m)	d(m)	Faces	Area(m2)	)
1	1	6535	5.9	2	77113	
2	1	6535	1.2	1	7842	
3	1	6535	1.2	1	7842	
					92797	_ m2

#### Rates

Concrete	m3	190
Formwork	m2	140
Reinforcement	t	1600

#### Costs

Concrete	m3	16272 m3	at	190	=	3,091,709
Formwork	m2	92797 m2	at	140	=	12,991,580
Reinforcement	t	1670 t	at	1600	=	2,672,554
				\$		18,755,842

#### Initialisation

Project: Newfoundland Fixed Link Pre-feasibility Study

Section: North Approach
Option: Bored Rail Tunnel

Date: 8-Jun-04

Calculations by: ANW

Surface gradient -2.2 %

+ sloping same way as track/road - sloping against track/road

Track/Road Gradient 1.64 %

Ground elevation at portal 100 m

Bottom of slab elevation at portal 86.95 m

Total length= 339.8438 m


Total Cost=\$ 3.5 M

Newfoundland Fixed Link Pre-feasibility Study	Date:	8-Jun-04
North Approach	Calculations by:	ANW
Bored Rail Tunnel		

## **UNIT RATES**

#### **Materials**


Item	unit	Rate
excavation	m3	60
concrete	m3	190
rebar	tonnes	1600
formwork/falsework	m2	140
SP&L<=4.6m deep	m2	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=6.7m>	m2	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0</td></sp&l<=10.6m>	m2	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0</td></sp&l<=13.7m>	m2	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0</td></sp&l<=16.8m>	m2	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0</td></sp&l<=20.0m>	m2	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0</td></sp&l<=25m>	m2	0
backfill + compact	m3	40
surface reinstatement	m2	30



# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	3834.0	60	230041.4
concrete	m3	886.3465	190.0	168405.8
rebar	tonnes	106.4	1600	170178.5
formwork/falsework	m2	788.2676	140	110357.5
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>842.6</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	842.6	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	309.2578	30	9277.734

Total 688261




Newfoundland Fixed Link Pre-feasibility Study North Approach Bored Rail Tunnel Date: 8-Jun-04

Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	3430.4	60	205826.5
concrete	m3	815.3871	190.0	154923.6
rebar	tonnes	97.8	1600	156554.3
formwork/falsework	m2	699.5684	140	97939.57
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>753.9</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	753.9	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	309.2578	30	9277.734

Total 624521.7




Newfoundland Fixed Link Pre-feasibility Study North Approach Bored Rail Tunnel

Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	2959.1	60	177545.3
concrete	m3	676.656	190.0	128564.6
rebar	tonnes	81.2	1600	129917.9
formwork/falsework	m2	610.8691	140	85521.68
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>665.2</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	665.2	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	302.3335	30	9070.005


Total 530619.6



# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	2456.3	60	147375.7
concrete	m3	506.4505	190.0	96225.6
rebar	tonnes	60.8	1600	97238.5
formwork/falsework	m2	522.1699	140	73103.79
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>576.5</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	576.5	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	289.5681	30	8687.043


Total 422630.6



# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	2014.0	60	120838.8
concrete	m3	396.7905	190.0	75390.2
rebar	tonnes	47.6	1600	76183.79
formwork/falsework	m2	433.4707	140	60685.9
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>487.8</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	487.8	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	280.5962	30	8417.887

Total 341516.5




Newfoundland Fixed Link Pre-feasibility Study North Approach Bored Rail Tunnel Date: 8-Jun-04

Calculations by: ANW Page 2 of 2

# Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	1618.0	60	97079.41
concrete	m3	333.4233	190.0	63350.42
rebar	tonnes	40.0	1600	64017.27
formwork/falsework	m2	344.7715	140	48268.01
SP&L<=4.6m deep	m2	0.0	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>399.1</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	399.1	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	275.5198	30	8265.595

Total 280980.7




Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	1238.2	60	74290.81
concrete	m3	286.2353	190.0	54384.7
rebar	tonnes	34.3	1600	54957.18
formwork/falsework	m2	256.0723	140	35850.12
SP&L<=4.6m deep	m2	310.4	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	271.0849	30	8132.546

Total 227615.4




Calculations by: ANW Page 2 of 2

## Calculated costs

ltem	Unit	Quantity	Rate	Cost
excavation	m3	869.9	60	52196.72
concrete	m3	250.6226	190.0	47618.28
rebar	tonnes	30.1	1600	48119.53
formwork/falsework	m2	167.373	140	23432.23
SP&L<=4.6m deep	m2	221.7	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	266.6499	30	7999.497

Total 179366.3




Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	513.3	60	30797.14
concrete	m3	226.5851	190.0	43051.16
rebar	tonnes	27.2	1600	43504.33
formwork/falsework	m2	78.67383	140	11014.34
SP&L<=4.6m deep	m2	133.0	0	0
4 6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	262.2149	30	7866.448

Total 136233.4



Calculations by: ANW Page 2 of 2

## Calculated costs

Item	Unit	Quantity	Rate	Cost
excavation	m3	170.7	60	10244.76
concrete	m3	216.6674	190.0	41166.8
rebar	tonnes	26.0	1600	41600.14
formwork/falsework	m2	-10.02539	140	-1403.555
SP&L<=4.6m deep	m2	44.3	0	0
4.6 <sp&l<=6.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=6.7m>	m2	0.0	0	0
6.7 <sp&l<=10.6m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=10.6m>	m2	0.0	0	0
10.6 <sp&l<=13.7m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=13.7m>	m2	0.0	0	0
13.7 <sp&l<=16.8m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=16.8m>	m2	0.0	0	0
16.8 <sp&l<=20.0m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=20.0m>	m2	0.0	0	0
20 <sp&l<=25m deep<="" td=""><td>m2</td><td>0.0</td><td>0</td><td>0</td></sp&l<=25m>	m2	0.0	0	0
backfill	m3	0	40	0
surface reinstatement	m2	261.6797	30	7850.391

Total 99458.54

Section   Cost   0 %	North Approach	d Link Pre-feasibility Study Date: 8-Jun-04 Calculations by: ANW					
Section Cost 1 688261 2 624521.7 3 530619.6 4 422630.6 5 341516.5 6 280980.7 7 227615.4 8 179366.3 9 136233.4 10 99458.54							
1 688261 2 624521.7 3 530619.6 4 422630.6 5 341516.5 6 280980.7 7 227615.4 8 179366.3 9 136233.4 10 99458.54	Summary of Costs		Markup for adjacent	0 %			
1 688261 2 624521.7 3 530619.6 4 422630.6 5 341516.5 6 280980.7 7 227615.4 8 179366.3 9 136233.4 10 99458.54		Section	Cost				
3 530619.6 4 422630.6 5 341516.5 6 280980.7 7 227615.4 8 179366.3 9 136233.4 10 99458.54			688261				
4 422630.6 5 341516.5 6 280980.7 7 227615.4 8 179366.3 9 136233.4 10 99458.54							
5 341516.5 6 280980.7 7 227615.4 8 179366.3 9 136233.4 10 99458.54							
7 227615.4 8 179366.3 9 136233.4 10 99458.54		5	341516.5				
8 179366.3 9 136233.4 10 99458.54							
9 136233.4 10 <u>99458.54</u>							
10 _ 99458.54 _							
Sub-total <u>3531204</u>		10	99458.54				
		Sub-total	3531204				



# **Tunnel Estimating Database**

Copyright Hatch Mott MacDonald, 2002 Version VANC-1.5

**Detailed Cost Estimate Report** 

P:MEMORIALI213789|DESC|CostEstimating & Scheduling|IT - Rail|South D&B Approach June 11 2004 xls|V-315

Project:Newfoundland Fixed Link StudyProject Number:213789Estimate Description:Prefeasibility LevelParent Estimate ID:V-300

Tunnel Name: <u>IT Rail - South D&B Approach</u> **Project Phase:** Prefeasibility Design

Construction Activity: Excavation (Drill & Blast) & Initial Support Geology Type: Poor to Fair Sediments & Volcanics

Constitution Activity.	LACAVALI	on (Bini & Biast) & initial 5a	рроге		Geology Type.	tool to I all bealth	icitis & voicumes
Estimate Definition ID:	V-315			Estimate Date: June 11 2004			
	Tunnel Characteristics				Sh	ift Details	
Tunnel Length:	2,100.0		m		Shift Arrangement:	3.0	Shifts / Day
Design Width:	6.4		m			8.0	Hours / Shift
Design Wall Height (Ave.)	6.6		m			5.0	Days / Week
Design Wall to Roof:	2.5				Drill, Charge, Blas	st, Vent & Mucki	ng Details
Design Max Height :	9.1		m		Survey Tunnel / Holes / Map:	30.0	Min / Cycle
Ave Tunnel Overbreak:	20.0		cm		<b>Drilling Blast Holes:</b>		
Tunnel Face Area:	59.3	(Includes Overbreak)	$m^2$		Hole Length:	3.9	m / Hole
Crown Perimeter:	9.6	(Includes Overbreak)	m		Perim. Blast Hole Spacing:	0.50	m
Wall & Crown Perimeter:	23.2	(Includes Overbreak)	m		Interior Blast Hole Spacing:	1.25	m
Wall & Crown Area:	48,748	(Includes Overbreak)	$m^2$		No. Perimeter Holes:	46	No.
Neat Tunnel Excav. Vol.:	124,530	(Includes Overbreak)	$m^3$		No. Interior Area Holes:	38.0	No.
Re-Muck / Pull-Out Bays:					No. Blast Initiation Holes:	14	No.
Bay Length:	10.0		m		Number of Drillholes / Blast:	99	Blastholes / Blast
Spacing Bttn Bays:	1000.0		m		Blast Hole / Face Area Ratio:	1.67	Holes / m <sup>2</sup>
Number of Bays:	2		No.		Typical / Check Ratio:	<u>1.56</u>	Holes / m <sup>2</sup>
Total Length of Bays:	20.0		m		Drill Eqpt Set-Up Time:	20	min / Set-up
Neat Excavation Vol.:	1,186		$m^3$		Drill Penetration Rate:	1.50	m / M in
Гotal Tunnel Volume:	125,716		$m^3$			90	m/hour
Muck Bulking Factor:	1.6		Ratio		# of Drills or Booms:	3.0	No.
Bulked Tunnel Volume:	201,145	(Loose Muck Volume)	$m^3$		Charging & Blasting:		
<u>Prin</u>	ary Muck	ing Production Details			Prime & Load Rate / Hole:	1.25	min / Blasthole
Activity to remove blast muc	ck from fac	e to conveyor & muck cars)			Prep & Hook-up Time:	20.0	min / Set-up
Muck Volume / Blast:	3 13 . 1		$m^3$		Total No. Blasts / Tunnel:	642	No.
Mucking Volume / Trip:	5.00		$m^3$		Net Blast Break Length:	3.3	m / Blast
Bucket Fill Factor (%):	90.0		%		Blast & Ventilation Time:	0.5	Hours
Number of Trips:	70		No.		<u>Pre-Excavava</u>	tion Grouting De	<u>etails</u>
Ave. Dist. to Load:	<b>35.0</b> (A	(Ave Distance One Way)	m		% Tunnel to be Grouted:	5.0	%
Ave. Tramming Speed:	8.0		km/hr		Tunnel Length to Grout:	105	m
Load, Dump, Manoever:	<b>1.0</b> (T	Time per Trip)	Min		Grout Hole Length:	7.0	m
Face Cleanup / Blast:	15.0		Min		No. of Grouting Applications:	15	No.
Mucking Time:	2.0		Hours		Perim. Grout Holes Spacing:	1.50	m
Mucking Rate:	155.1		$m^3/H$	our	# Perim. Grout Holes:	15	Holes / Grout Cycle
<u>,                                     </u>	Funnel Su	pport Class Details			Drilling Penetration Rate:	50	m/hour
Class I - No Support:	0.0	%)	0	(m)	No. of Drill Booms:	2	No.
Class II - Spot Bolts:	0.0	<b>%</b> )	0	(m)	Drilling Time per Cycle:	16	Min
Class III - Crown Only:	40.0	(%)	840	(m)	Grout Eqpt. Set-Up Time:	1.0	Hours / Grout Cycle
Class IV - Full Pattern:	50.0	%)	1,050	(m)	No. of Holes Grouted at Once:	2	Hoses
Class V - Steel Sets:	<u>10.0</u> (	<b>%</b> )	<u>210</u>	(m)	Grouting Injection Rate:	10	min / Drillhole
Total	100.0		2,100	(m)	Full Grout Cycle Time:	26.4	Hours
<u>In</u>	itial Shotc	rete Support Details			Steel Set I	nstallation Detail	<u>ls</u>
Support Arc Length:	23.2		m		Steel Set Spacing:	1.0	m
Thickness:	25.0		mm		Total No. Sets / Tunnel:	210	No.

Estimated by: \_\_\_\_PJP\_\_\_\_ Checked by: \_\_\_\_ Time: 0.8 (Includes Scaling & Equip Set-up) Hours

Total Installation Time:

630

Hours

Estimated by: \_\_\_\_PJP\_\_\_\_ Checked by: \_\_\_\_

Printed: 3:54 PM on 7/28/04 Page 2 of 5

_		sh Installation Details	2		Rockbolt S	upport Class Detai	<u>ls</u>
Install Rate:	100		m <sup>2</sup> / Hour	<u>(</u>	Bolts Per		(Bolts Per Suppo
Total Install Time:	537.5		Hours		Row)	(Bolts Per m)	<u>Class</u> )
ve. Install Time:	50.2		Min	Class I:	0	0.0	0
verlap:	5		%	Class II:	0.0	0.0	0
et Applied Area:	48,74	8 (Assume Class V only)	$m^2$	Class III:	6	4.0	3,360
rea with Overlap:	53,74	5	m <sup>2</sup>	_Class IV:	15	10.0	10,500
<u>Final</u>	Shote	rete Support Class Details		Class V:	0	0.0	<u>0</u>
hotcrete Thickness:				Total:			13,860
Classes I and II:	0		mm		<u>F</u>	ace Scaling	
Class III:	0		mm	Scaling Time:		20.0	min / Blast
Classes IV:	50		mm		Rockbolt	Installation Details	<u>3</u>
Class V:	100		mm	Rockbolt Length:		3.0	m
upport Arc Length:				Row Spacing:		1.5	m
Class I:	0.0		m	No. Rockbolts Requ	ired:	13,860	No.
Class II:	0.0		m	Ave. Bolts / Round:		21.8	Bolts / Blast
Class III:	0.0		m	Drilled Length / Ros	und:	65	m
Class IV:	23.2		m	Total Drilling Lengt	th:	41,580	m
Class V:	23.2		m	Drill Penetration Ra	ıte:	1.5	m / Min
	d Final	Shotcrete Application Details		# of Drills / Booms U	Used:	3	No.
et Volume:	1,706		$m^3$	Ave. Drilling Time /		14.5	Min
ebound / Waste:	15		%	Bolt Install Rate	Mounu.	2.0	Min / Bolt
inal Layer Volume:	1,962		m <sup>3</sup>	Ave. Bolt Install Tir	ne:	43.6	Min Min
o. of Applications:	369	(Required Per Bench)	No.	Drill Set-Up Time:	iic.	10.0	Min
ve. Vol. / Application:	5.3	(	m <sup>3</sup>	Total Bolt Drill/Inst	all Time	68.1	Min
urface Prep Time:	10.0		Min	Total Bolt Billining		inhole Details	IVIIII
otal Surface Prep Time:	3,691		Min	Drainhole Spacing:	<u>171 a</u>	3.0	m
pplication Rate:	24.0		m <sup>3</sup> / Hour	Drainhole Length:		1.1	m
otal Application Time:	4,905		Min	Total Area:		24,374.2	m <sup>2</sup>
	20.0		Min	Total Drainholes:		*	# / Per Tunnel
qpt. Setup Time:						2,708.2	
otal Setup Time:	7,382		Min	Total Length:	1 .	2,979 1	m ···
qpt. Remove Time:	10.0	(Required Per Application)	Min	Note: Activity carrie			ities.
otal Remove Time:	3,691		Min			Tunneling:	
otal Shotcreting Time:	19,66	9 (For Final Shotcrete Layer)	Min	Pre-Exc. Grouting T	l'ime =	395.4	Hours
quivalent Time / Blast:	30.6		Min / Cycle	Drilling Time =		1,130.7	Hours
		ary Mucking Details		Charge, Blast, Vent		1,857.3	Hours
teq'd during Tunneling:	No	(No if loaded directly into trucks is	· · · · · · · · · · · · · · · · · · ·	Primary Mucking T	ime =	1,296.7	Hours
ve. LHD Tram Speed:	0.0		km / hour	Scaling Time =		642.8	Hours
<del></del>		<u>ain Installation Details</u>		Survey / Map Time		321.2	Hours
rain Spacing:	0.0		m	Install Steel Sets Tir		630.0	Hours
nstallation Time / Row:	0.0		Hours / Drain	_ Initial Shotcreting T	Γime =	487.2	Hours
<u>Average</u>	Tunnel	ing Productivity Cycle Details		Install Services Tim	e =	321.2	Hours
				Rockbolting (of % C	Critical) =	218.7	Hours
Equiv. Pre-Exc. Grouting:	0.6		Hours	Non-Productive Tin	ne =	<u>321.2</u>	Hours
rilling:	1.8		Hours				
Charging:	2.4		Hours	Total Time =		7,622.4	Hours
Blast & Venting:	0.5		Hours			14.7	Months
Aucking:	2.0		Hours	(Critical Path Tunn	eling <	63.5	Weeks
caling:	0.3		Hours	Activities Only)		317.6	Days
urveying / Mapping:	0.5		Hours	Oth	ier Concuri	ent Tunneling Act	ivities
nitial Shotereting:	0.8		Hours				
ıstall Services:	0.5	(Equiv. Time Per Cycle)	Hours	Rockbolting (of % No	ot Critical) =	510.3	Hours
on-Productive Time:	0.5	(Travel in/out, Break)	Hours	Wiremesh Installati		537.5	Hours
			-	Final Shotcreting T		0.5	Hours
nclude Rockbolting:	Ves	(Yes / No, as part of Cycle Time)		Drilling Drainholes		794.4	Hours
f yes, % of Support Rq'd:	30	(% Req'd During Cycle for Poorer	r Ground)	Secondary Mucking		0.0	Hours
Rockbolting:	0.3	Concede Daring Choic for 1 00101	Hours	Wick Drain Installa		0.0	Hours
Rockboining.	U.J		110013	TO INCLUDE A HISTORIA			110413
otal Cyala Timas	10.2		Uoura		Overal	1 Advance Rate:	m / Day
Cotal Cycle Time:	10.2		Hours		<u>_</u>	0.0	m / Day

Estimated by	y:PJP	
Checked b	y:	

Resource Type	Resource Name	Unit Rate	Unit	Quantity	Resource Quantity	Total
Labor						
	Miner - Shift Boss	50.68	\$/hr	7,622.4	1.00	386,303.5
	Miner - Operator - Journeyman	47.84	\$/hr	7,622.4	7.00	2,552,591.2
	Miner - Foreman	50.68	\$/hr	7,622.4	3.00	1,158,910.5
	Miner - Laborer - Journeyman	47.40	\$/hr	7,622.4	3.00	1,083,906.1
	Miner - Laborer - Apprentice	45.00	\$/hr	7,622.4	3.00	1,029,024.7
	Tunnel Electrician - Journeyman	47.84	\$/hr	7,622.4	3.00	1,093,967.6
					20.00	7,304,703.8
Plant	Cable - Fans & Pumps - High Voltage	120.00	\$/m	2,100.0	0.20	50,400.0
	Cable - Lights / Controls - Low Voltage	10.00	\$/m	2,100.0	0.80	16,800.0
	Compressor	519.52	\$/wk	63.5	1.00	33,000.0
	Conveyor - Heading Muck Loading	20,367.59	\$/wk	63.5	1.00	
						1,293,750.0
	Drill - Jack-Leg	330.60	\$/wk	63.5	4.00	84,000.0
	Drill Jumbo - Rail Mounted - 2 Boom	4,132.55	\$/wk	63.5	1.00	262,500.0
	Drill Jumbo - Rail Mounted - 3 Boom	5,903.65	\$/wk	63.5	1.00	375,000.0
	Excavator - Rail Mounted	1,298.80	\$/wk	63.5	1.00	82,500.0
	Generator - Back-Up - 500KW	1,239.77	\$/wk	63.5	1.00	78,750.0
	Generator - Working - 1000KW	9,256.92	\$/wk	63.5	1.00	588,000.0
	Grout Plant-Consol-D&B-Pump, Hoses	779.28	\$/wk	63.5	1.00	49,500.0
	Lighting (Including Consumables)	7.50	\$/m	2,100.0	1.00	15,750.0
	Locomotive - Diesel - 16T	1,844.30	\$/wk	63.5	4.00	468,600.0
	LHD Loader - D&B Tunnel	3,961.35	\$/wk	63.5	1.00	251,625.0
	Manlift / Platform - Rail Mounted	1,731.74	\$/wk	63.5	1.00	110,000.0
	Pipe - 50mm (Water Supply)	7.50	\$/m	2,100.0	1.00	15,750.0
	Pipe - 100mm (Air Supply)	15.00	\$/m	2,100.0	1.00	31,500.0
	Pipe - 150mm (DeWatering)	25.00	\$/m	1,050.0	1.00	26,250.0
	Pipe - 250mm (Dewater)	70.00	\$/m	1,050.0	1.00	73,500.0
	Pipe - Dewatering Clamps (<=200mm)	7.00	\$/m	2,100.0	1.00	14,700.0
	Pumps - Dewatering - Tunnel - 50HP	397.43	\$/wk	31.8	15.00	189,337.5
	Rail - 80 lb/yd - Used	101.54	\$/m	4,600.0	0.60	280,246.1
	Rail - California Switch Gear	75,000.00	\$/Nr	1.0	3.00	225,000.0
	Rail Car - Flat	50,000.00	\$/Nr	1.0	3.00	150,000.0
	Rail Car - Man Rider	50,000.00	\$/Nr	1.0	1.00	50,000.0
	Rail Car - Muck Cars	25,000.00	\$/Nr	1.0	18.00	450,000.0
	Rail Car - Muck Car Tipping System	75,000.00	\$/Nr	1.0	1.00	75,000.0
	Shotcrete Machine - Rail Mounted	1,900.97	\$/wk	63.5	1.00	120,750.0
	Shotcrete Machine - Tire Mounted	3,077.77	\$/wk	63.5	2.00	391,000.0
	Small Tools	· · · · · · · · · · · · · · · · · · ·				
		200.00	\$/wk	63.5	1.00	12,704.0
	Tie Plates, Splice Bars, Bolts	150,000.00	LS	1.0	1.00	150,000.0
	Ties - Wooden - Untreated - 7" x 9" x 40"	23.00	\$/m	2,100.0	1.00	48,300.0
	Transformers & Switch gear - High Voltage	865.87	\$/wk	63.5	1.00	55,000.
	Transformers-Switch gear-Low Voltage	432.93	\$/wk	63.5	1.00	27,500.
	Ventilation Duct - Rigid	110.00	\$/m	2,100.0	1.00	231,000.
	Ventilation Fans - 75HP	244.41	\$/wk	63.5	7.00	108,675.0
	Welder (Plant)		\$/wk	63.5		

6,488,112.66

Estimated by: \_\_\_\_PJP\_\_\_\_ Checked by: \_\_\_\_

Resource Type	Resource Name	Unit Rate	Unit	Quantity	Resource Quantity	Total
Consumables						
	Bits, Powder and Caps - Blasting	15.00	\$/m3	125,715.8	1.00	1,885,737.15
	Bits - (Drainholes & Rockbolts)	5.00	\$/m	44,559.1	1.00	222,795.33
	Drill Jumbo Maintenance	100.00	\$/hr	1,081.6	1.00	108,156.51
	Electricity - Tunnel Heading Conveyor	0.22	\$/kwh	150	160.61	5,300.00
	Electricity - Fans & Lighting	0.22	\$/kwh	398	3,811.20	333,534.90
	Electricity - Jumbo	0.22	\$/kwh	75	1,081.57	17,845.82
	Electricity - Pumps Dewatering	0.22	\$/kwh	559	5,335.68	656,505.14
	Lubricants	2,500.00	\$/wk	63.5	1.00	158,800.12
	Fuels & Lubricants	5,000.00	\$/wk	63.5	1.00	317,600.24
	Other Consumables	1,500.00	\$/wk	63.5	1.00	95,280.07
						\$ 3,801,555.29
Materials	Grout - Consolidation	50.00	\$/m3	2,000.0	1.00	100,000.00
	Other Materials	2,000.00	\$/wk	63.5	1.00	127,040.10
	Rock Bolts - No.10 - 3.0m - (Non-Galv)	40.00	\$/Nr	13,860	1.00	554,400.00
	Shotcrete	180.00	\$/m3	1,962.1	1.00	353,181.90
	Steel Sets - W10 x 65	152.75	\$/m	210	23.21	744,631.26
	Synthetic Wick Drains	5.00	\$/m	0	1.00	, -
	WWF mesh	5.50	\$/m2	53,745	1.00	295,597.89
						\$ 1,779,253.26
Subcontracts	Tunnel Muck - Miscl Surface Handling	20.00	\$/m3	201,145.30	1.00	4,022,905.91
	runner widek - wilser Surface Handling	20.00	Ф/1113	201,143.30		\$ 4,022,905.91

Total Estimated Cost: \$ 23,396,530.99

 Per Meter:
 \$ 11,141.21

 Per m³:
 \$ 186.11

Estimated by: \_\_\_\_PJP\_\_\_\_ Checked by: \_\_\_\_

# Newfoundland Fixed Link Pre-feasibility Study IT Rail Tunnel - South D&B Approach Final Liner Tunnel Final Liner Cost Estimate

Tunnel length= 2100 m Liner cross section area= 13.5 m2

## Shift pattern

Shifts	Hours	Days
3	8	5

Advance rate= 10 m/day

Rebar ratio= 0.12 t/m3 of concrete

Concrete supply=\$ 135 /m3

Rebar supply=\$ 900

Initial form set-up time= 4 weeks

#### **Durations**

Number of days= 230 days
Number of hours= 5520 hours
Number of weeks= 46 weeks

#### Labour

Crew size 20
Average labour rate \$ 47 /hour

Total labour cost=\$ 5,188,800

#### **Equipment**

Form \$ 1000000
Weekly cost of other equipment \$ 15000 (see TED 2370)

Total equipment cost=\$ 1,690,000

#### Materials Cost Summary

3,061,800

Concrete= 28350 m3 Labour 5,188,800 Rebar= 3402 Equipment 1,690,000

Materials 6,889,050
Concrete cost=\$ 3,827,250


Total 13,767,850

Total material cost=\$ 6,889,050

Rebar cost=\$

Newfoundland Fixed Link Pre-feasibility Study Cost Estimating IT Rail Tunnel - South D&B Approach Finishes Tunnel Structural Finishes Page 1 of 2

**Date:** June 07, 2004 **Calculation by:** A.White



## Newfoundland Fixed Link Pre-feasibility Study Cost Estimating IT Rail Tunnel - South D&B Approach Finishes

**Tunnel Structural Finishes** 

Page 2 of 2

**Date:** June 07, 2004 **Calculation by:** A.White

## **Quantity Take-off**

Concrete					Concrete	Rebar
Element	Nr.	L(m)	b(m)	d(m)	Qty(m3)	Qty(m3)
1	1	2100	0.3	6.9	4347	521.6
2	1	2100	1.5	0.3	945	113.4
3	1	2100	1.5	0.3	945	113.4
4	1	2100	5.5	1.0	11550	1386.0
					17787 m3	2134 t

#### Formwork/falsework

Element	Nr.	L(m)	d(m)	Faces	Area(m2)	
1	1	2100	6.9	2	28980	
2	1	2100	1.5	1	3150	
3	1	2100	1.5	1	3150	
4	1	2100	0	0	0	
					35280	_ m2

#### **Rates**

Concrete	m3	190
Formwork	m2	140
Reinforcement	t	1600

#### Costs

Concrete	m3	17787 m3	at	190	=	3,379,530
Formwork	m2	35280 m2	at	140	=	4,939,200
Reinforcement	t	2134 t	at	1600	=	3,415,104
				\$		11,733,834



# Newfoundland Fixed Link Pre-feasibility - Immersed Tube Railway Tunnel - Cost Summary

ITEM	UNIT	MAIN TUNNEL
MOBILIZATION & DEMOBILIZATION	LS	43,756,161
FABRICATION & DEMOBILIZATION	LS	52,309,783
TUNNEL ELEMENT FABRICATION	LS	576,906,382
TUNNEL ELEMENT FINISHES	LS	49,530,184
MARINE DREDGE & BACKFILL	LS	584,140,179
UNIT TRANSPORT, PLACEMENT & CLOSURE	LS	247,961,957
NORTH TBM TUNNEL	LS	110,073,842
SOUTH D&B TUNNEL	LS	35,130,365
SOUTH DAB TONNEL SOUTH APPROACH STRUCTURE	LS	6,061,178
NORTH APPROACH STRUCTURES	LS	3,531,204
RAIL TRACK	LS	13,398,500
TUNNEL DRAINAGE	LS	7,820,000
UTILITY DIVERSIONS	LS	1,000,000
MONITORING	LS	1,000,000
MONITORING	LS	1,000,000
SUBTOTAL CIVIL		\$1,732,619,735
SUBTUTAL CIVIL		\$1,732,615,733
CIVIL CONTINGENCIES	<del>                                     </del>	
CIVIL CONTINGENCIES		
CONTINCENCY	400/	\$693,047,894
CONTINGENCY	40%	\$U\$3,U47,U\$4
TOTAL CIVIL		\$2,425,667,628
TOTAL CIVIL		\$2,423,007,020
M&E DOL	LINC STOCK	RAIL HARDWARE AND FINISHING WORK
		\$48,000,000
ROLLING STOCK, TERMINALS, OCS, ETC VENTILATION EQUIPMENT	LS LS	\$3,000,000
VENTILATION EQUIPMENT VENTILATION SHAFTS AND BUILDINGS x 2	LS	\$5,000,000
		\$2,000,000
FIRE SUPPRESSION SYSTEM CONTROL CENTRE	LS LS	\$2,000,000
SIGNALLING	LS	\$1,000,000
LIGHTING	LS	\$2,000,000
CCTV SYSTEM	LS	\$2,000,000
GAS DETECTION	LS	\$900,000
SUBSTATION, GENERATORS, UPS	LS	\$2,000,000
SUBSTATION, GENERATORS, UFS	LS	\$2,000,000
SUBTOTAL M&E AND FINISHING		\$59,900,000
SOBTOTAL MIGE AND FINISHING		\$35,500,000
CONTINGENCIES	20%	\$11,980,000
CONTINGENCIES	20%	\$11,300,000
TOTAL M&E AND FINISHING		\$71,880,000
TOTAL MICE AND FINISHING		Ψ11,000,000
TOTAL CIVIL, M&E AND FINISHING		\$2,497,547,628
TOTAL CIVIL, MIGE AND FINISHING		\$2,437,347,020
ALLOWANCES		
ALLOWANCES	1	
CONTRACTOR OH	15%	\$374,632,144
CONTRACTOR OF	15%	\$374,632,144
OCH TRACTOR FROM	1 3 70	ΨΟΙΤ <sub>1</sub> ,002,144
CONSTRUCTION TOTAL	<del> </del>	\$3,247,000,000
CONSTRUCTION TOTAL	PRF-CONST	TRUCTION AND SUPERVISION
FEASIBILITY STUDY	LS	\$11,000,000
ENVIRONMENTAL ASSESSMENT	LS	\$4,000,000
DESIGN	5%	\$1,000,000
CONSTRUCTION MANAGEMENT	10%	\$162,350,000
	2%	\$524,700,000
OWNERS COSTS	270	\$04,340,000
DDE CONSTRUCTION TOTAL	-	\$555 000 000
PRE-CONSTRUCTION TOTAL	1	\$566,990,000
CRAND TOTAL	-	\$2 913 000 000
GRAND TOTAL	1	\$3,813,990,000



# Strait of Belle Isle Crossing Preliminary Immersed Tube Tunnel Cost Estimate - Rail Tunnel

Page Total \$468,308,432

ltem	Unit	Quantity	Rate	Total
General Details		-		
Tunnel Length Tunnel Element Length	18,000 150	metres metres	No. Elements =	120
1 Tunnel Element Fabrication				
Miscellaneous				
Mobilisation/demobilisation @ 3% of subtotal structure cost	ls	1	\$32,204,534.54	\$32,204,535
Fabrication facility lease (2 facilities assumed @ 5.5 yrs each)	year	11	\$3,500,000.00	\$38,500,000
Concrete				
Structural grade 4,000 psi placed by pump - slab on grade	$m^3$	165,150	\$157.32	\$25,981,398
Structural grade 4,000 psi placed by pump - elevated slab	$m^3$	135,270	\$169.62	\$22,944,497
Structural grade 4,000 psi placed by pump - walls	$m^3$	251,100	\$175.31	\$44,020,341
External Protection Layer, 2,500 psi, placed by pump	$m^3$	22,410	\$153.34	\$3,436,349
Keyed control joints transverse (at 20m centres approx)	$m^2$	32,310	\$13.25	\$428,108
Keyed control joints longitudinal (2 total at base/wall junction)	m	36,000	\$13.25	\$477,000
Curing, sprayed membrane, internal surfaces only	m	505,800	\$1.32	\$667,656
Formwork				
Walls, multiple use forms	$m^2$	626,400	\$78.92	\$49,435,488
Elevated Slab, multiple use forms	$m^2$	113,400	\$81.48	\$9,239,832
Reinforcement: grade 60 high yield				
Wall & Slab reinforcing, 130 kg/m <sup>3</sup>	tonnes	71,698	\$1,501.87	\$107,680,475
Bending, cutting & splicing	tonnes	71,698	\$270.44	\$19,389,899
Waterproofing Membrane				
Steel skin plate, A36, 8 mm thick	tonnes	30,436	\$3,132.11	\$95,328,117
Shear connectors, 150 mm x 12 mm, including stud welding	each	2,592,000	\$0.10	\$259,200
Automated Welding	m	309,240	\$14.86	\$4,595,306
Tunnel Joints				
Structural Steel End Frames (2/element)				
Embedded steel beams, 180 kg/m	tonnes	1,542	\$2,709.04	\$4,177,340
Front plates, 20 mm thick	tonnes	677	\$3,132.11	\$2,119,812
Gina fabrication, installation	each	120	\$18,524.00	\$2,222,880
Omega fabrication, installation & testing	each	120	\$23,335.00	\$2,800,200
Joint concrete, shear keys, cover plates etc.	each	120	\$20,000.00	\$2,400,000
	30.0	0	T,	<del>-,,,,</del>



# Strait of Belle Isle Crossing Preliminary Immersed Tube Tunnel Cost Estimate - Rail Tunnel

ltem	Unit Quai		Rate	Total	
		Tota	al Brought Forward	\$468,308,432	
Temporary Works Items (Per Element)					
Structural Steel Bulkheads (2/element)					
CO Support Columns, 250 kg/m	tonnes	1,920	\$2,709.04	\$5,201,357	
ON Skin plate, 12 mm thick	tonnes	1,440	\$3,132.11	\$4,510,238	
FE. Shear connectors, 150 mm x 12 mm, including stud welding	1.1E+07	360	\$3,174.03	\$1,142,651	
EN Automated Welding	4000000	120	\$3,174.03	\$380,884	
DE	5% #######	53,880	\$14.86	\$800,657	
CO 1	10% #######	53,880	\$40.06	\$2,158,433	
OV	2% #######				
	tonnes	600	\$3,132.11	\$1,879,266	
PRE-CONSTRUCTION TOTAL	#######				
	tonnes	2,640	\$2,709.04	\$7,151,866	
GRAND TOTAL	#######	42,768	\$60.40	\$2,583,187	
Membrane liner	m <sup>2</sup>	42,768	\$27.84	\$1,190,661	
2 Tunnel Transport & Placement					
Element Transport: tug rental etc.	each	120	\$500,000.00	\$60,000,000	
Element placement: barge/pontoons, divers, survey etc.	each	120	\$1,000,000.00	\$120,000,000	
Tunnel Closure					
Underwater joint completion	each	1	\$2,500,000.00	\$2,500,000	
3 Internal Structural & Civil Finish Works					
Ballast					
Track ballast concrete, 2,500 psi, placed by chute	m3	54,000	\$140.06	\$7,563,240	
Track ballast reinforcement: welded wire fabric 6 x 6 x #4, 2.8kg/m <sup>2</sup>	$m^2$	81,000	\$9.36	\$758,160	
Deduct in excess of 4.5 tonnes	tonne	222	-\$41.01	-\$9,104	
Emergency corridor sand/cement mix for HVDC cables	m3	20,250	\$140.06	\$2,836,215	
Precast Divider for Emergency Egress Corridor					
Panel fabrication, 8" thick, incuding reinformcement & lifting points	$m^2$	103,500	\$196.98	\$20,387,430	
Panel setting, based upon max panel weight of 6 tons.	each	9,000	\$285.70	\$2,571,300	
Seal and caulk panels	m	36,000	\$5.48	\$197,280	
Sprayed fireproofing for precast panels	$m^2$	103,500	\$20.77	\$2,149,695	
			Page Total	\$714,261,847	



# Strait of Belle Isle Crossing

# Preliminary Immersed Tube Tunnel Cost Estimate - Rail Tunnel

Ite	em	Unit	Quantity	Rate	Total
			Tota	l Brought Forward	\$714,261,847
4 Ma	arine Operation				
Dr	redging				
Мс	obilization/Demobilzation per season, 6 seasons, 2 vessels	each	24	\$150,000.00	\$3,600,000
Sta	age 1 bulk dredging of material	m3	4,028,049	\$84.00	\$338,356,116
Sta	age 2 fine tolerance dredging & additional trench cleaning	m3	604,207	\$43.00	\$25,980,901
Fo	oundation and Backfill				
Sc	reeded gravel foundation	m3	157,275	\$35.00	\$5,504,625
Se	elected locking fill	m3	377,496	\$35.00	\$13,212,360
Ва	ackfill	m3	550,368	\$35.00	\$19,262,880
Ro	ock armor protection	m3	470,790	\$51.00	\$24,010,290
Su	ubtotal Structure Cost				\$1,144,189,019
Tu	innel MEP Systems	ls	10 % of structure cost		\$114,418,902
	ail Systems	ls	15 % of structure cost		\$171,628,353
Со	ontingency on Tunnel Costs	ls	30% of subtotal structur	e cost	\$343,256,706
"S	Coft" Costs				
En	ngineers design & construction supervision fee	ls	10% of construction cos	t	\$177,349,298
Es	stimated Construction Cost				\$1,950,842,278
Es	stimated Construction Cost per linear metre				\$108,380

Page 1 of 3

## Newfoundland Fixed Link Pre-feasibility Study Road Connections Cost Estimate Summary

The following is a summary of the costs of road works associated with the project.

1		Road Tunnel Concept	Unit	Quantity	Unit Cost	Total Cost
1A	0.1	Newfoundland Side New Road Construction	km	1.4	\$550,000	\$770,000
	0.1	New Road Construction	KIII	1.4	\$330,000	\$770,000
	0.2	Intersection Construction	allowance	1	\$50,000	\$50,000
	0.3	Marshalling Area	sq meter	36,000	\$45	\$1,620,000
		Sub Total Nfld Side				\$2,440,000
1B		Labrador Side				
	0.1	New Road Construction	km	1	\$600,000	\$600,000
	0.2	Intersection Construction	allowance	1	\$50,000	\$50,000
	0.3	Marshalling Area	sq meter	36,000	\$57	\$2,052,000
		Sub Total Labrador Side				\$2,702,000
2		Rail Tunnel Concept	Unit	Quantity	Unit Cost	Total Cost
2A	0.1	Newfoundland Side New Road Construction	km	1.5	\$550,000	\$825,000
	0.2	Intersection Construction	allowance	1	\$50,000	\$50,000
	0.3	Marshalling Area	sq meter	36,000	\$45	\$1,620,000
		Sub Total Nfld Side				\$2,495,000
2B		Labrador Side				
	0.1	New Road Construction	km	1	\$600,000	\$600,000

# Page 2 of 3

0.2	Intersection Construction	allowance	1	\$50,000	\$50,000
0.3	Marshalling Area	sq meter	36,000	\$57	\$2,052,000
	Sub Total Labrador Side				\$2,702,000

# Page 3 of 3

3	Quebec North Shore					
0.1	New Road Construction	km	350	\$720,000	\$252,000,000	
0.2	Road Upgrading	km	40	\$360,000	\$14,400,000	
0.3	Branch Roads	km	20	\$312,000	\$6,240,000	
0.4	Bridges	ea	9	\$1,200,000	\$10,800,000	
	Sub Total Quebec North Shore Roads				\$283,440,000	
Total Road Costs						
	Road Tunnel				\$288,582,000	
	Rail Tunnel				\$288,637,000	